

CHANGE USER GUIDE



Release 25.9
Last Updated: 17 February 2026

Information in this document is subject to change without notice. Companies, names and data used in examples are fictitious.

Copyright ©2026 by InEight. All rights reserved. No part of this document may be reproduced or transmitted in any form or by any means, electronic or mechanical, for any purpose, without the express permission of InEight.

Microsoft Windows, Internet Explorer and Microsoft Excel are registered trademarks of Microsoft Corporation.

Although InEight Change has undergone extensive testing, InEight makes no warranty or representation, either express or implied, with respect to this software or documentation, its quality, performance, merchantability, or fitness for purpose. As a result, this software and documentation are licensed "as is", and you, the licensee are assuming the entire risk as to its quality and performance. In no event will InEight be liable for direct, indirect, special, incidental or consequential damages arising out of the use or inability to use the software or documentation.

Release 25.9
Last Updated: 17 February 2026

This page intentionally left blank.

CONTENTS

CHAPTER 1 – INEIGHT CHANGE OVERVIEW	16
1.0.1 Change Overview	16
1.0.1.1 Who uses Change?	17
CHAPTER 2 – PROJECT SETUP	19
2.1 Organization settings	20
2.1.1 Customizable Revenue Categories	21
2.1.1.1 Accessing Project Details	23
2.1.1.2 Accessing Organization Level Settings	24
2.2 Configurations	25
2.3 Custom lists	28
2.4 Pricing configuration	29
2.5 ID customization	29
2.6 Task type setup	30
2.7 Workflow assignments	30
Add a workflow assignment threshold	31
Add a budget move approval workflow	32
2.8 Change templates	32
2.8.0.1	33
2.9 Templates subtab	33
2.9.1 Download a sample template	33
2.9.2 Creating a change order template	33
2.10 Template contact tags	34
2.11 Maintain field formatting	35
2.12 DocuSign tags	35
2.13 Template types	35
2.14 Template language	36
2.15 Collection tables	36
Add a collection table to a template	37
2.16 Tips for using template tags	37
2.16.0.1 Tips for using template tags	37
General tag information	37
Collection table tags	38
DocuSign tags	38

Microsoft Word documents	38
Microsoft Excel documents	38
2.17 Build your template	39
2.17.1 Cost item pricing table grouping	42
2.17.2 Template versions	43
Build a Change Template	44
2.18 Template settings subtab	50
2.19 Change custom labels	52
2.20 Change Project Settings	53
Open Project Settings	55
2.20.1 IDF Response Codes	58
2.20.2 Notifications	58
2.20.2.1 Written Notification Time Requirement	58
2.20.2.2 Notify Scheduler of Issues	59
2.20.2.3 Notify Assigned To Persons	60
2.20.2.4 Notify controller of adjustments	61
2.20.3 Workflow	61
2.20.3.5 New issue approval setup	62
Add a new issue approval workflow	62
2.20.4 PCO and CCO approvals	63
2.20.4.6 Group workflows	63
Create group workflows	64
2.20.4.7 Change order approval setup	64
Add a workflow assignment	64
Document approval setup	66
2.20.5 Overview - CCO execution setup	67
2.21 Configurations	68
2.22 ID Customization	68
2.22.1 ID customization	68
2.23 Pricing markup	69
2.24 Allowance category	70
2.25 Dependent cost items	72
2.25.1 Allow users to edit adjusted cost	72
2.26 Decimal precision	73
2.27 Message configuration	73
2.28 Responsible party	74
2.29 Construction area	74
2.30 Custom lists	75

2.31 eSign setup	76
2.32 Change templates	77
2.33 DocuSign setup	78
2.33.1 DocuSign Advanced Options	78
2.34 Change custom labels	78
2.35 Permissions	79
2.35.1 Supporting documents permissions	79
CHAPTER 3 – GENERAL NAVIGATION	81
3.1 Page Navigation	82
3.1.1 Change Tools and Navigation	86
3.1.1.1 Change Toolbar	86
3.1.2 Change Register tabs	87
3.2 Column and Row Management	88
3.2.1 Expand Columns	88
3.2.2 Move Columns	89
Move Columns	89
3.2.3 Sort Columns	90
Sort Columns	90
Filter Columns	91
3.2.4 Manage Row density	92
3.3 Enhanced column management	92
CHAPTER 4 – ISSUES	95
4.1 InEight Change Workflow	96
4.2 Issue Creation and Setup	96
4.2.1 Issue Creation	96
Create a new issue	96
4.2.2 Issue Header	98
4.2.2.1 Cost, markup, and markup percent pricing breakdown	98
4.2.2.2 Status information	98
4.2.2.3 Issue status	99
4.2.2.4 Pricing status	100
4.2.2.5 Proposal status	101
4.2.3 Delete an issue	101
4.3 Details tab	102
4.3.0.1 Issue details	102
4.3.0.2 Issue description	103
Associate a vendor to an issue	104
Add a vendor to cost item pricing	106

Push a WBS code to cost item pricing	107
4.3.0.3 Additional details	108
4.3.0.4 Request for Information	112
Create a historical weather record for an issue	114
4.3.0.5 Project values	118
4.3.0.6 Custom fields	119
4.4 Review or Approve an issue	119
Review or approve an issue	119
4.5 Change toolbar	120
4.5.0.1 Project contract summary	120
4.5.1 Add notes	121
4.5.1.2 Allowance Category Summary	123
4.6 Current value	124
4.7 Supporting documents	125
Upload a document to Document	127
4.7.1 Show supporting documents in generated documents	129
4.8 View a supporting document	129
4.9 Create an RFI form in InEight Document	130
Create an RFI Form in InEight Document	130
4.10 Create Mail in InEight Document	134
Create mail	135
4.11 Package supporting documents	137
Package supporting documents	137
4.12 Main and subordinate issues	139
Convert a standard issue into a main issue with a subordinate	139
Add a subordinate to a main issue	141
Make an existing issue into a subordinate of a main issue	143
4.13 Issue Import	144
4.13.1 Import the template	144
Import issues	145
4.13.2 Import issues through an API	147
4.13.3 Export the template with data	147
4.14 Split Issues	147
Split an Issue	148
Add details to a split issue	150
4.15 Cost item pricing	152
4.16 Pricing tab	152
4.17 Pricing page organization tools	153

4.17.1 Group by column	153
Group cost items by column on the Pricing page	154
4.17.2 Column management	155
4.18 Add a cost item	156
Add an existing cost item	156
Add a new cost item	159
Add an unassigned pricing item	160
4.19 Edit cost items	161
4.19.1 Cost item details	161
4.19.2 Cost categories	162
4.19.3 Resources tab	162
4.20 Edit Plug items	162
4.20.1 Plug items	162
4.21 Edit Detail items	163
4.22 Copy a cost item	165
4.23 Cost item pricing templates	165
4.23.1 Cost item pricing templates	165
Create a cost item pricing template from the register	165
Create a cost item template when adding cost items	167
Add cost items from a template	168
4.23.1.1 Manage templates	168
4.23 Step by Step 1 – Send a copy of a template	170
4.24 Dependent cost items	170
Add an existing dependent cost item	171
Add a new dependent cost item	172
Edit a dependent cost item	173
4.24.1 Edit dependent cost items	174
4.25 Markups	174
Add a percentage-based markup to a cost item	176
Add a value markup to a cost item	177
4.26 Auto calculate cost items	178
Auto calculate cost items	178
4.27 Associate a pricing item to a vendor change order	180
Associate a vendor pricing item to an existing Contract VCO	180
Create a VCO in Contract	181
4.28 Import cost items	182
4.28.1 Import cost items from an Excel spreadsheet	182
Import Plug cost items	184
4.28.2 Import cost items from Estimate	185

Import cost items from Estimate	186
4.29 Cost item sync	186
4.30 Pricing summary	188
4.30.1	190
4.31 Direct cost total	190
4.31.1 Direct cost total	190
4.32 Vendor total	191
4.33 Edit vendor information	193
4.34 Vendor change orders	195
Associate a vendor pricing item to an existing Contract VCO	195
Create a VCO in Contract	197
4.35 Indirect cost subtotal	197
4.36 Markups	197
4.37 Deductions	199
4.38 Markup calculation levels	199
4.39 Budget moves	200
4.39.1 Initiate a budget move	200
4.39.2 Budget move workflow	202
4.39.3 Revise a budget move	202
4.40 Task creation in InEight Compliance	202
4.40.1 Compliance integration	203
4.40.1.1 Permissions	203
4.40.1.2 Compliance task template	203
4.40.2 Create a task	203
Create a task	204
4.40.3 Task log	204
CHAPTER 5 – CHANGE ORDERS	207
5.1 InEight Contract Workflow - Change Orders	208
5.2 Potential Change Order (PCO)	208
5.2.1 Overview	208
5.2.2 Potential Change Order (PCO) Creation	209
Create a potential change order (PCO)	209
5.2.2.1 Assign a PCO from Issue Record	212
5.2.3 PCO Header	212
5.3 PCO Details tab	213
5.3.0.1 eSign	215
5.3.1 Additional details	216
5.3.1.2 Schedule impact	216

5.3.1.3 Correspondence	216
5.3.1.4 Request for information	217
5.3.1.5 Tasks	217
5.3.1.6 Project values	217
5.3.1.7 Custom fields	217
5.4 PCO Pricing tab	217
5.4.1 Pricing tab	218
5.4.1.1 Pricing Summary tab	218
5.4.1.2 Update PCO values with issue values	218
5.5 PCO log	220
5.5.0.1 Aging days	221
5.6 Client Change Order (CCO) Generation	221
5.6.1 Overview	221
5.6.2 Client Change Order (CCO) Creation	222
Create a Client change order (CCO)	222
5.6.2.1 Convert to CCO from Issue/PCO Record	223
5.6.3 CCO Header	224
5.6.4 CCO Details Tab	224
5.6.4.2 eSign	226
5.6.5 Additional details	227
5.6.5.3 Client change order execution details	227
5.6.5.4 Schedule impact	227
5.6.5.5 Correspondence	228
5.6.5.6 Request for information	228
5.6.5.7 Tasks	228
5.6.5.8 Project values	228
5.6.5.9 Custom fields	228
5.6.6 CCO Pricing Tabs	229
5.6.6.10 Pricing tab	229
5.6.6.11 Pricing Summary tab	229
5.6.7 CCO Log	230
5.7 Client Change Order (CCO) Execution	231
5.7.1 Client Change Order Workflow Settings	232
5.7.2 Executed CCO status	233
5.7.3 Vendor change order creation	234
Execute a CCO	234
5.8 Change writer	236
5.9 Standard and bulk template processing	236
5.10 Generate a change document	237

Generate a standard change document	237
Generate a change document using bulk template processing	240
5.11 Supporting documents	244
5.11.0.1 Show supporting documents in generated documents	245
5.12 View a supporting document	246
5.13 Send Change documents for eSignature via DocuSign	247
Send a document for eSignature	247
Edit a sent document	250
5.14 DocuSign certificate of completion	251
5.15 Workflow Assignments	252
5.15.1 PCO and CCO workflows	252
Set up a PCO or CCO approval workflow	252
Start the approval workflow	253
5.15.2 Document approval workflows	254
Set up a document approval workflow	255
Start the document approval workflow	256
5.16 Audit Log	256

STEP-BY-STEP PROCEDURES

Add a workflow assignment threshold	31
Add a budget move approval workflow	32
Add a collection table to a template	37
Build a Change Template	44
Open Project Settings	55
Add a new issue approval workflow	62
Create group workflows	64
Add a workflow assignment	64
Move Columns	89
Sort Columns	90
Filter Columns	91
Create a new issue	96
Associate a vendor to an issue	104
Add a vendor to cost item pricing	106
Push a WBS code to cost item pricing	107
Create a historical weather record for an issue	114
Review or approve an issue	119
Upload a document to Document	127
Create an RFI Form in InEight Document	130
Create mail	135
Package supporting documents	137
Convert a standard issue into a main issue with a subordinate	139
Add a subordinate to a main issue	141
Make an existing issue into a subordinate of a main issue	143
Import issues	145
Split an Issue	148
Add details to a split issue	150
Group cost items by column on the Pricing page	154

Add an existing cost item	156
Add a new cost item	159
Add an unassigned pricing item	160
Create a cost item pricing template from the register	165
Create a cost item template when adding cost items	167
Add cost items from a template	168
4.23 Step by Step 1 – Send a copy of a template	170
Add an existing dependent cost item	171
Add a new dependent cost item	172
Edit a dependent cost item	173
Add a percentage-based markup to a cost item	176
Add a value markup to a cost item	177
Auto calculate cost items	178
Associate a vendor pricing item to an existing Contract VCO	180
Create a VCO in Contract	181
Import Plug cost items	184
Import cost items from Estimate	186
Associate a vendor pricing item to an existing Contract VCO	195
Create a VCO in Contract	197
Create a task	204
Create a potential change order (PCO)	209
Create a Client change order (CCO)	222
Execute a CCO	234
Generate a standard change document	237
Generate a change document using bulk template processing	240
Send a document for eSignature	247
Edit a sent document	250
Set up a PCO or CCO approval workflow	252
Start the approval workflow	253
Set up a document approval workflow	255

Start the document approval workflow	256
--	-----


CHAPTER 1 – INEIGHT CHANGE OVERVIEW

Change is where you can manage the living history of your changes, their associated costs, and convert them into change orders, as necessary, when working with both the owner and subcontractors. As issues arise, project engineers record and submit issues, get them approved through the client and execute change orders.

The concept of project related changes is one of the most difficult entities to track on a project. Most projects run into many kinds of issues during the contract lifecycle. Those projects that don't utilize InEight Change will usually track project progress in an Excel sheet, or alternate software.

The Change tool provides a consistent, thorough way to manage your changes. It replaces your change tracking spreadsheet with a thorough and flexible change order management process.


The Change module follows the following workflow:



1.0.1 Change Overview

When the Change workflow is activated in Project Settings, you will see that the Change register contains rows and columns like a spreadsheet and consists of tabs that further break down the different stages on an issue.

Change User Guide




The screenshot shows a table with columns: Issue ID, Issue name, Field condition, Issue start date, Issue status, Ball in court, Value type, Assigned to, Client CO ID, Ball in co..., PCO ID, Written no..., and Date. There are four rows of data, each representing an issue with a unique ID, name, and status. The interface includes a header with tabs for PENDING ISSUES, ISSUE LOG, POTENTIAL CO LOG, CLIENT CO LOG, ACTION ITEMS, AUDIT LOG, and CHANGE TEMPLATES. A toolbar at the top right includes buttons for Change issue status, search, and other actions.

Issue ID	Issue name	Field condition	Issue start date	Issue status	Ball in court	Value type	Assigned to	Client CO ID	Ball in co...	PCO ID	Written no...	Date
35	Test June 17 issue	paul trippi	06/17/2019	In Review							-1	
34	PT - Bearing Pads	paul trippi	06/17/2019	In Review							-1	
33	PT - Bearing Pads	paul trippi	06/17/2019	In Review							-1	
32	PT- Bearing Pads	paul trippi	06/17/2019	In Review	Client						-1	

The principal focus within Change is the concept of creating, approving and tracking of issues and change orders. As new issues come up within the contract lifecycle, Change is where you can collect your Issues, convert them into Potential Change Orders (PCOs) and Client Change Orders (CCOs).

Each issue has the capacity to track the information necessary for any legal action or related documentation. Some of the information you can capture to track an issue are:

- Issue name and full description
- When the issue started
- The source/cause of the issue (a field condition, client instruction, etc.)
- The scope of the issue (out of scope, in scope, contingency, etc.)
- Confirmation of notifying the client



The screenshot shows a form for creating a new issue. It includes sections for Current value (\$6.80), Actions, DETAILS, PRICING & PROPOSAL, and SUPPORTING DOCUMENTS. The DETAILS section contains fields for Issue description, Issue name (New issue), Issue start date (02/04/2020), Description (1000 characters), Source/cause (Source/cause 1), Change condition (None), Scope (None), and Allowance category (Allowance). The PRICING & PROPOSAL section includes fields for Delay days due to issue, Ball in court (None), Issue status (In Review), Pricing status (None), and Proposal status (None). The SUPPORTING DOCUMENTS section has tabs for Issue description, Field information, Schedule impact, Client notification, and Design information. Buttons for Cancel and Save are at the bottom right.

1.0.1.1 Who uses Change?

The primary users of Change differ from the typical roles that use the rest of InEight cloud platform, namely Contract Managers and Contract Administrators. In other words, the main users of Change are

typically the same as Contract. These are employees focused on contract and change management as their primary role.


CHAPTER 2 – PROJECT SETUP

To manage issues and change orders successfully, the correct Change settings must be set up before project initiation. Some settings differ between the organization and project levels.

2.1 ORGANIZATION SETTINGS

Prior to initiation, the organization and project settings are significant to successfully manage a project in Change.

Organization settings are distinct from the project settings since they are defined by the administrative level in your organization. The image below shows you how to access organization settings from the main menu.




2.1.1 Customizable Revenue Categories

Revenue categories and probability percentages are customizable within each organization through master data by manual entry or API. This customization has specific permissions around edits.


The Revenue category and Probability percentage in the Issue, PCO and CCO Logs pull data dynamically from master data.

Revenue categories are located in your organization's Master data libraries. From the Main menu, select **Master data libraries** and then **Revenue categories**.

When you land on the organization settings page, select **Change** from the left navigation. This opens the Change organization settings.



On the Revenue categories page, you can add new revenue categories or edit existing ones as well as, set revenue categories to be Active or Inactive.




	Revenue category name	Revenue change status name	Probability percentage	State	
<input type="checkbox"/>	Overruns updated	Overruns updated		0	Inactive
<input type="checkbox"/>	Extra Work, Force	Unexecuted Changes		0	Inactive
<input type="checkbox"/>	Bonus	Unexecuted Changes		0	Inactive
<input type="checkbox"/>	Highly Probable - Clear Entitl...	Unexecuted Changes		0	Active
<input type="checkbox"/>	Highly Probable - Client Ackno...	Unexecuted Changes		0	Active
<input type="checkbox"/>	Administratively Imminent	Unexecuted Changes		0	Active

Use permissions to control who can view, add, or edit revenue categories.

By default, the Executed change order revenue category is always present. This is the default status in all logs when an issue, PCO, or CCO is executed.

An example would be to tag a Potential entitlement, which is a \$100,000 change order. Organizations would set the categories and probabilities percentages based on their organization's business rules. Customizable per tenant and at the Change level, you can assign the revenue category to the PCO, CCO, or issue you want.



English				Spanish	
	Revenue category name	Revenue change status name	Probability percentage	State	
<input type="checkbox"/>	Potential Entitlement	Unexecuted		50	Active
<input type="checkbox"/>	Highly Probable	Unexecuted		80	Active
<input type="checkbox"/>	Executed	Executed		100	Active

	Revenue category name	Revenue change status name
Potential Entitlement		Unexecuted
Highly Probable		Unexecuted
ES_Executed Change Order_ES		ES_Executed_ES

These categories are used by InEight Control for revenue projections. These are required in Change and Control. Association is done between the probability percentage, revenue category and revenue change status.

Column options

Available columns

Selected columns

Search... q

ISSUE CUSTOM FIELD 3
ISSUE CUSTOM FIELD 4
Number of subcontractors
Plan/Detail sheet number
Probability percentage
Proposal checklist
Revenue category
Revenue change status
Schedule impact
Self perform subtotal
Source/cause
Specification section number
Sub checklist
Subcontractors
Temporary vendors
TBC

Search... q

Issue start date
Issue status
Assigned to
Ball in court
Written notice days remaining
Ball in court person
Date client notified
Value type
Current value
Pricing status
Date price to client
Proposal status
Scope
Supporting documents
Notes

Cancel Save

Probability perce... ... Revenue c... ...

None ▲

None

Highly Probable ▼

Highly Probable

Extra Work, For...

Overruns, Und...

After selections are done, such as Highly Probable, the Probability percentage pulls from the Master data. It is then pushed to Control.


2.1.1.1 Accessing Project Details

Project details can be accessed at the organization level in Settings > **Edit project**. Project details provides all the information for the project.

The screenshot shows the 'Edit project' page with the 'Project details' section highlighted. The page includes fields for Project ID (110140), External project ID (110140), Name (Procurement and Project Support - Krupski 2017), Status (Active), Organization (S100000 - PKS Incs : S100000 - PKS Incs : SB6000 - Home Office : SC6001 - Home Office Shared Services : S...), Project start date (05/26/2017), Project end date (12/28/2017), and Notes (kjdsksd;la). There is also a placeholder for an 'Add project image' with a 150x150 px recommended size.

2.1.1.2 Accessing Organization Level Settings

After you open the organization settings page, select the **Change** icon from the left navigation. You can use the expansion arrows to see the application names. This opens the Change organization settings.



2.2 CONFIGURATIONS


Change has organization settings to further configure the product for your organization. To see this setting, go to organization settings, then select Change > **Configurations**. The settings that are configurable at both the organization and project levels are:

- ID customization
- Change condition
- Pricing configuration
- Custom lists
- General status
- Pricing status
- Proposal status
- Responsible party
- Scope
- Source/cause
- Task type setup

You can manage and customize configurations according to your organization. You can also add to the list. Each configuration set up at the organization level flows down to the project level where further customization is available.

For Scope, status is configurable at the organization level. This lets you add and maintain scope definitions that are unique to your organization. Because scopes are custom, Change does not validate the scope when closing an issue.

These changes will be reflected in the project as drop-down lists.



DETAILS PRICING & PROPOSAL SUPPORT DOCUMENTS

Issue description Field information Schedule impact Client notifications

Issue description

Created by chandrakala c on 09/30/2019

* Issue name *Issue start date

abc_123 10/15/2019

Hint: Date of the start of impact

Description 1000

Source/cause Change condition

None None


Hint: Select what prompted the so... *Hint: Select the condition of the c...*

Scope Assigned to

None


Hint: Type employee name

Pricing and Proposal status list items for issues, PCOs and CCOs. When you select the Pricing status type on the left side of Pricing or Proposal status pages, you can add Change condition and Source or cause list items only for issues.



2.3 CUSTOM LISTS

The Custom list setting (organization Settings > Configurations > **Custom lists**) lets your organization configure default lists that automatically populate custom drop-down list fields for projects. You can configure two custom lists each for issues, PCOs, and CCOs.



You can customize the name of the fields using the Custom labels settings. Use the Active toggle to indicate whether the list item is active. When the value is active it is available in lists. If it is inactive, the value is not available for use in future issues, PCOs, and CCOs but is maintained where it was previously used.


After a custom list has been used you cannot delete it from the organization settings unless you delete it from all items. You also can deactivate a custom list, so it is not available for future use.

Custom lists set at the organization level are applied to the project level and default to *Active*.

2.4 PRICING CONFIGURATION

Use the Pricing configuration page (organization Settings > Configurations > **Pricing configuration**) to restrict the ability to modify the executed contract amount during the execution of a client change order.


When you disable Allow users to edit the Executed change order amount upon execution toggle at the organization level, the setting at the project level is also disabled. When you enable the setting at the organization level, you can enable or disable the setting for each project.



2.5 ID CUSTOMIZATION

Change lets you customize your PCO and CCO numbering schemes to ensure consistent numbering. Configuration settings at the organization and project levels let you specify whether to generate PCO and CCO IDs sequentially, and if so, a prefix and starting number.

You can configure customized IDs using the ID customization configuration list (Organization > Settings > Configurations > **ID customization**). You can set up numbering for PCOs and CCOs separately.




The Generate PCO/CCO IDs sequentially settings indicate whether Change generates numbers sequentially. When set to *No*, you enter any number as the ID when you create the PCO or CCO. When set to *Yes*, you can specify a prefix and a starting number that Change uses when it automatically generates the PCO or CCO ID.

The Prefix and Starting number fields are enabled only when the Generate Potential change order/Client change order IDs sequentially toggle is set to *Yes*. The prefix on the PCO or CCO is added to the ID in the exact way it is entered in the field. If you want a space between the prefix and the starting number, you must enter it in Prefix field. You can edit the starting number until a PCO or CCO has been created. After that, the field is disabled.

The Allow projects to edit settings check box specifies whether you can override the settings at the project level. When checked, the organization-level settings are the default at the project level, but the project administrator has the ability to override the settings. When the check box is checked, the numbering scheme is enforced at the project level. After you establish a starting number, and the first PCO or CCO is created, you cannot change the starting number at the project level.

2.6 TASK TYPE SETUP

Use the Task type set up page (organization Settings > Configurations > **Task type setup**) to select the InEight Compliance registered task template to use when creating tasks in an issue, PCO, or CCO. The template is used for all projects in the organization.



Refer to the [Compliance topics](#) for information about setting up templates.

2.7 WORKFLOW ASSIGNMENTS

The Workflow Assignments tab lets you set up approval processes for budget moves, potential change orders, client change orders, and documents. The settings include defining the number of steps in your approval processes and making assignments of who approves each step.

You can set up dollar-value thresholds based on contract type at an organization level for PCOs or CCOs. The organization has an approval matrix where any dollar amount over the threshold set must be approved. Approval for budget moves and document approvals have ordered steps assigned to roles.

Add a workflow assignment threshold

Summary: Add a workflow assignment threshold to set the amount at which a PCO or CCO must be approved.

Considerations: The workflow steps set at the organization level are performed after those set at the PCO/CCO and project levels. However, if the value of the PCO or CCO is below the organization level thresholds, the workflow thresholds set at the organization level will not show in the Workflow Assignments.

Thresholds are absolute values, so a pricing change in either direction starts the approval workflow.

Quick steps:

1. Go to the Workflow Assignments tab.
2. Select the **PCO approval setup** or **CCO approval setup** tab.
3. Click the **Add approval** icon.
4. In the Add approval slide-out panel, enter the threshold amount and approval step title.
5. Indicate whether projects must select specific users based on assigned roles. When the check box is selected, the project must add a user who has that role to that step before workflow can be started. If the check box is not selected, all users in that role are eligible for approval.
6. Enter the roles for the Assign approval roles.
7. Click **Add** to complete.
8. If you want the approval workflow for the threshold to have additional steps, click **Add another step**. To change the position of a step, select it, and then use the up and down arrows to the right of the steps to move up or down.

Organization-level thresholds cascade to every PCO or CCO. You can add additional steps at the project level, which are performed before the steps set at the organization level. You can add additional approval steps at the individual PCO or CCO level, which, regardless of the value of the PCO or CCO, are always first.

Add a budget move approval workflow

Summary: Add a budget move approval workflow when you want the budget move to be approved before being sent as a draft to InEight Control.

Considerations: When there is a workflow in place, the budget move is not sent to Control until it has been approved in Change.

Quick steps:

1. From the organization Settings > **Workflow assignments tab**, select the **Budget move approval setup** subtab.
2. Click the **Add approval** icon. The Add approval slide-out panel opens.
3. Enter the step title and the approver roles.
4. Indicate whether projects must select specific users based on assigned roles. When the check box is selected, the project must add a user who has that role to that step before workflow can be started. If the check box is not selected, all users in that role are eligible for approval.
5. Click **Add**.
6. Repeat steps 2-5 for each step you want to add.
7. Click **Save**.

What's next: You can add steps at the project level.

2.8 CHANGE TEMPLATES

Much like Contract writer, Change writer is a customized contract document writer intended for a vendor or subcontractor to eventually agree to, accept, or reject.

As an issue turns into a PCO, and a PCO to the client might turn into a CCO, the document associated with the CCO must be signed by all parties for legal reasons.

Change writer can create project specific change documents such as issue summary documents, PCOs or CCOs through Microsoft Word or Microsoft Excel templates and tags. This helps you create customized client change order documents. If there is a need to create a customized change contract for a client, Change provides Change writer to aid in the area. This is a legal document that is intended to be signed by all parties and stakeholders.

2.8.0.1

2.9 TEMPLATES SUBTAB


The templates subtab shows the templates register and gives you the tools you need to start building templates.

You can download a sample template that will help you get started with your template. You can also get a list of general tags and collection table tags to be used in the template. After you have opened the list, you can export the tags to a Microsoft Excel spreadsheet.

2.9.1 Download a sample template

You can download a sample template in Microsoft Word and Microsoft Excel formats. The samples show how a contract could look in either format. This feature is available at both the organization and project levels.

To download a sample template, click the **Download sample template** icon on the template register, and then select either **Download Word template** or **Download Excel template**.



Template	Description	Status	Template type	Template file	Created date	Created by	Modified date	Modified by	Template language	Attributes
New.CCO	New CCO	Published	Client change order	N-CCO.docx	06/15/2021		06/15/2021		NB-NB	
New.PCO	New PCO	Published	Potential change order	N-PCO.docx	06/15/2021		06/15/2021		NB-NB	
New	New	Published	Issue	N-Issue.docx	06/15/2021		06/15/2021		NB-NB	
Org to project Template	Org to project Template	Published	Issue	Norway-localizationtags_23...	06/11/2021		06/11/2021		EN	

2.9.2 Creating a change order template

To create a template for your change order documentation, you will use predefined change writer tags to auto-fill your change document with the information from your contract. From the Add change template record, you can select the **View available tags** icon and choose General tags to open the list of general tags that can be used in the body of the template only. Select **Collection table tags** to see the list of tags that can be used in collection tables. General tags cannot be used in a collection table. After you have opened the list, you can export the tags to an Excel spreadsheet.

The Location source shows the name of the page that Change pulls the information from when building the template. You can see an example of how this information might look in the change order in the Example column. The Applicable for column shows the type of template for which the tags are valid.

General tags				
Utilize below general tags to build change templates. Tags in the template would be replaced with the corresponding tag values, while generating change document.				
Tag name	Location source	Description	Example	Applicable for
<<Project ID>>	Project details	The project number	123456	All templates
<<Project name>>	Project details	The name of the project	Metro Power Station	All templates
<<Project address1>>	Project details	The address of the project	1700 Northwest Street	All templates
<<Project address2>>	Project details	The address of the project	Unit 3	All templates
<<Project city>>	Project details	The city of the project	Scottsdale	All templates
<<Project country or r...	Project details	The country of the project	US	All templates
<<Project postal code...>>	Project details	The postal or zip code of the project	85201	All templates
<<Project state>>	Project details	The state of the project	Arizona	All templates
<<Contract number>>	Project details	The projects contract number	CA 139481029	All templates
<<Project contract dat...	Project details	The date of the Project contract	17-03-2020	All templates
<<Date project started...>>	Project details	The date the Project started	01-09-2019	All templates
<<Original contract co...	Project details	Date project started + original duration	04-03-2021	All templates

Refer to the instructions on the Instructions tab of the Excel file for information about using tags and building a template.

2.10 TEMPLATE CONTACT TAGS

Template contact tags are general tags that correspond to fields in the project Assigned contacts (project > **Assigned contacts**). Tags let you select contact details to populate information in a generated document. For example, you could select a specific contact name for the greeting in a cover letter or notification letter.

The tags show in the general tags list as <<Template contact: *field*>>, where *field* corresponds to a field in the project contacts. The tags can be used to customize documents when you use standard or bulk template generation. See 5.9 Standard and bulk template processing on page 236 for information about standard and bulk template generation.

When the Change writer detects a template contact tag, it retrieves the information for the selected contact from the project's contacts. When you use the tags with Standard template processing, you can select one contact in the Select contacts step of the Change document wizard. When you use the tags with bulk template processing, you can select up to 10 contacts, and a separate document is generated for each contact.

2.11 MAINTAIN FIELD FORMATTING

Large text box fields, such as Issue description, PCO and CCO description of change, and PCO and CCO contract term fields, contain formatting tools that let you use boldface type, numbered or bulleted lists, and other text formats. To preserve this formatting in Microsoft Word templates, you can insert a Word merge field instead of a tag for the field.

To insert a merge field in a Word template, position the cursor, and then go to Insert > Quick parts > **Field**. From the Field dialog box, select MergeField, and then enter the tag name without the brackets in the Field Properties > **Field name** field (for example, CCO contract term 1). When a document is generated, Word uses the formatting from the field to format the text.

Refer to the Instructions in the Change templates tags spreadsheet for more information about merge tags.

2.12 DOCUSIGN TAGS

DocuSign eSignature tags for recipients let you embed signee information to pull into your organization or project templates. DocuSign tags used in a template are read when sending a document for signature.

The DocuSign tags serve as placeholders for the eSignatures. Change's DocuSign tags also include tags that serve as placeholders for text boxes, check boxes, drop-down lists, and radio buttons that are added by the document sender in the DocuSign Sender view. These tags are available for eSign 1-10 and for each project contact. When you add the tags in the template, you ensure that the corresponding item is consistently placed. For text and drop-down lists, you only place one tag in the template. For check boxes, you place one tag for each option. For radio buttons, a single tag places two buttons in the document. You can add more radio button tags for additional buttons.

When a document with these tags is opened in the DocuSign Sender view, the tags are present, but they do not have values. You can add the values from the Sender view. For example, if the template has three check box tags, when the document is opened in DocuSign, three empty check boxes are shown. You then add the value for each check box in DocuSign.

Refer to the instructions on the Instructions tab of the Excel file for information about DocuSign tags.

2.13 TEMPLATE TYPES

Change templates are classified by the template type. This classification can help you ensure that the template suits your business needs based on the purpose of the template. Change supports the

following template types:

- Client change order
- Potential change order
- Issue

The template type indicates which general tags and collection tags are valid for the template. For example, a client change order template can use the tags that are applicable for client change order templates. Any template can use the tags with the type All templates. The template tags are validated when you attach a template file to the template.

If you have invalid tags, the Template file section of the Details page shows a message that there are validation errors. You must go into the Word or Excel template and fix the errors. You cannot publish the template if there are any errors.

2.14 TEMPLATE LANGUAGE

You can define the language in which the contract template is generated using the Select template language field in the Change template details. Selecting a template language lessens the tags available. For example, if you select Spanish as the template language, you can use only Spanish tags in the template even if the language of your application is English. Upon generation, template and tags are generated in Spanish.

You cannot use tags in multiple languages in a single template. During template validation, the application only searches the tags of the selected language instead of all languages.

2.15 COLLECTION TABLES

You can add multiple items to a vendor, supporting documents, associations, or workflow approvals section of a template by using a collection table. You can create collection tables in Word or Excel that include those items and place them into the template.

A collection table contains collection tags specific to a template type. General tags cannot be used in a collection table. The Change writer searches the information in the Change application and returns the values in the table. Collection tags are specific to the template type. A collection table can have tags for one table type only, but a template can have multiple tables. For example, a Potential Change Order template type can have tables for vendors and supporting documents, but the tables can include only the tags for its table type. The vendors table can have only the tags for the Vendors table type, and the supporting documents table can have only the tags for the Supporting documents table type.

Add a collection table to a template

To add a collection table to a template:

1. Download the collection tags spreadsheet (list) and follow the instructions on the Instructions tab.
2. Open or create a new template in Word or Excel. Keep in mind the template type (issue, potential change order, or client change order).
3. Create a table in the document or spreadsheet.
4. Enter headers, if applicable, and format the table to suit your business needs.
5. Enter a tag in each column. The tag can be from one table type only.
6. Save your document.

What's next: Upload the template to Change. See [Build your template](#) for more information.

Collection tags do not show up on the Review templates page. If you have a template that has only collection tags you see the message No general tags found in this template in the review area. You can see collection tags in the preview. If there is an error you must fix it in the Word or Excel document. If a field is missing, you must go to the contract and fix that item.

2.16 TIPS FOR USING TEMPLATE TAGS

2.16.0.1 Tips for using template tags

Template tags are the building blocks of a Change document. The tags pull information from the corresponding data fields in the issue, PCO, or CCO detail to populate the document, except for Sum of pay items original price and Sum of pay items current price, which pull information from fields in InEight Control. Use the following guidelines when you are adding tags to your template.

Additional instructions can be found in the tags export.

General tag information

- General tags cannot be used in a table.
- Equations are discarded in document generation. No tags in an equation are read.

- Some fields in the application have their own formatting that is applied in the template (for example, a bullet list). The general tags associated with those fields use the application's formatting, and you do not have to enter additional formatting in the template.

Collection table tags

- Only collection table tags can be used in a collection table.
- Tags cannot be read from nested tables, such as a table within a table.
- Tags for the Pricing summary collection table gather the information from the pricing summary page for an issue, PCO, or CCO and places them in the collection table. If a PCO has multiple issues or a CCO has multiple issues or PCOs, the collection table shows each issue or PCO on a separate line. When a markup is applied to multiple issues, each markup shows on a separate line.

DocuSign tags

- Change the color of DocuSign tags to white, otherwise the tags show in the document. The white text matches the background and hides the tag.
- When adding a DocuSign tag to an Excel template, the column or row must be large enough for the entire tag name. When the Excel file is converted to a PDF to send to DocuSign, the system cannot read the tag if the whole tag name was not visible in Excel.

Microsoft Word documents

- Any text formatted in Change on the Details pages are retained in Word documents.
- The pricing summary tags for issue, PCO, and CCO generates all pricing details generate in the Times New Roman font. The tag always generates as a preformatted table.

Microsoft Excel documents

- For large text cells where you can format text, the formatting is converted to plain text.
- Any text formatted in Change on the Details pages are converted to plain text in Excel.
- Only the first sheet in an Excel template is read and tag information inserted. To generate multiple Excel sheets, create multiple Excel files and merge them into a single PDF.
- The Change writer discards text boxes, word art, drawings, equations and formulas inserted into an Excel document.

- Tags cannot be used in calculations.
- The Pricing summary tags are not valid in Excel.

2.17 BUILD YOUR TEMPLATE

After the Excel file opens from the download, you can copy the tags you need into a Word or Excel version of your change order document, inserting them in the header, footer, and body of your change documents. Refer to the Instructions tab of the Excel file for information about using tags and building a template.

	A	B	C	D	E
1	Tag name	Location source	Description	Example	
2	<>Project ID>>	Project details	The project number	123456	
3	<>Project name>>	Project details	The name of the project	Metro Power Station	
4	<>Project address1>>	Project details	The address of the project	1700 Northwest Street	
5	<>Project address2>>	Project details	The address of the project	Unit 3	
6	<>Project city>>	Project details	The city of the project	Scottsdale	
7	<>Project country or region>>	Project details	The country of the project	US	
8	<>Project postal code>>	Project details	The postal or zip code of the project	85201	
9	<>Project state>>	Project details	The state of the project	Arizona	
10	<>Contract number>>	Project details	The projects contract number	CA 139481029	
11	<>Project contract date>>	Project details	The date of the Project contract	17-03-2020	
12	<>Date project started>>	Project details	The date the Project started	01-09-2019	
13	<>Original contract completion date>>	Project details	Date project started + original duration	04-03-2021	
14	<>Original duration>>	Project details	Contract time duration in calendar days	550	
15	<>Original project value>>	Project details	The original value of the Project contract	\$50,00,000.00	
16	<>Sum of all executed CCOs>>	Project contract summary (sigma)	Sum of all executed change orders to date (except dropped)	\$1,00,000.00	
17	<>Current project value>>	Project contract summary (sigma)	The original project contract value + the sum of executed change	\$51,00,000.00	
18	<>CCO value>>	Current CCO	The value of the selected change order	\$59,137.50	
19	<>Revised project value>>	Calculation	Total sum of the current project value + current change order val	\$51,59,137.50	

A sample Word template is provided for you as an existing template record on the Details Template page.

You access this template by either the Organization level settings or Project level settings. Click the **Download sample template** icon, and then select **Download Word template** or **Download Excel template** to access the download sample template in Word or Excel, respectively.

		CONFIGURATIONS	CHANGE TEMPLATES	CHANGE CUSTOM LABELS				
<input type="checkbox"/>	Template	Description	Status	Template type	Template file	Created date	Created by	Modified date
<input type="checkbox"/>			Published	Issue	fulltemp.docx	07/28/2020		07/28/2020
<input type="checkbox"/>			InActive	Issue	fulltemp.docx	07/28/2020		07/28/2020
<input type="checkbox"/>			Published	Issue	MP_preview test.docx	07/22/2020		07/28/2020
<input type="checkbox"/>			Draft	Issue	MP_preview test.docx	07/22/2020		07/22/2020
<input type="checkbox"/>			Published	Issue	English.docx	07/22/2020		07/22/2020
<input type="checkbox"/>			Published	Issue	English.doc	07/17/2020		07/17/2020
<input type="checkbox"/>			Published	Issue	fulltemp.docx	07/17/2020		07/17/2020
<input type="checkbox"/>			Published	Issue	Change Sample Template...	07/17/2020		07/17/2020

Tags must be inserted exactly as they appear in Tag Name. After all tags are inserted into the Change-related Microsoft Word document, save it as a .docx file. Change writer template can be named the same at the Organization level as those in the Project level. Below is an example of a document with the tags inserted. Everything in yellow are the highlighted tags.

Sample Template with Tags

PROJECT: <<Project name>> <<Project address1>> <<Project city>>, <<Project state>> <<Project postal code>>	CHANGE ORDER NUMBER: <<CCO ID>> DATE: <<CCO created date>> ARCHITECT'S PROJECT NUMBER: <<Contract number>> CONTRACT DATE: <<Project contract date>> CONTRACT FOR: <<Blank 1>>	OWNER: <input type="checkbox"/> ARCHITECT: <input type="checkbox"/> CONTRACTOR: <input type="checkbox"/> OTHER: <input type="checkbox"/>
TO CONTRACTOR: <<Blank 2>> <<Blank 3>>		

THE CONTRACT IS CHANGED AS FOLLOWS:

<<CCO description of change>>

Original Contract Sum	\$<<Original project value>>
The net change by previously authorized change orders	\$<<Sum of all executed CCOs>>
The total value prior to this change order	\$<<Current project value>>
Value of current CCO in review	\$<<CCO value>>
New contract sum including this change order	\$<<Revised project value>>

The contract time will be increased/decreased/by (<<CCO approved time extension days>>) days
The date of Substantial Completion as of the date of this Change Order therefore is <<Revised contract completion date>>

NOTE: This Change Order does not include adjustments to the Contract Sum, Guaranteed Maximum Price, or Contract Time which have been authorized by Construction Change Directive until the last item has been agreed upon by all parties in which the Change Order is then executed to supersede the Construction Change Directive.

ARCHITECT: <<Blank 4>>	CONTRACTOR: <<Blank 5>>	OWNER: <<Blank 6>>
SIGNATURE: ____	SIGNATURE: ____	SIGNATURE: ____
PRINTED NAME/TITLE: <<Blank 7>>	PRINTED NAME/TITLE: <<Blank 8>>	PRINTED NAME/TITLE: <<Blank 9>>
DATE: ____	DATE: ____	DATE: ____

Name the template and save it as an MS Word (.docx) document.

Returning to the Change template register, select the **Add**  icon to create a new Change template. This opens the Change template details page.

Overview - Contract template Details


Item Number	Name	Definition
1	Preview with sample data	Opens a preview of your template using the default sample data.
2	Create new version	Creates a new version of the template. This feature lets you update the version of a template rather than inactivating it and then creating a new one.
3	Control buttons	Lets you to cancel the template creation, save and publish or only save to access later.
4	Detail area	Lets you name the template, specify the template type and language, and add a description of the template.
5	Tags and sample template	Area where you can view and download the general or collection table tags.
6	Template file	Attach the template file which was created with the downloaded tags.
7	Attributes	Lets you add one or more market attributes that provide additional ways to filter templates. Organization-level templates associated to markets are automatically switched to <i>On</i> for Project use on any project with the same market listed in the Project details. When a market is added to the project details, the templates with the associated market are enabled for the project.
8	Advanced options	When Change detects a cost item pricing collection table in the uploaded template, the Advanced option section shows. This section lets you select how you want data to be grouped in the cost item pricing table in the generated document. You can select a field and the columns you want subtotalized in each section. See Cost item pricing table grouping for more information.

New templates appear in the Change templates list in both Organization settings and Project settings.

2.17.1 Cost item pricing table grouping

After you upload a template to the Template details page, Change detects the cost item pricing collection table and then shows the Advanced options section.

You can then select the field you want to group entries by using the Group by tag drop-down list. If you want to show subtotals for the group, click **Select subtotals**. The Select subtotal options dialog box opens showing all field tags that can be subtotalized. Use the arrows to move the fields between the Available subtotals and Selected subtotals list as necessary.



When you generate the Change document, the cost item pricing table shows the data in the specified group. Subtotals within the group are also calculated.

Cost item description	CB total cost	Adjusted cost	Labor cost/M-hr	Billing rate markup %	Billing rate markup	Markup	Billable amount	Debit
Cost pricing: Labor								
10 SUB-Maintenance Force Account (7/31/19-7/31)	0	2100	0	0	0	0	2100	Me
11 STS-Maintenance During Construction	102170.5	3076.92	0	0	0	0	3076.92	Cu
12 C1(Labor (Labor cost item pricing 10.00%))	0	0	0	0	0	517.69	517.69	
	5,176.92				517.69		5,694.62	
14 Cost pricing: Equipment								
15 LABOR	181718.54	600	0	0	0	0	600	Ms
16 SUB-Maintenance During Construction	1021739.13	629.58	0	0	0	0	629.58	Cu
17 Egrnt(Equipment cost item pricing)	0	0	0	0	0	800	800	
	1,229.58				800.00		2,029.58	
18 Cost pricing: Materials								
20 PM-Maintenance During Construction	459792.38	600	0	0	0	0	600	Me
21 C1(Materials (Material cost item pricing 10.00%))	0	600.00	0	0.00	0	600.00	600.00	
	600.00			0.00			600.00	
22 Cost pricing Grand Total	0	0	0	0	0	416.21	416.21	
23 GT markup (Grand Total cost item pricing 5.00%)	0	0	0	0	0	416.21	416.21	
24	0.00							

2.17.2 Template versions

When you update templates with additional information, you can create a new version of the template instead of deactivating it. The Create new version button is enabled when you edit a template.

When you create a new version, the version numbering starts after the previous version. The new template version starts in the draft state. You can edit any of the fields except the template type and language. You can then attach the new file. Only one draft version can exist for a template at a time.

Only one version of a template can be active at a time. After you publish a new version, the previous version becomes inactive and is removed from the Templates register.

The Version column of the Templates register lets you see the template version number. When you click the version number, the template version history is shown. The template names are linked to the Template details page, so you can quickly view the detail information.

Template	Description	Status	Version	Template type	Template file	Created date	Created by	Modified date	Modified by	Temp
ORG A123	ORG A1 TEST	Published	3	Potential change order	PCD template-valid.docx	04/26/2022	Organization level	04/26/2022	Auto Test1	EN
test today proj.2a	test today	Draft	3	Issue		05/10/2022	Emily Barker	05/07/2022	Mandy Becker	EN
test today.proj.2	test today	Published	2	Issue	test template.docx	04/29/2022	Emily Barker	05/10/2022	Emily Barker	EN
new temp 4/15	new temp 4/15	InActive	1	Issue	Issue.docx	04/15/2022	Organization level	05/07/2022	Mandy Becker	EN
new.org.item.4/15	new.org.item.4/15									EN
template testing	template testing									EN
Temp4017398	usfbabaaedfdgfb									EN
Temp830028	eyHfhydodsgmz									EN
Temp1291373	gxmeedslpkorpz									EN
Temp4955956	zbfmduwbrwzr									EN
Temp32170749	qaldlfbduwdrq									EN
test today	test today ng									EN
test today proj	test today									EN
hope@14	edffdf									EN
Story.testing	Story testing									EN
Story.testing.1	Story testing									EN
aaa	aaa									NB-M
Vendor collection	Vendor collection	Published	1	Client change order	IssueLog_2022-April-29...	05/10/2022	Organization level	05/10/2022	chandrakala c	EN
		Published	1	Issue	examplecollection.xlsx	05/11/2022	Organization level	05/11/2022	lav kumar	EN

Template Version History

Version	Status	Template type	Template name	Description	Created date	Created by
3	Published	Potential change order	ORG A123	ORG A1 TEST	04/26/2022	Auto Test1
2	InActive	Potential change order	ORG A11	ORG A1 TEST	04/26/2022	Auto Test1
1	InActive	Potential change order	ORG A1	ORG A1 TEST	04/26/2022	Auto Test1

The Version history subtab contains links to previous versions of a template. The version history shows all versions in descending order, including inactive versions.

Version	Template type	Template name	Description	Status	Template file	Created date	Created by	Modified date	Modified by	Template language	Market
3	Potential change or...	ORG A123	ORG A1 TEST	Published	PCD template-valid.docx	04/26/2022	Auto Test1	04/26/2022	Auto Test1	English	
2	Potential change or...	ORG A11	ORG A1 TEST	InActive	PCD template-valid.docx	04/26/2022	Auto Test1	04/26/2022	Auto Test1	English	
1	Potential change or...	ORG A1	ORG A1 TEST	InActive	PCD template-valid.docx	04/26/2022	Auto Test1	04/26/2022	Auto Test1	English	


Versions of organization-level templates are available for use at the project level, but you can only create a new version of those templates at the organization level.

Build a Change Template

- From the Organization settings page, select Change Templates.

Template	Description	Status	Template file	Created date	Created by	Modified date	Modified by
Testing doc_bug_1	testing	Published	Test.doc for templates...	08/02/2019	Johnathon Harper	08/02/2019	Johnathon Harper
Testing 688955	Test123	InActive	Sample CCO Template...	06/24/2019	Johnathon Harper	06/24/2019	Johnathon Harper
testing	testing	InActive	Change Sample Temp...	06/19/2019	Sathy Jayaraj	06/19/2019	Sathy Jayaraj

- Click the **View available tags** icon, and then select **General tags** to view the tags.



- The Change writer tags document opens.

Change writer tags

Utilize below tags to build change templates. Tags in the template would be replaced with the corresponding tag values, while generating change document.

Tag name	Location source	Description	Example
<<Project ID>>	Project details	The project number	123456
<<Project name>>	Project details	The name of the project	Metro Power Station
<<Project address1>>	Project details	The address of the project	1700 Northwest Street
<<Project address2>>	Project details	The address of the project	Unit 3
<<Project city>>	Project details	The city of the project	Scottsdale
<<Project country or re...	Project details	The country of the project	US
<<Project postal code>>	Project details	The postal or zip code of the project	85201
<<Project state>>	Project details	The state of the project	Arizona
<<Contract number>>	Project details	The projects contract number	CA 139481029
<<Project contract date...>>	Project details	The date of the Project contract	17-03-2020

3. Select the **Export tag list** icon to export it to your hard drive as an Excel file.
4. Save the exported file.



5. Open the Excel file you just saved. The value in the Applicable for column indicates the template type that can use the tag.

Tag name	Location source	Description	Example	
<<Project ID>>	Project details	The project number	123456	
<<Project name>>	Project details	The name of the project	Metro Power Station	
<<Project address1>>	Project details	The address of the project	1700 Northwest Street	
<<Project address2>>	Project details	The address of the project	Unit 3	
<<Project city>>	Project details	The city of the project	Scottsdale	
<<Project country or region>>	Project details	The country of the project	US	
<<Project postal code>>	Project details	The postal or zip code of the project	85201	
<<Project state>>	Project details	The state of the project	Arizona	
<<Contract number>>	Project details	The projects contract number	CA 139481029	
<<Project contract date>>	Project details	The date of the Project contract	17-03-2020	
<<Date project started>>	Project details	The date the Project started	01-09-2019	
<<Original contract completion date>>	Project details	Date project started + original duration	04-03-2021	
<<Original duration>>	Project details	Contract time duration in calendar days	550	
<<Original project value>>	Project details	The original value of the Project contract	\$50,00,000.00	
<<Sum of all executed CCOs>>	Project contract summary (sigma)	Sum of all executed change orders to date (except dropped)	\$1,00,000.00	
<<Current project value>>	Project contract summary (sigma)	The original project contract value + the sum of executed change	\$51,00,000.00	
<<CCO value>>	Current CCO	The value of the selected change order	\$59,137.50	
<<Revised project value>>	Calculation	Total sum of the current project value + current change order val	\$51,59,137.50	

6. Copy and paste the tags into the Word or Excel document you are creating as your new Change document.
 - Tags must be inserted exactly as they appear in Tag name column.
 - A template can use tags that are applicable to one template type plus the tags that are applicable to all templates.

When adding tags for DocuSign, change the font color to white, so the tag name does not show in the generated document.

7. If needed, you can insert one or more collection tables that are applicable to the template type. Refer to [Collection tables](#) for information about building a collection table.
8. After all tags are inserted into the Word or Excel document, name the new template as [your initials] - contract template.
9. Save it as a Word (.docx) or Excel (.xlsx) file.
 - Below is an example of a document with inserted tags

Sample Template with Tags

PROJECT: <<Project Name>>

TO CONTRACTOR:

CHANGE ORDER NUMBER: <<CCO ID>>

DATE: <<CCO created date>>

ARCHITECT'S PROJECT NUMBER:

CONTRACT DATE:<<Contract date>>

CONTRACT FOR:

OWNER:

ARCHITECT:

CONTRACTOR:

OTHER:

THE CONTRACT IS CHANGED AS FOLLOWS:

<<CCO description>>

Original Contract Sum <<Change original contract sum>>

The net change by previously authorized change orders <<Change in value due to executed CCOs>>

The total value prior to this change order <<Change total prior to this CCO>>

Value of current CCO in review <<Change in sum>>

New contract sum including this change order <<Change new contract value>>

The contract time will be increased/decreased/by <<CCO approved time extension days>> days

The date of Substantial Completion as of the date of this Change Order therefore is

NOTE: This Change Order does not include adjustments to the Contract Sum, Guaranteed Maximum Price, or Contract Time which have been authorized by Construction Change Directive until the cost item has been agreed upon by all parties in which the Change Order is then executed to supersede the Construction Change Directive.


ARCHITECT: _____ CONTRACTOR: _____ OWNER: _____

SIGNATURE: _____ SIGNATURE: _____ SIGNATURE: _____

PRINTED NAME/TITLE: _____ PRINTED NAME/TITLE: _____ PRINTED NAME/TITLE: _____

DATE: _____ DATE: _____ DATE: _____

10. Return to the Change templates tab, and then select the **Add template** icon.



The screenshot shows the 'Change templates' tab. On the left, there is a sidebar with icons for General, Control, Plan, Progress, Compliance, and Contract. The 'Contract' icon is highlighted. On the right, there is a table with a header row: 'Template' (with a downward arrow), 'Description', and 'Status'. There are three rows of data:


Template	Description	Status
<input type="checkbox"/> Testing doc_bug_1	testing	Published
<input type="checkbox"/> Testing 688955	Test123	InActive
<input type="checkbox"/> testing	testing	InActive

A red box highlights the 'New template' button (a blue circle with a white plus sign) in the top right corner of the table area.


11. In the Add a new template dialogue, fill in the fields with the following:

- Template name: Use the name you named your template
- Description: Test contract template


12. Under the Template file section, select **No template file attached**.



13. Find and select the change template you want to add.
14. If the template contains a cost item pricing collection table, the Advanced options section shows on the Template details page. You can optionally select a field from the Group by tag field list to specify grouping. If you want items subtotalized, click **Select subtotals**, and then select the columns to subtotal.
15. After the contract template is uploaded, click **Add**.



16. A validation notice is shown.



- If the document was not validated, select the not validated link to view the errors, fix the errors in your Word document, save, and publish again.

The file can be closed and published with invalid tags. During change order generation, invalid tags are not replaced with contract data. The invalid tag displays in the generated contract as it was inserted.

17. Click **Save**.

- To check the formatting of the change document, click **Preview with sample data**. A preview document opens in a separate window, which uses sample data from the tag list. After you have viewed the sample, click **Close**. If you need to make changes to the document, you can update the source and reattach it.


18. Click **Save and Publish**.

Item number	Name	Definition
1	Template	The name you gave as the changed template.
2	Description	The description you used when creating the template.
3	Status	The status of the template after created. The status will show Draft, Published or Saved.
4	Template type	The type of change document that can use the template. Valid types are Client change order, Potential change order, Issue, and Other.
5	Template file	Name of the file which was uploaded into the contract writer.
6	Created date	Date that the contract template was created.
7	Created by	Name of person who created the template.
8	Modified date	Date that the last modifications were made to the template.
9	Modified by	Name of the person who made the last modification to the template.
10	Template language	The language of the tags in the template.

1	2	3	4	5	6	7	8	9	10
Template	Description	Status	Template type	Template file	Created date	Created by	Modified date	Modified by	Template language
<input type="checkbox"/> POC level template	POC level template	Published	Potential change order	docx	04/05/2021	Lavkumar Pandey	04/05/2021		EN
<input type="checkbox"/> Issue level template 1	Issue level template 1	Published	Issue	docx	04/05/2021	Lavkumar Pandey	04/05/2021		EN
<input type="checkbox"/> Check at Project level for P...	Check at Project level for P...	InActive	Issue	docx	04/05/2021	Lavkumar Pandey	04/05/2021		EN
<input type="checkbox"/> AF_Spanish vendor 1	AF_Spanish vendor 1	Published	Issue	docx	03/31/2021	asad fathima	03/31/2021		ES-MX
<input type="checkbox"/> AF_English_POC Workflow 1...	AF_English_POC Workflow 1...	Published	Potential change order	xlsx	03/31/2021	asad fathima	03/31/2021		EN
<input type="checkbox"/> AF_English_CCO workflow	AF_English_CCO workflow	Published	Client change order	xlsx	03/31/2021	asad fathima	03/31/2021		EN
<input type="checkbox"/> AF_Workflow_English_POC	AF_Workflow_English_POC	Published	Potential change order	xlsx	03/31/2021	asad fathima	03/31/2021		EN

2.18 TEMPLATE SETTINGS SUBTAB

Template settings let you configure characteristics for each template type at the organization level. The Template settings subtab (Settings > Change templates > **Template settings**) contains controls for editing, watermark stamps, and PDF output.



Item number	Name	Definition
1	Allow users to edit the document during generation	Indicates whether users can edit the contract document when it is in the review stage. When set to <i>Yes</i> , a user can edit the contract document from the Review templates dialog box. When set to <i>No</i> , the contract document cannot be edited from the dialog box, and the user must edit contract information in Contract.
2	Require a watermark stamp upon document generation	Indicates whether to apply a watermark stamp when the document is generated. When set to <i>Yes</i> the watermark is applied to the document, but is removed after the document has been approved. You can configure the watermark text and settings in the Watermark stamp section of this page. When set to <i>No</i> , the contract document does not have a watermark.
3	Output as PDF only	Indicates whether you can only generate a PDF when you create a contract document. When set to <i>Yes</i> , you cannot generate a Microsoft Word or Excel document or make changes to the contract files individually.

Item number	Name	Definition
4	End watermark requirement event	<p>Indicates the change order approval event that must occur before the watermark stamp is no longer required for this template type. For example, if you set the End watermark event field to CCO approval, the watermark is no longer required after the CCO is approved.</p> <p>You can also indicate that the watermark stamp is always required regardless of the change order approval event.</p> <p>The watermark is removed from the generated document when the document is approved. This field is enabled only when the Require watermark stamp upon document generation toggle is set to Yes.</p>

Because a change document might have templates defined at the issue, PCO, and CCO levels, Change uses the following conditions to determine which setting has precedence when there is a difference in settings:

- If the Allow users to edit the document during generation toggle is set to *No* for any of the templates, Change gives precedence to that setting, and no editing is allowed for any template.
- If the Require watermark stamp upon document generation toggle is set to *Yes* for any of the templates, Change gives precedence to that setting, and a watermark is required for all templates.
- If the Output as PDF only toggle is set to *Yes* for any of the templates, Change gives precedence to that setting, and only PDF output is available for all templates.

The Watermark stamp section lets you define watermark text and layout for the Select watermark stamp drop-down list in the Change writer. You can define the text for all languages used in your templates. The language of the watermark matches the language of the template.

The watermark requirement events that are available vary by template type. The options are as follows:

Template type	Available end watermark events
Issue	Always required
PCO	Always required PCO approval

Template type	Available end watermark events
CCO	Always required CCO approval CCO execution
Other	Always required

2.19 CHANGE CUSTOM LABELS

Change has settings that let you customize field names in the application to align with your business terminology. You can customize the following fields in all languages supported in the InEight product.

- Allowance category
- Change condition
- Change order
- Client
- Client change order
- CCO
- CO
- Issue
- Potential change order
- PCO
- Scope
- Source/cause
- Vendor

Field name	Custom label - EN	Custom label - ES-MX	Custom label - FR-CA	Custom label - PT-BR	Custom label - NL
Change order					
Client change order					
Client CO					
CCO	CCO	CCO	CCO	CCO	CCO
CO	CO	CO	CO	CO	CO
Potential change order					
Potential CO					
PCO	PCO	PCO	PCO	PCO	PCO
Vendor	Vendor	Vendor	Vendor	Vendor	Vendor


You can enter the label text for each of the fields in each language. The custom text replaces the default text in field names, tab names, messages, templates, and other labels throughout the system.

The **Enable custom labels** toggle lets you switch between using your custom labels and Change's default labels. When switched on, Change uses the defined labels in all languages. If you have not defined a label, Change uses the default text for that field. When off, Change uses the default labels for all fields in all languages. You can refer to the Change Custom Labels tab in Project settings as a legend showing the custom labels and how they are referred to in tags and in the Change user interface.


When custom labels enabled at the organization level do not apply to your project, you can switch the **Enable custom labels** toggle in the project settings to Off. When custom labels are disabled at the organization level, you must use the default labels for all projects.

2.20 CHANGE PROJECT SETTINGS

Prior to initiation, it is important to check the project settings to successfully manage a project within Change. Project settings are distinct from organization settings, which are defined by the administrative level of your organization. The image below shows how to get to the project settings from the Main menu.



The image below shows you the two ways you can access Project settings from the Project home page.




Some settings defined at the organization level will limit the settings you can define at the project level.

The following steps walk you through how to navigate to project settings.

Open Project Settings


1. From the home page, click the **Main menu** icon on the upper-left side of the page.
2. Click the **All projects & organizations** menu option.
3. On the Projects tab of the All projects and organizations page, search for the Steel Training job.



The screenshot shows a table with columns: ID, Name, Status, Organization, and Created by. Two rows are visible: one for 'CJ - TP - San Angelo' and another for 'MEC - NY Warehouse 2018'. The 'Name' column contains links to project details. The top right of the table has a search bar with a magnifying glass icon and a red box highlighting it.

ID	Name	Status	Organization	Created by
103631	CJ - TP - San Angelo	Active	3 - Power : SE2020 - Kiewit Power Delivery	Shannon Pechan
103632	MEC - NY Warehouse 2018	Active	1 - SD3007 - Infrastructure East (SVP Level)	Danielle Sandila


4. After you find the project, click the project link in the Name column. The Project home page opens.




The screenshot shows a table with columns: ID, Name, Status, Organization, Created by, and Created on. Five rows are listed, each with a 'Name' column containing a link. A red arrow points to the 'Steel Training Job' link in the first row. The top right of the table has a search bar with a magnifying glass icon.

ID	Name	Status	Organization	Created by	Created on
105091	Steel Training Job	Active	S100000 - PKS Incs	jeremy cheek	03/07/2019 11:12:14 AM
105092	Steel Training Job 2	Active	S100000 - PKS Incs	jeremy cheek	04/23/2019 11:20:39 AM
105093	Steel Training Job 3	New	S100000 - PKS Incs	jeremy cheek	04/23/2019 11:21:13 AM
105094	Steel Training Job 4	New	S100000 - PKS Incs	jeremy cheek	04/23/2019 11:21:57 AM
105095	Steel Training Job 5	New	S100000 - PKS Incs	jeremy cheek	04/23/2019 11:22:25 AM

5. Click **Settings** from the Main menu. The Project settings page opens.



6. Click the **Change** icon in the left side navigation. You can use the expansion arrows to see the icons with product names.



2.20.1 IDF Response Codes

The Issue Documentation Form (IDF) section of Change allows you to view the IDF field name that is mapped to the response code by toggling the switch to on (green check).

IDF response codes

View response codes and field names assigned to the mobile issue documentation form?

Response code	IDF field
IssName	Issue name
IssSDate	Issue start date
FCon	Field Contact
Desc	Description
VerNClient	Have you verbally notified the client?
WorkPlanID	Daily plan ID of impacted work
WrkStrtd	Has work started?
Schlmp	Does this impact the schedule?

2.20.2 Notifications

Under Notifications, select which notifications to turn on. Select the time of the email and use the drop-down list to assign users or roles.

2.20.2.1 Written Notification Time Requirement

The first section of the notifications sections allows you to control within how many days the project must notify the client of issues based on the prime contract. It also allows for the scheduling of email times and users/roles assignments.

Written notification time requirement

What is the written notification time requirement from Prime Contract?

61

Hint: Enter number of business days

Send notification email to recipients as a reminder to send written notification of issue per Prime Contract?

Assign roles or users to receive email reminder 1 day before expiration of written notice time requirement.

Users


Send email at selected time

8:00 AM

* Users

Gopala Penmetsa nagalakshmi s

When written notification is set up, the user receives the following notification email, where the links direct to the specific issue details or the issue log.



2.20.2.2 Notify Scheduler of Issues

This is an email notification that is sent to recipients based on schedule impact of an identified issue. The email notification includes new issues that have a Yes selected for scheduled impact within the Issue Detail page.

Notify scheduler of issues

Send notification email to recipients based on schedule impact of identified issue?

Assign roles or users to receive notifications on schedule impact

Users ▼

Send email at selected time

11:00 AM

* Users

Johnathan Harper X

2.20.2.3 Notify Assigned To Persons

The user receives a summary notification of issues, PCOs, and CCOs assigned to them, where the links direct them to the specific issue details.

Notify 'Assigned to' persons

Send notification email summary to the selected 'Assigned to' persons on identified issues?

Send email at selected time

11:00 AM ▼

Example 1: Email with notification that an issue has been created and needs approval.

The following issue has been created and requires your approval.

Issue Name	Issue start date	Description	Created date	Created by
SC - lighting	06/13/2019	lights need replacement	06/13/2019	susan cappelloni

You can approve/reject this pending issue directly in the [Pending Issue log](#).
 If you need to edit any Issue details, you can select the pending issue from your [Action Items](#) tab.

This is a system generated email. Do not reply.

InEight Change

This is a system email generated by . Do not reply.

Example 2: Email with notification that an issue has been approved.

The following issue has been approved by paul trippi

<u>Issue name</u>	<u>Issue start date</u>	<u>Description</u>	<u>Approver notes</u>
Plumbing piping	06/14/2019		

This is a system generated email. Do not reply.

InEight Change

This is a system email generated by . Do not reply.

2.20.2.4 Notify controller of adjustments

The Notify controller of adjustments settings let you notify a user when a contract adjustment or budget move has been sent to InEight Control.

Notify controller of adjustments

Send notification email to recipients based when Contract adjustment or Budget move has been sent to Control

Assign roles or users to receive notifications on schedule impact

Users

Send email at selected time

08:00 AM

• Users

Items are sent to Control when a client change order is executed. The email notification includes all adjustments that have been sent to Control.


2.20.3 Workflow

One of the primary objectives of Workflow within Change is to provide users or roles with applicable access to approve issues, PCOs, or CCOs. Approvers will see different tabs on the Change register than a user with only viewer access.

2.20.3.5 New issue approval setup

Setting up a workflow for new issue approvals lets you specify approval steps and the users or roles responsible. The steps are performed for all new issue approvals in the project. The workflow cannot be edited in an individual new issue.

New issue approval workflows are configured on the project Settings > Workflow Assignments > **New Issue approval setup** page.



Add a new issue approval workflow

Add a new approval workflow to specify how a new issue gets approved.

1. From the New approval setup page (Settings > Workflow Assignments > **New Issue approval setup**), click the **Add approval** icon. The Add approval slide-out panel opens.
2. Enter a title for the approval step.
3. Select whether the step is to be approved by a specific user or a user in a role, and then enter the name of the user or role. User names include email addresses to help you distinguish which user to enter.
4. Click **Add**. The step is added to the grid.
5. Repeat steps 1-4 for each approval step. You can use the up and down arrows to change the order of the steps.
6. Click **Save**.

When there is at least one step in the workflow, any new issues go into the New issue log with a status of In approval, and an email notification is sent to the approver.

2.20.4 PCO and CCO approvals

The Workflow Assignments tab of your project settings is where you set up approval processes for approving PCOs and CCOs. The settings include defining the number of steps in approval processes and making assignments of who approves each step.

2.20.4.6 Group workflows

Change orders often have varying approvers, which can result in changing the project settings for each change order. Configuring approver group workflows provides alternatives in the approval process, which saves you from manually altering the workflow at the project level each time you require a change-specific workflow.

An approver group is a set of users or roles in steps, similar to an entire workflow. You can set up multiple groups in a single step in a workflow. For example, when a project is done in segments, you might have a different set of approvers for change orders in each segment. Instead of setting up a workflow that applies to the whole project, you can create a multistep group workflow for each segment. You can have one or more group steps in a workflow.

You can configure groups from the Group approver setup page (Project > Settings > Change > Workflow Assignments > **Group approver setup**). Each group can act as its own workflow. In the sample image, a project has two segments, each with a different field engineer and project engineer. The business manager is the same for both segments. A business manager only group is set up for a flow that only needs approval from the business manager, such as resubmitting a previously rejected payment form. All PCOs and CCOs in the project can use the groups.

Group approval name & Approval steps	Users/Roles
Segment 1	Field engineer: Aaron Project engineer: Bennett Business manager: Chris
Segment 2	Field engineer: Diego Project engineer: Elle Business manager: Chris
Business manager only	Business manager: Chris

When you start the approval process from the PCO or CCO, you can select the appropriate view when you click **Save and Start approval**.

Create group workflows

Use group approval workflows as a single step in a larger workflow. The group workflow is users or roles arranged in steps, like the steps used in thresholds. Group workflows let you set up segment-specific workflows to use when a change order has multiple segments or when only one user or role must give an approval.

Only one step in an entire workflow can have a group step.

1. Go to the Group Approver Setup page (Project > Settings > Change > Workflow Assignments > **Group approver setup**).
2. Click the **Add group approval** button. The Add group approver slide-out panel opens.
3. Enter the group approver name (for example, Segment 1), the step title of the first step (for example, Field engineer), and the users or roles for that step, and then click **Add**. The group and its step are added to the grid.
4. To add another step, click **Add another step**, and then enter the step title and approvers. Click **Add**. Repeat this step as necessary to add all steps in a workflow.

You can change the order of the steps by selecting the step and using the up and down arrows. You can use the group approval as a step when setting up PCO or CCO approval workflow.

2.20.4.7 Change order approval setup

You can set up dollar-value thresholds for PCOs or CCOs at the project level. The project has an approval matrix where any dollar amount over the threshold set must be approved.

In the project settings, go to Workflow assignments > **PCO approval setup** or **CCO approval setup**.




Add a workflow assignment


Add a workflow assignment threshold to set the amount at which a PCO or CCO must be approved.

The workflow steps set at the project level are performed after those set at the PCO/CCO. However, if the value of the PCO or CCO is below the project level thresholds, the workflow thresholds set at the project level will not show in the Workflow Assignments.

1. Go to the Workflow Assignments tab.
2. Select the **PCO approval setup** or **CCO approval setup** tab. If an organization step shows a red hazard icon, you must edit the step to select specific users based on assigned roles.
3. Click the **Add approval** icon.
4. In the Add approval slide-out panel, enter the threshold amount and approval step title.



5. Enter the roles, users, or groups in the Assign approval roles field. You can also assign an approver as required by the organization level when you edit a threshold at the project level. When you edit a project-level threshold, the Edit approval slide-out panel includes a view of the organization-level steps at the same threshold. If the organization-level steps require editing, you can assign a user. All other fields of the organization steps are read-only. If the organization-level steps do not require editing, the entire step is read-only.



Organization steps that require editing are marked with a red triangle in the approval details. If there are no project-level steps, you can edit the organization-level steps individually.


6. Click **Add** to complete.
7. If you want the approval workflow for the threshold to have additional steps, click **Add another step**. To change the position of a step, select it, and then use the up and down arrows to the right of the steps to move up or down.

Users, roles, or groups can be assigned to steps at a project threshold.

Project-level thresholds cascade to every PCO or CCO. In a PCO or CCO, you can add additional approval steps. These steps are first, regardless of the value of the change order.

Document approval setup

The Document approval setup lists document types for each document type instead of thresholds. For document approval, you select a document type, and then add approval steps.




2.20.5 Overview - CCO execution setup

Overview - CCO execution setup

Item	Field	Definition
1	Allow users to approve/reject executed CCOs	This setting is automatically defaulted to No. If it is set to Yes, users are allowed to approve/reject issues. If the option is set to On, you cannot switch to Off, if there is anything active in Workflow. If you would like to turn off Workflow, you would need to approve/reject/cancel all the pending Workflows, and then turn it Off. You can set up the Workflow to receive one email for each CCO, or receive a summary email of pending CCOs. If you select the second option, then you can select a specific time that the summary will be emailed.
2	Receive on email for each CCO	User or Role will receive an email for each individual issue.
3	Receive a summary email of executed CCOs	User or Role will receive a summary/grouping formatted email, instead of receiving individual issue emails.
4	Assign user or roles for CCO approval	When choosing the users option, you can select from a list of users to send out emails. If you choose the roles option, you can choose for a list of pre-defined roles.

Overview - CCO execution setup (continued)

Item	Field	Definition
5	Users/Roles	Based on what is chosen for “Assign users or roles for new issue approval”, you will need to choose from a list of users or roles. User names include email addresses to ensure that you select the correct user account.



2.21 CONFIGURATIONS

Project-level configurations let you customize Change for your project. To see the configuration settings, go to project settings, and then select Change >**Configurations**.

2.22 ID CUSTOMIZATION

2.22.1 ID customization

Configuration settings for ID customization (Project settings > Change > Configurations > **ID Customization**) lets you override the organization-level numbering when projects are allowed to edit PCO or CCO IDs (that is, the Allow projects to edit settings check box at the organization level is checked). Override the organization-level numbering by setting the Generate Potential Change order IDs sequentially toggle to Yes. If set to No, IDs function as free text.

When the Generate Potential Change order IDs sequentially toggle is set to Yes, the Allow users to edit generated IDs toggle is shown, and the Prefix and Starting number fields are enabled. You can set the Allow users to edit Generated IDs to Yes to allow users to edit the generated IDs when creating a PCO or CCO or for a PCO or CCO that has been generated. When the field is set to No, users cannot edit the IDs and must use the IDs generated by Change.

You can edit the starting number field only if a PCO or CCO has not been created.

2.23 PRICING MARKUP

The Pricing markups Configurations (Project settings > Change > Configurations > **Pricing markup**) is used to bring over markup values into the Pricing summary and cost item pricing.

You can configure a predefined set of markups and either have the markups automatically populate in the Pricing summary tab or Cost item pricing tab for an issue, or otherwise choose to select specific markups from a list set.

Item Number	Field	Definition
1	Markup Name	Actual name of markup.
2	Markup percentage	Amount added to the cost price of goods or services to cover overhead and profit. Percentages can have up to three digits before the decimal.
3	Applied to section	The section that the markup applies to, which includes Labor, Equipment, Materials, Small tools & supplies, Self-perform subtotal, Vendor Subtotal, Time related overhead, and Grand total.

Item Number	Field	Definition
4	Markup level	Markup calculation levels can be added to the Grand total in cost item pricing or to the Grand subtotal in the pricing summary. Levels 0-4 are available. Markups to other sections are automatically added at level 0. See Markup calculation levels for more information.
5	Auto Display	If set to <i>Yes</i> , the markup populates automatically under the Pricing summary column. If set to <i>No</i> , you have the option to bring in the markup, but the markup does not show automatically.

Pricing summary markups

Create and manage markups to be available for selection at the Pricing summary level.

English		Español		ES-MX	
	• Markup name 1	• Markup Percentage 2	• Applied to section 3	Markup level 4	Auto display 5
<input type="button" value=""/>	<input type="text" value="Enter markup name"/>	0.00000	Select one	Select one	<input checked="" type="checkbox"/>
<input type="checkbox"/>	M1	10.00000%	Labor	Level 0	<input checked="" type="checkbox"/>
<input type="checkbox"/>	Grand total	10.00000%	Grand Total	Level 0	<input checked="" type="checkbox"/>
<input type="checkbox"/>	Indirect cost total	10.00000%	Indirect cost total	Level 0	<input checked="" type="checkbox"/>
<input type="checkbox"/>	Non Billable	10.00000%	Non billables	Level 0	<input checked="" type="checkbox"/>

Cost item pricing markups

Create and manage markups to be available for selection at the Cost item pricing level.

English		Español		ES-MX	
	• Markup name	• Markup Percentage	• Applied to section	Markup level	Auto display
<input type="button" value=""/>	<input type="text" value="Enter markup name"/>	0.00000	Select one	Select one	<input checked="" type="checkbox"/>
<input type="checkbox"/>	MarkupGTLlev1	11.00000%	Grand Total	Level 0	<input checked="" type="checkbox"/>
<input type="checkbox"/>	markupgttest1	0.00000%	Grand Total	Level 4	<input checked="" type="checkbox"/>
<input type="checkbox"/>	markup 2	8.00000%	Grand Total	Level 4	<input checked="" type="checkbox"/>
<input type="checkbox"/>	TestLabor	5.00000%	Labor	Level 0	<input checked="" type="checkbox"/>

2.24 ALLOWANCE CATEGORY

Projects need a way to track issues or change orders against project specific allowances defined within Prime (client contracts). Allowance categories and values are customizable within each project settings by manual entry. This customization has specific permissions around edits. Issues can select a category if it applies for tracking purposes. This provides a project's ability to customize based on Prime Contract and provide assistance in forecasting. If the WBS has costs appear in the OB or CB total cost associated within InEight Control, it automatically populates. The values are for reference or comparison purposes only.

Allowance category						
Create and manage categories and their corresponding values to be available for selection from the 'Allowance category' dropdown within the Issue Upon 'Save', all modifications will be reflected in the 'Allowance category' dropdown and the 'Allowance category' field for all assigned issues.						
English	Position	* Allowance category name	Allowance category value	WBS	Control budget data	Español
	04	Enter allowance category name	Enter value of allowance category	Type WBS ID/Description	OB total cost	ES-MX
<input type="checkbox"/>	01	Warranty				ES_Warranty_ES
<input type="checkbox"/>	02	Allowance				ES_Allowance_ES
<input type="checkbox"/>	03	Contingency				ES_Contingency_ES

Setting the categories is done under the Project settings > Change > Configurations > **Allowance Category** tab. The settings default to Warranty, Allowance and Contingency. These categories are editable.

Additional categories can be added by typing in the name of the allowance and value, then select **Add**.

The categories show in the drop-down list under Change > Issue Log > Details > **Allowance category** to be tagged against. These categories are meant to track values which dollars need to be tracked against. If a WBS was associated from the Allowance category, its number appears in the WBS window. Selecting the eye icon opens an additional information window about that WBS.

Issue description
Field information
Schedule impa

Source/cause

None

Hint: Select what prompted the source/cause ...

Change condition

None

Hint: Select the condition of the change

Scope

None

Assigned to

Hint: Type employee name

Allowance category i

WBS allowance

WBS i

X 58 X 17

Hint: Type WBS ID or WBS description

2.25 DEPENDENT COST ITEMS

The Dependent cost items Configurations section (Project settings > Change > Configurations > **Dependent cost items**) is used to bring dependent cost item values into cost item pricing.

You can configure a predefined set of dependent cost items so you can select specific markups from a list set.

English	Dependent cost item name	Cost percentage	WBS	Applied to section	Español	ES-MX
<input type="text" value="Enter dependent cost item name"/>	<input type="text" value="Enter percentage"/>	<input type="text" value="Type WBS ID/Description"/>	<input type="text" value="Select one"/>	<input type="text" value="Dependent cost item name"/>	<input type="text" value="Enter dependent cost item name"/>	<input type="text" value="Equipment Overhead"/>
Equipment Maintenance	3.00%	1002-Job Overhead	Equipment	Equipment Overhead	Equipment Overhead	<input checked="" type="checkbox"/>
Small Tools & Consumables	3.00%	1005-Erect Steel - Light	Labor	Small Tools & Consumables	Small Tools & Consumables	<input checked="" type="checkbox"/>

Allow users to edit adjusted cost

Field	Description
Dependent cost item name	The name of the dependent cost item that will show in cost item pricing.
Cost percentage	The percentage to be multiplied by all items in the cost item pricing section to calculate the value of the dependent cost item.
WBS	The WBS code for the dependent cost item.
Applied to section	The section that the dependent cost item applies to, which includes Labor, Equipment, Materials, Small tools & supplies, Self-perform subtotal, Vendor Subtotal, Time related overhead, and Grand total.

2.25.1 Allow users to edit adjusted cost


When the Allow users to edit adjusted cost setting is enabled, users can edit the adjusted cost or cost percentage of a dependent cost item in an issue. When you edit the Adjusted cost field, the Cost percentage field is automatically recalculated and vice versa. When editing the adjusted cost is disabled, the dependent cost item values cannot be overwritten by a user.

2.26 DECIMAL PRECISION

You can use the Decimal precision configuration to set the number of digits that follow a decimal point. The precision decimals are used in issue, potential change order, and client change order logs, detail pages; and pricing. Exports for the logs also support decimal precision.

Tag output uses two decimal places.

You can set decimal precision on the Decimal precision configuration page (Project settings > Change > Configurations > **Decimal precision**). You can choose separate decimal precision for values, quantities, and percentages.



You can choose 0-11 digits. If you choose 11 digits, the decimal characters do not fit in the fields of the issue, PCO and CCO headers, and an ellipsis is shown. If you do not enter a value, Change uses a default value of 2.

2.27 MESSAGE CONFIGURATION

Your organization has set defaults for scope status in the organization level settings. This helps drive business behavior or requiring messages for status changes. At the Project level settings, access from Project settings > Change > Configuration > **Message configurations**. From the Configuration list you can toggle on/off the display message, as well as allowing notes. The explanation icon depicts this line item is set at the organization level.

Configuration list	Display confirmation message	Require notes
Allowance category	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Ball in court	<input type="checkbox"/>	<input type="checkbox"/>
Change condition	<input checked="" type="checkbox"/>	<input type="checkbox"/>
General status - Issue	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
General status - Potential change order	<input checked="" type="checkbox"/>	<input type="checkbox"/>
General status - Client change order	<input checked="" type="checkbox"/>	<input type="checkbox"/>

2.28 RESPONSIBLE PARTY

Your organization can establish a default responsible party list in the organization settings. The project inherits the organization list and may mark some as inactive or create additional responsible party options.

To customize responsible party at a project level, go to Project settings > Change > **Configurations**.

Responsible party

⚠ Responsible party names displayed here are established at the organizational level and cannot be deleted. Additional Responsible party names may be added if needed.
Upon save all modifications will be reflected in the 'Responsible party' drop down menu and the 'Responsible party' field for all assigned Issues/PCOs/CCOs.

English		* Responsible party name	+ Active
<input type="button" value="+"/>	38	<input type="text" value="Client"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	01	<input type="text" value="Contractor"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	02	<input type="text" value="Designer"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	03	<input type="text" value="Sub/Vendor"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	04		

The organization list defaults to active. To deactivate, change the toggle in the Action column from the check mark to the minus sign, and then save. Only those responsible party options with an active control are available to select in the issue, PCO, and CCO logs Responsible Party drop-down menus.

2.29 CONSTRUCTION AREA

In Change, for projects that started prior to Release 22.10, there is a drop-down list to reference Construction Areas to project changes you are tracking. In the Construction Area of Configurations (Project settings > Change > Configurations > **Construction area**), you can indicate where the drop-down list of Construction Area comes from.

On the Construction area section of this page, you can switch the toggle to select the source of the Construction Area attributes.

Construction Area

Use the Construction area list created within Plan and it's maintained updated list?

Manually enter the construction areas that will be available for this project.

Position	ID	Description	Actions
1	Area 17	AB down	<input type="checkbox"/>
2	Area 2	Administration	<input type="checkbox"/>
3	Area 18	Superstructure	<input type="checkbox"/>

4 Enter ID Enter description

Up Down

When the toggle is set to *Yes*, construction work area information configured in the InEight Platform Construction Work area (project > Project values > **Area**) populates the Construction area drop-down list in the Field information section of the Additional details in an issue.

When the toggle is set to *No*, you can enter construction area values, and those values populate the Construction area drop-down list. The Construction Area attributes are used in Change.

Construction area configuration in Change is not an option for projects that started with release 22.10 or later, the only way to customize Construction area information is in the Platform Construction area configuration.

2.30 CUSTOM LISTS

Custom lists let you create fields with drop-down lists. Values configured for the custom lists automatically populate project drop-down lists in the specified order. To configure a custom list go to Project settings > Configurations > **Custom Lists**, and then select the custom list.

You can create two custom lists each for issues, PCOs, and CCOs. For each list item, you can add the list position and the description. When a list item is no longer needed for your project, you can switch the Active toggle to Off.

The custom lists are available in the Column options on the issue, PCO, and CCO logs, and you can change the values directly from the log. The fields are not available on the Details pages.

You can use custom labels (Project > Settings > Change > **Custom Labels**) to customize the names of the fields and lists.

2.31 ESIGN SETUP

The eSign setup tab (Project settings > Change > Configurations > **eSign Setup**) lets you add the names of up to 10 recipients, along with their companies, titles, and email addresses, that can be used with every contract in the project.

Each eSign recipient field in this list has a corresponding template tag. You can add the tag to templates to require the signee's signature. The tags are read when sending the document for signature. You can also add recipients to a document when you send the document for eSignature. See

5.8 Change writer on page 236 for information about sending documents for signature. See 2.1 Organization settings on page 20 for information about using tags in templates.

If you edit the eSign setup, the recipients are available for new change documents only. You can override the eSign recipients in the eSign section of the PCO or CCO details.


2.32 CHANGE TEMPLATES

Change writer templates added at an organization level are available for projects by default. At the project level, you may deactivate a template if the template does not suit the needs of the project.

To deactivate a template, go to the project settings, then select Change > Change Templates > **Organization level templates**. Use the Project level use column to change the minus to the check mark.

Only templates that have the Project level use switch set to On appear in the Project level template list and be available for selection when generating a Change document from a template.

Templates may also be added directly at a project level. You can also set up the recipients for eSignature via DocuSign.



Change Templates							
Project Details		Notifications		Workflow		Custom Lists	
Project level templates				Organization level templates			
Template	Description	Status	Template file	Created date	Created by	Project level use	
sasfdsf	dsfdsf	Published	Change Sample Templ...	06/17/2019	venkatesha km	<input checked="" type="checkbox"/>	
Temp_1	Temp_1	Published	Doc2.docx	06/17/2019	asad fathima	<input checked="" type="checkbox"/>	
asds	sadsa	Published	Change Sample Templ...	06/17/2019	venkatesha km	<input checked="" type="checkbox"/>	
abcd123	abcd123	Published	Change Sample Templ...	06/19/2019	Sathya Jayaraj	<input checked="" type="checkbox"/>	
aaa	aaa	Published	Change Sample Templ...	06/19/2019	Sathya Jayaraj	<input checked="" type="checkbox"/>	

2.33 DOCUSIGN SETUP

If your project is integrated with DocuSign for eSignatures, you can embed common signees into your project templates. See [eSign setup](#) for information about setting up eSign.

2.33.1 DocuSign Advanced Options

Change supports the use of DocuSigns Advanced Options. The DocuSign Advanced Options are configured in DocuSign. These options let you customize the DocuSign experience. Your DocuSign administrator can set up the following options in DocuSign:

- Branding options let you select a logo and brand colors that were set up by the DocuSign administrator, for the envelope.
- Reminders options let you specify whether DocuSign sends reminders to signees, when to start sending them, and how often to send them.
- Expiration options let you set the number of days until the envelope expires and how often to send alerts. After the envelope is expired, recipients can no longer view or sign the documents in the envelope.
- Comments options let senders and recipients to enter comments on documents in the envelope.
- Recipient privilege lets you give recipients options for how they sign the document, such as signing on paper, assigning delegates, and editing documents.

2.34 CHANGE CUSTOM LABELS


To view the default values of custom labels set at the organization level, select the **Change Custom Labels** tab. You can use the read-only view as a reference, so you can see where tag information is mapped in a change order. The **Enable custom labels** toggle lets you specify whether to use the organization custom labels at the project level. When the toggle is set to On, the custom labels in the view are used in tabs, fields, tags, and widgets throughout Change. When the toggle is set to Off, Change uses the default labels.

2.35 PERMISSIONS

Permissions for each role are configured in Suite administration. Refer to the InEight Platform help topics for more information about roles and permissions.

2.35.1 Supporting documents permissions

If you want a role to be able to add, edit, or delete supporting documents, you must select the Add supporting documents, Edit supporting documents, and Delete supporting documents permissions nested under the Edit Change permissions. The check boxes for Add supporting documents and Edit supporting documents are enabled when the Edit Change permission is selected. The check box for the Delete supporting documents permission is enabled only when the Edit supporting documents permission is selected.




CHAPTER 3 – GENERAL NAVIGATION

The following topics describe how to use the pages and registers in Change.


3.1 PAGE NAVIGATION

You can open Change using the link provided by your manager or facilitator. Open a web browser, and then click the link provided to open the InEight software.

Click the **Main menu** icon, and then select **All projects & organizations**.




Click your project **Name** link to open the project.



If your project is not shown, you can search by selecting the **Search** icon in the top right corner. This search function searches all terms in all columns.




After you click the project Name link, the Projects home landing page opens.




From the Projects home landing page, you can launch Change in multiple ways:


- Click **Change** from the left menu



- Click the **Main menu** icon, and then click the project or organization. Select **Change** from the list.



- Select **Change** from the app launcher icon in the upper-right corner of the page.




3.1.1 Change Tools and Navigation

Each register page in InEight Change contains menus and tools to help you navigate and perform key functions on the page.

Overview - Change Register Page Tools and Navigation

Title		Description
1	Administrative tools	View your profile and notifications and sign out.
2	Tabs	Tabs you can click to access pertinent information.
3	Actions menu	Contains actions that can be performed from the register page, including viewing the import history, launching the reporting dashboard in InEight Explore, and generating a Change document.
4	Toolbar	Contains functions for the register page you are currently viewing, with specific editing options on the left, such as, add, edit, delete, and copy, and options that involve the entire page on the right, such as, search, import and export options, and contract information on the right.




3.1.1.1 Change Toolbar

The options on this toolbar are different for approvers and non-approvers. The toolbar allows you to use functions for the register page displayed, with basic editing functions on the left and other functions on the right. The toolbar options will change depending on what page you are currently on.

Overview - Change Toolbar

Icon	Function	Permissions
1 Add	Add a new issue to the register page.	Approver/ Non-Approver
2 Reject	After selecting an Issue Id, you can reject an Issue with the option of adding notes.	Approver
3 Approve	After selecting an Issue Id, you can approve an Issue with the option of adding notes.	Approver
4 Clear all filters	To clear all logs in the Change application and the change templates in the project settings.	Approver/ Non-Approver
5 View prime contract summary	The sigma icon displays is accessible throughout the application with details for Prime Contract such as current and projected contract value, contingency amounts and milestone dates.	Approver/ Non-Approver
6 Search	Search all columns for content by the keyword you enter.	Approver/ Non-Approver




3.1.2 Change Register tabs

The Change Register tabs will be visible based upon user access.

	Tab	Access	Definition
n/a	New Issue (when Workflow is turned off)	Viewer/Approver	An incident that happens during a project that could incur costs or impact the schedule. New Issue tab appears when Workflow is turned off.
1	Pending	Viewer/Approver	Similar to the New Issues tab, except Pending

	Tab	Access	Definition
	Issue		
2	Issue Log	Viewer/Approver	Contains a register of all your issues, even if they are new issues or have become PCOs and CCOs during the process.
3	PCO Log	Viewer/Approver	A potential change to the owner's contract that you are pricing and getting ready to negotiate with the owner.
4	CCO Log	Viewer/Approver	A finalized change you are ready to send to the owner.
5	Action Items	Approver	If you are a designated workflow approver, you see this Change page that shows an additional tab called Action Items. The Approve and Reject buttons are enabled for approvers per the Change project settings under Workflow.
6	Audit Log	Viewer/Approver	Captures all changes made into issues, Potential Change Orders, and Client Change Orders.



3.2 COLUMN AND ROW MANAGEMENT

3.2.1 Expand Columns

You can expand a column as needed to see the entire title of that column by using the same method that you would in Microsoft Excel. When you hover over the column, the cursor changes from the arrow to the width selector.

Issue status	Assigned to	Responsible ...	Responsible ...	Written notic...	Date Client notified	Value type
New 1		Contractor		-56		
New 1		Contractor		-56		Estimate
PCO		Contractor		-59		Estimate
New 1		Contractor		-60		
New 1		Contractor		-60		


3.2.2 Move Columns

You can move a column from one place to another using drag and drop. If there are columns that you do not use, you can hide and unhide them from the view as needed.

Move Columns

Summary: You can manually move columns on a Change page to fit your business needs. If you have multiple columns to move, you can also use the enhanced column management tools. For more information, see [Enhanced column management](#).

1. On a Change page, click on a column header, hold down the left mouse button, and then drag the column to the right or left. It shows raised with a shadow box. The right border of the column shows in dark blue and the icon in the shadow box changes to a plus sign to guide you to a new column location.



Markup	Markup %	Pricing status	Date price to Client
\$ 0.00	0.00 %		month/day/year <input type="button" value="Calendar"/> <input type="button" value="Filter"/>
\$ 0.00	0.00 %		
\$ 0.00	0.00 %		
\$ 0.00	0.00 %		
\$ 0.00	3.35 %		

2. Drop the column header where you want to place the column.


3.2.3 Sort Columns

You can sort any column by clicking once on the column header.

Sort Columns

Summary: Sort columns to change the order of the information on the page.

1. To sort a column, click on the column header. An up arrow symbol shows on the column header indicating the column is sorted in ascending order



Issue name ↑	A1	AAAAAA	acinsdvcav	Additional Steel W...	asas

2. To show the column in descending order, click the column header again. The down arrow symbol shows on the column header.
3. Click the column header again to remove the sort. The arrow symbol no longer shows.

Filter Columns

Summary: Filter columns to help you quickly find the information you need.

1. From aChange page, click the **Filter** icon in a column header.


Issue name	Issue status	Assigned to
		
ASD		
New issu		
sad		
Issue 10		
steel stru		
Structure		
Structure Bui...	In review 2	
Structure buil...	New 1	
Additional St...	New 1	

A list of filter operators shows.

2. Select an operator, and then enter filter criteria in the search box in the column header. For example, using the image in the previous step, you could select the operator *Contains* for the Issue name column, and then enter the criteria *structure*. Change filters the column entries based on the filter criteria.

	Issue ID	PCO ID	CCO ID	Issue name
				
<input type="checkbox"/>	214			steel structure Building.c
<input type="checkbox"/>	^ 212			Structure building A
<input type="checkbox"/>	213			Structure Building A2
<input type="checkbox"/>	212.1			Structure building A
<input type="checkbox"/>	^ 210			steel structure Building A
<input type="checkbox"/>	210.1			steel structure Building.A

3. To clear a filter, click the **Clear** icon. If you have used multiple filters, you can click **Clear all filters** in the right toolbar.



The screenshot shows a grid interface for managing issues. The top toolbar includes standard actions like 'New', 'Edit', 'Delete', and a 'Clear all filters' button, which is highlighted with a red box. The grid has columns for Issue ID, PCO ID, CCO ID, Issue name, and Issue status. A slide-out panel on the right displays a detailed view of the first issue, including columns for Written notice, Date Client notified, Value type, Current value, Cost, Markup, and Markup %. The 'Clear all filters' button is also present in this panel.

3.2.4 Manage Row density

You can adjust the row density on the Issue log, PCO log, and CCO log. Click the **Row density** icon in the toolbar to select from Relaxed, Narrow, or Tight density.



The screenshot shows the toolbar for the Issue log. The 'Row density' icon, which is a grid with a red border, is highlighted with a red box. Other buttons in the toolbar include 'New Issue', 'Issue Log' (which is selected and highlighted in blue), 'PCO Log', 'CCO Log', 'Action Items', 'Audit Log', 'View' (set to 'Unsaved (All (except Parked...))'), and various search and filter buttons.

Row density settings on a grid, such as the Pricing summary, are applied to any slide-out panels or dialog boxes accessed from that page.

3.3 ENHANCED COLUMN MANAGEMENT

The enhanced column management tools in the Issue, PCO, and CCO logs provide an efficient way to choose and arrange columns in the grids. The column management feature lets you add or remove columns in the locked sections and remove columns if they are not needed.

To manage columns on a log, click the **Manage columns** icon in the toolbar to open the Column selector builder.

The screenshot shows a 'Column section builder' dialog box overlaid on a log grid. The dialog has two main sections: 'Available columns' (1) and 'Selected columns' (2). It includes search fields (3), move up/down icons (4), transfer icons (5), transfer all icons (6), and a lock/unlock indicator (7). The log grid in the background displays columns like Cost, Markup, Markup %, and Pricing status.

Use these sections and tools to help you organize columns in the Issue, PCO, and CCO log grids:

Item	Description
1	The Available columns section shows all the columns to choose from that are not currently used in the grid.
2	The Selected columns section shows all columns that currently show in the grid and their order.
3	The Search feature lets you search the available columns or the selected columns for a field.
4	The Move up and Move down icons are enabled when one or more columns are selected in the Selected columns section. Click an icon to move the selected column up or down in the list
5	The Transfer to and Transfer from icons are enabled when one or more items are selected in the Available columns or Selected columns section, respectively. Click the Transfer to icon to move the selected columns from the Available columns section to the Selected columns section. Click the Transfer from icon to move the selected columns from the Selected columns section to the Available columns section.
6	The Transfer all to and Transfer all from icons let you transfer all columns to the Selected columns section to the Available columns section, respectively.
7	All columns listed above the Locked section indicator are locked and remain stationary as you scroll left or right. Columns listed below the locked center are unlocked and


Item	Description
	scroll left or right. You can use the Move up arrows, or you can drag and drop to move columns from the unlocked section to the locked section.

Click **Save** to apply the changes. The changes are saved for as long as you are on the log. To save the column arrangement as a view, expand the **View** drop-down menu, and then select **Save view as**.

CHAPTER 4 – ISSUES

Change features let you create, manage, and price issues.

4.1 INEIGHT CHANGE WORKFLOW



4.2 ISSUE CREATION AND SETUP

4.2.1 Issue Creation

The following steps walk you through creating a new issue in InEight Change. The Add new Issue wizard lets you add supporting documents and vendors in a single operation. Vendors added with the issue show in the Vendors grid on the issue's Details page.

If supporting documents or vendor information, you can edit the new issue later.

Create a new issue

When an issue occurs in your project, you can create a new issue record from the New Issue page or the Issue log.

Considerations: These instructions assume that you have supporting documents and vendor information. If you do not have this information, you can click **Add** or **Add and New** to quickly add the issue. If workflow is configured at the issue level, you can click Submit for approval. You can return to the issue later.

1. From the New issue page or the issue log, click the **Add issue** icon. The Add new issue wizard opens.
2. Enter the issue name and issue start date. You can also optionally enter the ROM, a description of the issue, and other detailed information.
3. Click **Next** to go to the Add supporting documents page and then add supporting documents information. For more information about adding supporting documents, see [Supporting documents](#). If you do not have supporting documents, go to the next step.
4. Click **Next** to go to the Add Vendors page and then select vendors from the list.
5. Add or submit as follows:
 - If workflow is not configured, click **Add** to add this issue or **Add and next** to add an additional issue.
 - If workflow is configured, click **Submit for approval** to submit for approval or **Add and next** to add an additional issue.

If approval is not configured or if you are the first approver in the workflow, the issue is added to the New issue page and the Issue log with an issue ID assigned and an issue status of *New*. If a workflow is configured and you are not the first approver, the issue is added to the New issue log with a status of *Pending*. If you added vendors, they are added to the Vendors grid on the issue's Details page.

How the Issue ID, Issue status, and Issue approval status of a new issue are assigned depends on whether workflow is configured.

- When workflow is not configured, the issue is added to the New issue page and the Issue log with an issue ID assigned. The issue status is *New*, and the issue approval status is *Not applicable*.
- When workflow is configured and the person who created the issues is also the first approver in the workflow, the issue is automatically approved for the first step. The issue is added to the New issue page and the issue log with an issue ID assigned and an issue status of *New*. The issue approval status is *Approved*. When you hover over the issue approval status, it shows that it has been approved for the first step and is in step 2, if there is a step 2.
- When workflow is configured and the person who created the issue is not the first approver in the workflow, the first approver (either a person or a role) receives an email letting them know there is an issue to be approved. The issue is added to the New Issue page with an issue ID of *Pending*, an issue status of *New*, and an issue approval status of *In approval*. The issue is not added to the issue log until it has gone through all the approval steps.

- When issues have been rejected in workflow, they show in the New Issue log with the Issue ID *Rejected*, so they can be quickly identified. Rejected issues are disabled, so you can no longer see the issues. InEight recommends using the Comments section in the workflow to describe the issue and the reason it was rejected.

When the issue is in workflow, Change allows you to add supporting documents and edit fields that might help the reviewers in making approval decisions. To open the pending issue, click the **Pending** link in the Issue ID column of the New issue log. The Issue Details page opens, and you can then edit any field that is enabled. You can also go to the Supporting documents tab to add documents.

You can also import issues from a template. See [4.13 Issue Import on page 144](#) for information about importing issues.

Contract users can also add an issue from a VCO in Contract. If a new issue approval workflow is configured, the issue automatically goes to the New Issue log with an Issue ID of Pending. It does not get an issue ID until it is approved.

4.2.2 Issue Header

When you click on an issue's ID or name, the issue's record page opens. At the top of the page, a header section provides workflow and status information that you can update during the issue's lifecycle.



Current value \$ 100,013.00000	Cost \$ 100,013.00000	Billing markup \$ 0.00000	Markup \$ 0.00000	Markup % 0.00000%	Deductions \$ 0.00000	Net value \$ 100,013.00000	Issue status New	Pricing status None	Proposal status None
-----------------------------------	--------------------------	------------------------------	----------------------	----------------------	--------------------------	-------------------------------	---------------------	------------------------	-------------------------

4.2.2.1 Cost, markup, and markup percent pricing breakdown

The Issue, PCO, and CCO shows the breakdowns of cost, billing markup, markup, markup percent, and deduction fields. This gives you the visibility into the profit you are making on an issue or change.

The Cost is the total of all priced items. The Billing markup is the markup based on the resource billing rates. The Markup is the total of all markups from the cost item, Pricing tab, PCO, and CCO. The Markup % is the markup divided by the cost. Deductions come from the cost item pricing tab and are subtracted from the current value. Current value is costs plus markups minus deductions.

4.2.2.2 Status information

The status information lets you see issue status information at a glance. The statuses include the following:

- Issue status (called PCO status or CCO status on their respective tabs)
- Pricing status
- Proposal status


4.2.2.3 Issue status

The Issue Status drop-down menu is used to define the general progress of an issue, potential change order, or client change order and is the primary indicator used to determine what action is needed next and by whom. It is used to track the change through the different stages in the change management process, highlighting its progress from issue creation and review through CCO execution. Depending on the selection, fields in the selected issue, PCO, or CCO become locked.

The following are examples of statuses you can assign. Your organization or project might have configured custom statuses:

- In Review – The issue is currently being reviewed.
- PCO – The issue is now connected to a Potential Change Order.
- CCO – The issue now converted to a Client Change Order.
- Parked – The issue is no longer active but may be brought up again later. When selected, all fields within the issue become locked.
- Dropped – The issue is no longer being considered. When selected, all fields within the issue become locked.
- Dispute – The issue is under dispute.
- Closed - The issue is closed. You cannot split a closed issue or associate it to a Potential Change Order (PCO) or Client Change Order (CCO).

Changes made to Issue status open a dialog box where you can add notes related to the assignment you are making. Notes are not mandatory to save the change but canceling the dialog box causes the Issue status to revert to the previous state.




4.2.2.4 Pricing status

The Pricing status is used to track the progress of all financial activities related to a change, from initial ROM or cost estimation to the final pricing agreement with the client. This field defines the current state of the financial evaluation for the Issue, PCO, or CCO. It can be used to track the entire pricing life cycle, including cost gathering from vendors, internal estimation, review, and formal submission to the client.

You can select the Pricing status drop-down menu to classify where you are in the process of pricing the issue. Options include the following:

- Complete
- Not Started
- In Process
- Audit Review
- Complete




When changing the Pricing status, you are prompted to record notes just like you were when changing the other statuses.

4.2.2.5 Proposal status

The Proposal status is used to track the life cycle of the official proposal package, from initial negotiations to submission and approval to the subcontractor or client. This field defines the current state of the formal written proposal that bundles all budgetary, scheduling, and technical details for a change. It is used to track the progress of the official client-facing document, distinguishing it from internal pricing and general status.

Select the Proposal status drop-down menu to classify the proposal status of the issue. Options include:

- Not started
- In negotiation
- Submitted by sub
- Accepted by Contractor
- Submitted to client
- Accepted by client
- Rejected



When changing the Proposal status, you are prompted to record notes just like you were when changing the other statuses.

4.2.3 Delete an issue

You can delete issues from the Issue log that were entered in error or are no longer valid. The issues must meet certain criteria based on their status, PCO or CCO association, and origin.

You can delete an issue if it meets the following criteria:

- The issue must have been created in Change or added via an API. Issues that originate from another InEight product, such as Plan, Progress, Compliance, Contract, or Document cannot be deleted.
- The issue must have a status of *New*, *Parked*, *Dropped*, or a custom status.
- The issue cannot be associated with a PCO, CCO, or budget move.
- The issue cannot be a main issue.

If you delete the issue with the highest number, the next issue created will take that number. If you delete an issue with a number in the middle of the list, that number is not used again.

To delete issues, select one or more issues from the Issue log, and then click the **Delete** icon. You must have the permission Delete issues.

4.3 DETAILS TAB

Below the header on the issue record, there are three tabs for capturing the issue's details, costs, and supporting documentation.

The Details tab is where you can record key information for understanding the nature of the issue and its potential impact. It is organized into the following sections:

- Issue details
- Issue description
- Additional details

4.3.0.1 Issue details

The issue details section includes fields that identify the issue.

Title		Description
1	Issue navigation	Lets you navigate to other issues without having to go back to the Issue log. Click the arrow to see a list of issues, and then select one. The selected issue opens in the same window.
2	Issue name	<ul style="list-style-type: none">• Free-text entry (will auto populate from initial entry screen)• Contract will generate un-editable Issue ID separate from Issue name for internal tracking• Required to create new issue

Title		Description
3	Issue start date	<ul style="list-style-type: none"> • Calendar drop-down • Select start date of actual impact (will auto populate from initial entry screen) • Required to create new issue
4	Description of change	Free-text entry and editor for description of issue (auto populates from initial entry form).

The screenshot shows a web-based form titled 'Issue: 45 - details'. At the top, there is a status indicator '1' and a note 'Created by [redacted] on 10/26/2021'. Below this, there are two input fields: 'Issue name' (2) and 'Issue start date' (3). The 'Issue name' field contains a blurred value. The 'Issue start date' field contains '10/26/2021' and includes a calendar icon. A hint below the date field reads 'Hint: Date of the start of impact'. At the bottom of the form is a rich text editor for 'Description of change' (4), which includes a toolbar with 'Format' and other editing icons.

4.3.0.2 Issue description

The Issue description section contains fields that help classify the issue.

Title		Description
1	Source/Cause	Drop-down menu populated with general issue causes. The Source/Cause field identifies the underlying reason or root driver, such as an originating document, event, or instruction that initiated the issue. The source or cause typically requires investigation to determine why the issue occurred (for example, the initial soil analysis was incomplete or inaccurate).
2	Change condition	Drop-down menu populated with general conditions of change. The Change condition identifies the immediate event or circumstance that triggered the issue (for example, encountering rock in an area where soil was expected.)

Title	Description	
3	Scope	Drop-down menu populated with scope identification of issue.
4	Allowance category	Category assigned to issue for tracking.
5	Vendors	An area where you can associate vendors to an issue without having to go to the Pricing page.
6	Assigned WBS	Validated WBS structure to associate a code with your issue. WBS codes include all terminal cost items from InEight Control. WBS codes can be assigned from InEight Plan or Control, or from this section. If the project is imported again from InEight Estimate after the WBS is associated, you must manually update the issue with the new WBS code.
7	Push to cost item pricing	Automatically add the WBS codes to the cost item pricing for the issue.

Issue description

Source/cause 1

2

Change condition 2

1

Scope 3

4

5

Allowance category 4

1

Vendors 5

Vendor ID

6
7
Push to cost item pricing

Assigned WBS 6

7
Push to cost item pricing


Hint: Type WBS ID or WBS description

Associate a vendor to an issue

Associate one or more vendors to an issue when you have vendor information, but you are not ready to price the issue.


Vendors must already have contracts on the project to be able to be selected from the issue Details page.

1. From the issue's Details page, click the **Add vendor** icon in the Vendors field. The Select vendor dialog box opens.



The screenshot shows the 'Issue description' section of the 'Details' tab. At the top, there are tabs for 'DETAILS' and 'PRICING'. Below the tabs, there are sections for 'Source/cause' and 'Change condition', both set to 'None'. Under 'Vendors', there is a table with columns for 'Vendor ID' and 'Vendor'. A red box highlights the '+' icon in the 'Vendor' column header. Below the table, a message says 'No Vendors have been selected'. At the bottom, there is a 'Hint' field with the placeholder 'Type WBS ID or WBS description'.

2. Select one or more vendors from the Available Vendors list, and then click **Add**. The vendors are added to the issue.



3. On the Details page, click **Save**.

When you are ready to price the issue, you can add a vendor to cost item pricing.

Add a vendor to cost item pricing

Add a vendor to cost item pricing from the Details page when you have already added vendors to the issue and are adding cost items.

1. From the issue's Details page, select a vendor, and then click **Push to cost item pricing** in the Vendors field. Only vendors that have been added from the Details page can be pushed to cost item pricing. Vendors that have already been added to cost item pricing are shown as disabled.

The screenshot shows the 'Issue description' section of a software interface. It includes fields for 'Source/cause' (None), 'Change condition' (None), 'Scope' (None), 'Allowance category' (None), and 'Vendors'. The 'Vendors' section lists several entries: 'Vendor ID' (0010001055 is checked and highlighted with a blue box), '0010001491', and '0010001288'. To the right is a list of 'Vendor' names: 'Marco Crane & Rigging Co' (highlighted with a blue box), 'Bigge Crane & Rigging Co', and 'Professional Service Industries'. Below the vendor list is a 'Push to cost item pricing' button. The 'Assigned WBS' field is empty, with a placeholder 'Hint: Type WBS ID or WBS description'.

The Select WBS to push to cost item pricing dialog box shows with a list of all contracts associated with the vendor and associated WBS phase codes.

2. Select one or more WBS phase codes, and then click **Add**. The vendor is added to the Vendor section of cost item pricing and shows on the pricing summary. It also shows as disabled in the Vendor list of the issue's Details page.

After you push the vendor to cost item pricing, you can associate the cost item to a vendor change order.

If you have pushed a vendor to cost item pricing by mistake and want to remove it, you must remove the cost item pricing item from the Pricing page and then remove the vendor from the Pricing summary. The vendor is then automatically removed from the Details page. When a vendor is associated to a vendor change order, you cannot delete the vendor from the Vendors section.


Push a WBS code to cost item pricing

You can push the WBS codes you add to an issue directly to the cost item pricing for the issue, so you do not have to add them again when you configure cost item pricing.

This procedure adds the WBS codes to the cost item pricing. Any items that you add to the pricing are not pushed to the Details page. You can add them manually.

1. On the Issue Details page, enter the WBS codes you want to use for the issue in the Assigned WBS field.

2. Click **Push to cost item pricing**. The Push WBS to cost item pricing dialog box opens.



3. Select the WBS codes you want to push to the cost item, and then click **Add**. The items are added to the pricing.

Items that are manually added on the Cost item pricing tab are not automatically added to the details. You must add them manually.

4.3.0.3 Additional details

The Additional details section has expandable subsections for the following features:

- Control budget change
- Schedule impact
- Responsible parties
- Correspondence
- Request for information
- Tasks
- Weather
- Field information
- Design information
- Revenue category
- Project values
- Custom fields

Click the arrow in the subsection heading to expand the subsection.

Overview - Details Tab - Control budget change

Title	Description
Control budget status	<p>The status of the budget move in InEight Control. You can click the link in the field to go to the Control Workspaces page.</p> <p>When this field contains a value, the heading for this section shows the corresponding status icon from Control. See Budget moves for more information about initiating a budget move.</p>
Control change register ID	<p>The change register ID from Control. You can click the link in the field to go to the Control Workspaces page.</p>

Additional details

Control budget change [🔗](#)

Control budget status	Control change register ID
Draft	197.0

Schedule impact

Overview - Details Tab - Schedule Impact

Title	Description
1 Has work started?	Yes/No drop-down menu.
2 Delay days	The number of delay days associated with the issue.
3 Does this impact the schedule?	Yes/No/TBD drop-down menu.
4 Schedule impact comments	<ul style="list-style-type: none"> • Free text entry to enter comments explaining how the issue will impact the schedule • Only available if you select Yes for <i>Does this impact the schedule?</i>

Additional details

Schedule impact

Has work started? **1** Delay days **2**

Select

Does this impact the schedule? **3**

Select

Schedule impact comments **4** 500

Overview - Details Tab - Responsible Parties

	Title	Description
1	Assigned to	Validated drop-down list of users assigned to current project.
2	Responsible party	The job title or role responsible for the issue.
3	Responsible party person	The person who is responsible for the issue. This is a free text field.

Additional details

Schedule impact

Responsible parties

Assigned to **1**

Hint: Type employee name

Responsible party **2**

Hint: Select the responsible party person

Responsible party person **3**

Hint: Type employee name

Correspondence

Overview - Details Tab - Correspondence

Title	Description
1	Have you verbally notified the client?
2	Conversation summary <ul style="list-style-type: none"> Free text entry of summary of client verbal notification Only available if you select Yes for <i>Have you verbally notified the client?</i>
3	Date client notified <p>The date the client was notified. An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.</p>
4	Date price to client <p>The date the price was communicated to the client. An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.</p>

Additional details

Schedule impact

Responsible parties

Correspondence

Have you verbally notified the Client? 1

Conversation summary 2

Correspondence

Date client notified 3

Date price to client 4

Date

i

File/Link

i

InEight Inc. | Release 25.9

Page 111 of 257

4.3.0.4 Request for Information

RFIs are often a result of an issue. You can manually add RFI documents from this section or from the Supporting Documents page. If you manually upload an RFI, only the Title and RFI No. columns are filled. The Status column is only filled when you add an RFI from InEight Document. The heading for the Request for Information section includes a counter so you can quickly see the number of associated RFIs the issue has.

The screenshot shows the 'Additional details' section of the Change Management software. On the left, there's a sidebar with 'Description of change' and 'Issue description' sections. The main area contains a table for 'Request for information' with two rows: 'New RFI document' and 'From InEight Document'. A red box highlights the 'New RFI document' button. The table also includes columns for 'Title' and 'Status', with a note 'There are no associated RFIs'.

To add an RFI document from this section, click the **Add Request for information** icon, and then select whether to add a new document or a document from InEight Document.

Although you can add an RFI to a PCO or CCO, the Request for information section only shows for issues.

Overview - Details Tab - Tasks

Title	Description
1 Task count	The number of pending and overdue tasks for the issue.

Overview - Details Tab - Tasks (continued)

Title		Description
2	Task title	The name of the task. The name is a link to the task in InEight Compliance.
3	Task person	The name of the person assigned to the task.
4	Due date	The date the task is due. Overdue tasks are highlighted in red.
5	State	The state of the task (scheduled, pending, overdue, complete). Pending tasks are highlighted in yellow; overdue tasks are highlighted in red;

Task title	Task person	Due date	State	
task1	task1 person	12/10/2021	Pending	1
task2	task2 person	12/05/2021	Complete	2
task3	task3 person	11/20/2021	Complete	3
task4	task4 person	11/29/2021	Overdue	4
task5	task5 person	11/06/2021	Overdue	5
task6	task6 person	11/06/2021	Overdue	

Overview - Details Tab - Weather

Title		Description
1	Weather heading	Lets you see at a glance the first weather condition assigned in the issue.
2	Weather condition	You can select a weather condition from the drop-down list. An icon for the weather condition is shown in the Weather heading. You can select multiple weather conditions (for example, snow and wind), but only the first icon shows in the heading.
3	Create historical weather record	Lets you create a historical weather record for a seven-day period. The historical weather record uses the longitude and latitude from the project details to give a precise report of the weather conditions for the specified period. You can specify a start date that is up to one year before the current

Overview - Details Tab - Weather (continued)

Title	Description
	<p>date. The end date can be up to seven days after the start date. The conditions include the temperature, weather condition, wind speed in meters per second and miles per hour, and precipitation.</p> <p>Change creates a PDF of the record and stores it in the Supporting documents tab for the issue.</p>

Additional details

Schedule impact ▾

Responsible parties ▾

Correspondence ▾

Request for information ▾


Tasks ▾

Weather  ①

③ Create historical weather record

Snow ▾ ②

 Add weather condition



Create a historical weather record for an issue

You can create a historical weather record for a seven-day period within the last year.

If you choose a start date that is less than seven days from the current date, the report is for the period from the start date to the current date. You cannot choose a date that is older than a year from the current date.

1. From the Issue Details page, expand the Weather section in the Additional details.
2. Click **Create historical weather record**. A weather record dialog box opens.

Create historical weather record for Omaha, Nebraska, 68114, United States Of America, Lat. 41.2656 , Lon. -9...

Upon clicking the Create button, a supporting document will be created and added to the supporting documents tab.

Select up to 7 day date range from past year to display hourly weather history.

(UTC-06:00) Central Time (US & Canada)

Start date	Start time	End date	End time			
11/22/2021	12:30 AM	11/28/2021	11:30 PM	Search	Create	Reset parameters
Date	Time	Temperature	Weather condition	Wind	Precipitation	
11/22/2021	1:00 AM	-1°C,30°F.	overcast clouds	0 m/s, 0.00 mph		
11/22/2021	2:00 AM	-1°C,30°F.	broken clouds	0 m/s, 0.00 mph		
11/22/2021	3:00 AM	-1°C,30°F.	overcast clouds	0 m/s, 0.00 mph		
11/22/2021	4:00 AM	-1°C,30°F.	overcast clouds	0 m/s, 0.00 mph		
11/22/2021	5:00 AM	-1°C,30°F.	scattered clouds	0 m/s, 0.00 mph		

3. Enter a start date and time and end date and time, and then click **Search**. Change calls a weather API and then returns hourly weather conditions for each hour.
4. Click **Create**. Change creates a PDF of the weather record and stores it in the Supporting documents tab for the issue.

Overview - Details Tab - Field Information

Title		Description
1	Construction Area	The construction area associated with the issue. Select from a list of construction areas defined in InEight Platform from the drop-down menu. The Settings icon is a shortcut to the Construction areas configuration (project > Project values > Area), so you can configure a new construction area, if needed.
2	Field Contact	Validated drop-down list of users assigned to current project.
3	Daily Plan ID of impacted work	The daily plan ID associated with the issue. You can click the Add daily plan ID of impacted work button to add additional daily plan IDs. The daily plan ID is for reference only. You can click the Daily plan ID search icon to search for plan IDs in InEight Plan or InEight Progress. The Daily plan ID search lets you select operators, and the search returns plan IDs that meet the search criteria. Values selected from the search results are hyperlinked to the fields in Plan or Progress.

Overview - Details Tab - Field Information (continued)

Title	Description
4 Latitude and Longitude	The latitude and longitude of the construction area associated with the issue. These fields are for reference only.

Additional details

Control budget change ▾

Schedule impact ▾

Responsible parties ▾

Correspondence ▾

Request for information ▾

Tasks ▾

Weather ▾

Field information ^

Construction area **1**  Field contact **2** 

Select 

Hint: Type employee name

Daily plan ID of impacted work **3**  Daily plan ID search

Hint: Enter "123"

 Add daily plan ID of impacted work

Latitude **4** Longitude





Overview - Details Tab - Design Information

Title		Description
1	Plan/detail sheet number	Click the Add link to display a field to enter plan/detail sheets - optional entry field.
2	Specification section number	Click the Add link to display a field to enter specification section numbers - optional entry field.
3	Components	Click the Add link to display a field to enter related components - optional entry field.

Additional details

Schedule impact ▾

Responsible parties ▾

Correspondence ▾

Request for information ▾

Weather ▾

Field information ▾

Design information ▾

Plan/detail sheet number 1

[\(+\) Add plan/detail sheet number](#)

Specification section number 2

[\(+\) Add specification section number](#)

Components 3

[\(+\) Add component](#)

Revenue category ▾

Custom fields i ▾

Overview - Details Tab - Revenue category

Title		Description
1	Revenue category	The revenue category for the issue. The revenue categories are defined in the organization master data. You can select the category from a drop-down list.

Overview - Details Tab - Revenue category (continued)

Title	Description
2 Revenue change status	The change status of the revenue category. This field is read-only.
3 Probability percentage	The probability percentage based on the settings in the master data. This field is read-only.

Additional details

Schedule impact	▼
Responsible parties	▼
Correspondence	▼
Request for information	▼
Weather	▼
Field information	▼
Design information	▼
Revenue category	^
Revenue category 1	<input type="text" value="None"/>
Revenue change status 2	<input type="text"/>
Probability percentage 3	<input type="text"/>

4.3.0.5 Project values

The Project Values section shows the project values configured for the project. For each project value, you can select a value from the drop-down list. Each field has a Settings icon that takes you to the Available project values page of the project. You can add project values or change the status of existing project values with the applicable permission.

4.3.0.6 Custom fields

Custom fields include Issue custom lists 1 and 2 and Issue custom fields 1-4.


4.4 REVIEW OR APPROVE AN ISSUE

If you are an approver in the approval workflow, you are notified by email when you have an issue to approve. If you are an approver in the first approval step, your issue is automatically approved, and the approval step is skipped.

Review or approve an issue

Summary: Review or approve an issue when workflow is configured and you get a notification

1. Navigate to the Steel Training Job > Change > Issue Log.
 - Since you are an approver, your issue is not queued for approval and is in a Review status.
 - Notice that an Issue ID has been assigned to the issue.
2. Click on the Issue ID for [your initials] – Bearing Pads.



	Issue ID	PCO ID	Client CO ID	Issue name
<input type="checkbox"/>	38			PT-Bearing Pads
<input type="checkbox"/>	37			PT - Bearing Pads
<input type="checkbox"/>	36 B	PAT001	Client Chang...	PAT - Bearing Pads (B)

3. As part of your review as an approver, go into the Issue and make a change to the Description.
 - Description: Add This is a high priority

Issue description

Created by paul trippi on 06/26/2019

*Issue name

PT - Bearing Pads

*Issue start date

06/26/2019 

Hint: Date of the start of impact

Description

904

Installed bearing pads do not match pad locations on turbine generator This is a high priority.

4. Select **Save**.

4.5 CHANGE TOOLBAR

Change has Project contract summary, supporting documents, and Notes icons available on every tab.




See [Supporting documents](#) for information about using the Supporting documents tool.

4.5.0.1 Project contract summary

Click the Project contract summary icon to open a slide-out panel that has a breakdown of the totals.


Title		Description
1	Current project value	The sum of the original project value and the Executed CCOs.
2	Projected project value	The projected project value is the sum of the current project value and the Non-executed CCOs. The Potential project value is the sum of the projected project value and the non-executed PCOs.
3	Milestones	Lists of contract and forecast dates for the project. The Forecast start date, Duration, and Completion date are entered on the Project details page. The Extension/Reductions, Revised duration, and Revised completion

Title	Description
	date are sent to the Project details page. Extension/Reductions are updated and populated from the CCO schedule impact dates upon execution of the CCO, and the revised completion date is updated accordingly. The Estimated float is the difference between the Forecasted revised completion date and the Contract revised completion date.
4 Allowance category	The totals of any issues associated with an allowance category on the Issue details page out of the total value that was assigned to that category in the project settings.




4.5.1 Add notes

To add notes to an issue, click the Add notes icon. The Notes slide-out panel opens, and you can view previous notes and add a new one.



The supporting document notes are maintained as the issue moves up to a PCO and CCO.

When you add notes on the Supporting documents tab, the slide-out window has a tab that lets you add notes that are specific to the document. Notes added at other levels are also visible.




When you approve or reject a document at the issue level, the notes you add for the approval or rejection are also visible at the PCO and CCO levels.

4.5.1.2 Allowance Category Summary

When you open the Prime contract summary panel with the sum Σ icon button, an Allowance category section is at the bottom of the panel. This section shows all of your project's allowance categories and their calculated amounts. Color-coded bars show how much of each category's amount is actual, potential, or remaining. You can hover over each color in the key to see definitions. These amounts are defined as:

- **Actual**- Sum of closed and executed issues
- **Potential**- Sum of all issues except closed, dropped, and executed
- **Remaining**- Allowance value minus the sum of actual and potential




4.6 CURRENT VALUE

The Current value of an issue is displayed in the issue log as well as the far left of the issue header.

The screenshot shows a table of issues for job 105091. The columns include Issue ID, PCO ID, Client CO ID, Issue name, Issue start date, Issue status, Assigned to, Ball in court, Ball in co..., Written no..., Date clien..., Value type, and Current value. The 'Current value' column is highlighted with a red border.

Issue ID	PCO ID	Client CO ID	Issue name	Issue start date	Issue stat...	Assigned to	Ball in court	Ball in co...	Written no...	Date clien...	Value type	Current value
4			Extra bolt as...	05/30/2019	New				-14		ROM	\$37,450.00
34			PT - Bearing...	06/17/2019	In Review				-2		ROM	\$20,700.00
5			Rebar Coupl...	04/25/2019	New				-39		ROM	\$20,500.00
11			PT - Bearing...	06/05/2019	New				-10		Proposed	\$7,000.00




The issue's Current Value updates automatically with the information entered in the Pricing fields. The value that the Current Value displays comes from the sum of the Self perform and Vendor subtotals, plus any lump sum adjustments, if any.


4.7 SUPPORTING DOCUMENTS

The Supporting Documents tab houses all the documentation for the issue in one location. This includes checklists, designs, diagrams, insurance, meeting notes, permits, proposals, etc. By housing this in one tab, all involved with the issue can verify all necessary documentation is gathered from the parties involved.

You add supporting documents by clicking the **Add** icon on the issue's Supporting Documents tab. You have the choice of adding a new supporting document or adding a document from InEight Document.



When you choose **New supporting document**, in the resulting Add supporting documents window, you can add the appropriate documents as needed by filling out the Title and Document type in the Add supporting document dialog box, then browsing to your document file and attaching it. When the document is added from InEight Document, and the document type in Document matches a document type in the cloud platform, that value shows as the default document type. You can edit the document type as needed.



The screenshot shows a modal dialog box titled "Add supporting documents". It contains the following fields:

- *Title: An input field.
- *Document type: A dropdown menu set to "Select one".
- *File/Link: An input field with a "SELECT FILE..." button to its right, which is highlighted with a red box.
- Notes: A text area with a character limit of 200, containing the placeholder "Type message here".

At the bottom are two buttons: "Cancel" and "Add".

When you add a supporting document type of Proposal and subtype From vendor, you can optionally select a contract from a list of all vendor contracts on the issue and then select from a list of all vendor change orders associated with the contract. This lets you specify the contract and vendor change order that is related to the supporting document and visibility to the contract associated with the proposal. The document is then visible in InEight Contract as read-only on the main Supporting document register and the contract's Supporting Document tab. If a VCO association to a contract is made, the supporting document also shows in the Contract or VCO supporting document page.

The action Contract takes depends on the action taken in Change:

- When you add a pricing item without a VCO ID to the Vendor section of the pricing summary and then add a supporting document with type Proposal and subtype from vendor, a new field, Vendor Change order ID is shown in the New supporting document dialog box. If you click Add without adding the VCO ID, the document is added to the contract's Supporting documents page and the main Supporting documents page in Contract. See "Pricing" for information about adding pricing items.

- When you create a new VCO from the pricing item, a vendor ID is associated to the pricing item. When you add a new supporting document Proposal from vendor, you can select the VCO ID. When you add the document, it is added to the VCO's Supporting documents page, the Contract's supporting documents page, and the main Supporting documents page in Contract.
- When no contract ID is entered, Change sends the proposal to Contract. The document shows in the Contract main Supporting document register until you add a contract ID in Change.

The document is read-only in Contract because it came from Change. If the documents are updated in Change, the changes will show in the document in Contract. For example, if you change title, Contract updates the title. If you change the document type or subtype, Contract deletes the document.

You can upload a saved supporting document to Document from Change, so you do not have to load it in Document, and then link it back in Change.


Upload a document to Document

Upload a supporting document to Document when you want to take advantage of Document's organization and versioning features.


Only documents with the document source *My computer* can be uploaded.

Single-sign on is available for Change to Document features, such as creating mail or a form. When you use one of these features, the Document sign-on page opens, and you can enter your credentials. This creates a sign-on token that lets you remain signed in until the session ends. The first time you sign in to Document, a black secondary window and the Document Home window also open. You can close these windows. Single sign-on is activated, and they are not shown again.

- From the Supporting documents register, select a document with the document source *My computer*, and click the **Upload** icon.



- If you are not already signed into InEight Document, use your credentials to sign in to **InEight Document**.




A sign-in token is created that lets you remain signed in to Document until the session ends. If this is the first time you are signing in to Document from Change, a black secondary window and the Document Home window are shown. After you close these windows, single sign-on (SSO) to Document is activated, and they are not shown again.

The Upload window in the Documents module of Document opens with the document you selected in Change already attached.

3. If you want to add more documents, you can add them at this time.
4. Click **Save and Transmit**. The document is now saved in the Document Documents module.
5. Close the Document window. Change shows the Edit supporting document dialog box. The file link is replaced with the document link from Document.
6. Click **Save**. The Supporting documents register refreshes with the file link to the Documents module. The Document source is replaced with InEight Document, and the External document type and status are now populated.

4.7.1 Show supporting documents in generated documents

A toggle on the Supporting documents register, Show in generated document, lets you indicate whether the document is shown in a collection table based on the collection table type. When you have a supporting document that you do not want to show in a collection table in a generated document, set the toggle to *No*. When a document is generated, only the documents that were set to *Yes* are shown.



The screenshot shows a table with columns: Current value, Cost, Billing markup, Markup, Margin, Deductions, Net value, PCO status, Pricing status, and Proposal status. Below these are tabs for DETAILS, PRICING, SUPPORTING DOCUMENTS (which is selected), and WORKFLOW ASSIGNMENTS. At the bottom are buttons for Start approval, Reject, and Approve. The main table has columns: Title, Document type, External document ty..., External document st..., Document source, Added on, Original issue, Executed Change ord..., DocuSign status, Approval status, and Show in generated document. The 'Show in generated document' column contains checkboxes, many of which are checked and highlighted with a red border.

A document that is available at more than one level, such as an issue-level document available on the issue, PCO, and CCO Supporting documents pages, can have a different setting at different levels. For example, you might set the toggle at the issue level to *Yes* to show in a generated document. You could set the toggle at the PCO level for the same document to *No* to not show in a PCO document. Change uses the setting that corresponds to the level of the collection table tags in the template. Using the previous example, Change shows the supporting document in a collection table as follows:

- When you generate a document for an issue, the document is shown because the only collection table type in an issue document is an issue table.
- When you generate a document for a PCO that has an issue-level collection table, the document is shown because it is part of an issue-level collection table.
- When you generate a document for a PCO that has a PCO-level collection table, the document is not shown, because the document is suppressed at the PCO collection table level.

4.8 VIEW A SUPPORTING DOCUMENT

To view a supporting document, click the link in the File/Link column of the Supporting documents register. The document opens a preview in a new tab, so you can view the pages of the document and then decide if you want to download it to your workstation. You can use the **Previous** and **Next** buttons to view all pages.

Date	Time	Temperature	Weather condition	Wind	Precipitation
04/05/2023	12:30 AM	20°C, 67°F.	clear sky	0 m/s, 0.00 mph	
04/05/2023	01:30 AM	22°C, 71°F.	clear sky	3.6 m/s, 8.00 mph	
04/05/2023	02:30 AM	22°C, 72°F.	clear sky	6.17 m/s, 14.00 mph	
04/05/2023	03:30 AM	20°C, 68°F.	clear sky	8.75 m/s, 20.00 mph	
04/05/2023	04:30 AM	14°C, 58°F.	clear sky	11.32 m/s, 25.00 mph	
04/05/2023	05:30 AM	11°C, 51°F.	clear sky	9.26 m/s, 21.00 mph	
04/05/2023	06:30 AM	7°C, 44°F.	scattered clouds	12.86 m/s, 29.00 mph	
04/05/2023	07:30 AM	5°C, 41°F.	broken clouds	10.29 m/s, 23.00 mph	
04/05/2023	08:30 AM	4°C, 39°F.	overcast clouds	8.23 m/s, 18.00 mph	
04/05/2023	09:30 AM	3°C, 38°F.	overcast clouds	10.29 m/s, 23.00 mph	
04/05/2023	10:30 AM	3°C, 37°F.	overcast clouds	11.83 m/s, 26.00 mph	
04/05/2023	11:30 AM	2°C, 35°F.	broken clouds	10.8 m/s, 24.00 mph	
04/05/2023	12:30 PM	2°C, 35°F.	overcast clouds	8.75 m/s, 20.00 mph	
04/05/2023	01:30 PM	1°C, 34°F.	broken clouds	9.77 m/s, 22.00 mph	

To download the document to your workstation, click **Download file**.


4.9 CREATE AN RFI FORM IN INEIGHT DOCUMENT

You can create an RFI form in the InEight Document Mail module from an issue. Document saves the form and creates a link in the Change Supporting documents tab.


Create an RFI Form in InEight Document.

Single-sign on is available for Change to Document features, such as creating mail or a form. When you use one of these features, the Document sign-on page opens, and you can enter your credentials. This creates a sign-on token that lets you remain signed in until the session ends. The first time you sign in to Document, a black secondary window and the Document Home window also open. You can close these windows. Single sign-on is activated, and they are not shown again.


1. In the Supporting Documents tab of an issue, expand the Actions drop-down menu, and then select Create document > Form.
2. Select **Request for Information** in the pop-up window.



- The Create new form window will open showing available forms




3. If you are not already signed in to InEight Document, use your login credentials to sign in.




A sign-in token is created that lets you remain signed in to Document until the session ends. If this is the first time you are signing in to Document from Change, a black secondary window and the Document home window are shown. After you close these windows, single sign-on (SSO) to Document is activated, and they are not shown again.

4. After the New Request for information window opens, complete the form.




The screenshot shows the 'New Request For Information' window. At the top, there are buttons for 'Save', 'Complete Action', 'Print', 'Close', 'More', 'Configure Workflow', and 'Select Reviewers'. The status is set to 'Outstanding'. The main area is titled 'Details' and contains fields for 'Subject' (RFI No.), 'Message' (a large text area), and dropdowns for 'Discipline', 'Area', and 'Location'. The 'Subject' field is empty, and the 'Message' area is also empty.

5. When completed, select the users for distribution of your form.




The screenshot shows the 'Workflow Distribution' window. It has a dropdown menu labeled 'Distribution' with the option '--Select Workflow Distribution--'. Below the dropdown is a list of users: 'Chad Test', 'Contract', 'Matt / Aaron' (which is highlighted with a gray background), 'QA Team', and 'UAT TEST'. A cursor arrow is pointing at the 'Matt / Aaron' entry.

- A Notification of success appears.



- This allows you to go into Document from Change and grab a pre-defined form, fill out the information, save, and complete.
- In the Add Supporting documents window, a link to the form you just completed, appears.



- Under the Request for information window, this form now appears with a status of **Outstanding**.
- You access this file in Document by selecting its title.

Request for information

RFI No.	Title	Status
KIEWITTEST-RF...	<u>test</u>	OUTSTANDING

If Create document > **Form** is inactive, you can select the cogwheel  icon to set up integration with InEight Document.

You are then taken to InEight Document's Forms module to fill out the form. If you save and complete the workflow, the new RFI populates the Request for information box in the Details tab of the issue.

You can see issues with attached RFIs in the References column of the Issues log register. If there is an RFI associated with the issue, the column shows the number of associated RFIs. Click on the link in a cell for more information about the RFIs and links to the files.


4.10 CREATE MAIL IN INEIGHT DOCUMENT

You can create mail in the InEight Document Mail module from an issue. Document saves the mail and creates a link in the Change Supporting documents tab.

Create mail


Single-sign on is available for Change to Document features, such as creating mail or a form. When you use one of these features, the Document sign-on page opens, and you can enter your credentials. This creates a sign-on token that lets you remain signed in until the session ends. The first time you sign in to Document, a black secondary window and the Document Home window also open. You can close these windows. Single sign-on is activated, and they are not shown again.

1. From the Details page go to Actions > Create document > **Mail**.
2. If you are not already signed into InEight Document, use your login credentials to sign into **InEight Document**.



A sign-in token is created that lets you remain signed in to Document until the session ends. If this is the first time you are signing in to Document from Change, a black secondary window and the Document Home window are shown. After you close these windows, single sign-on (SSO) to Document is activated, and they are not shown again.

3. The Create Document Mail dialog box opens. Select the mail type from the list defined in Document that are specific to the project's mail type, and then click **Next**.



4. Optionally add an attachment. If documents were previously selected on the Supporting documents page, they are already selected in the dialog box.
 - To add an attachment from the Supporting documents tab, click **Next**. The **Select documents** dialog box opens. You can choose documents from the Supporting documents tab with the Document source *My computer*. After you attach the documents, click **Create**. The Mail module opens in Document with your attachments included.
 - To add an attachment in Document, click **Create**. The Mail module opens in Document. Click **Attach files > Attach Documents**, where you can search for the document. After you select a document, click **Save**.
 - To send mail without an attachment, click **Create**. The Mail module in Document opens.
5. Enter information in the **To** and **Subject** fields. The other fields on the page are optional. Enter or update the fields as needed for the mail message, and then click **Send**. A summary page opens.
6. Edit links and notes, if needed. The mail is added in Document.
7. Close the Document window. You are then prompted to add the mail as a supporting document in Change. The document type defaults to Correspondence but can be changed.
8. Click **Save** to save the mail to the Supporting documents page.

4.11 PACKAGE SUPPORTING DOCUMENTS


When you have multiple related documents, you can package them into a single document, so you do not have to download each document separately and combine them outside of Change. You can use packaged documents to send to InEight Document or send out for electronic signature.

Package supporting documents

You can package documents when you want to combine multiple documents into a single document.

Documents must be in Microsoft Word or Excel, PDF, or image format and come from the document source My computer to be added to a package.


1. From the Issue, Potential Change Order, or Client Change Order log, select multiple documents, and then click the **Package documents** icon.




Actions	Title	File/Link	Document type	Subtype	External document t...	External document s...	Document source	Added on	Subordinate Issue
<input type="checkbox"/>	Spanish pricing summary	355_Spanish pricing su...	Other				My computer	02/06/2023	
<input type="checkbox"/>							InEight Document	02/06/2023	
<input checked="" type="checkbox"/>	doc 3	testDoc.xlsx	Correspondence	Client			My computer	02/06/2023	
<input type="checkbox"/>	doc 2	Strums.png	Checklist	Change proposal prepar...			My computer	02/06/2023	
<input type="checkbox"/>	doc 1	package_doc_1.docx	Certification				My computer	02/06/2023	

The Package supporting documents dialog box opens to the Selected documents step.

2. You can select additional eligible documents to be in the package or reorder the documents in the package.



3. Click **Next** to go to the Package document details step.
4. Enter the title, document type, file or link name, and notes. The File/Link name field defaults to the value you enter in the Title field, but you can change it.



5. Click **Save** to save the package as a PDF in the Supporting documents register.

4.12 MAIN AND SUBORDINATE ISSUES


Main issue adds flexibility within the tool to be able to group issues together and get a roll-up cost of all the associated issue. The grouped issues are subordinate issues to the main issue. They can be created within an issue or move an existing issue as a subordinate issue. This feature also provides the flexibility of seeing a roll-up cost of specific issues that can be tied to separate PCO/CCOs.

You can create main and subordinate issues in the following ways:

- Convert standard issue into a main issue with subordinate
- Add subordinate to main issue
- Make an existing issue into a subordinate of a main issue


Convert a standard issue into a main issue with a subordinate

1. Go to the Change > Issue Log tab.
2. Select an issue and then select the Subordinate issue icon.




	Issue ID	PCO ID	Client CO ID	Issue na
	9			Bearing
	7			Bearing
	7.2			7.2

3. Select Create subordinate.



- The following box appears, indicating that a main issue is being created and the standard issue becomes the first subordinate issue.



4. Select Yes.

- The standard issue is now a subordinate issue and a main issue has been created

	Issue ID	Client CO ID	Issue name	Issue start date
	9		Bearing Pad...	09/03/2019
	9.1		Bearing Pad...	09/03/2019

- The main issue becomes a rollup of all subordinate issues. The row becomes disabled as it is a summary of the subordinate issues

	Issue ID	Client CO ID	Issue name	Issue start date	Issue stat...	Assigned to	Balf in court	Balf in co...	Written n...	Daf
	9		Bearing Pad...	09/03/2019	Open					
	9.1		Bearing Pad...	09/03/2019	New					-4

- In the Main issue details, only Name and Description are editable. Subordinate issues are all shown. On the details page, you can add or remove a subordinate from the main issue


- Pricing is a read-only summary of the subordinate pricing

- Supporting documents shows supporting documents of all subordinate items

Add a subordinate to a main issue

- In the project you have been using, navigate to Change > Issue Log tab.
- Select the main issue and then select the Subordinate issue icon.


3. Select **Create subordinate**.



The screenshot shows a table titled 'ISSUE LOG' with three columns: 'Client CO ID', 'Issue name', and 'Issue start date'. There are three rows of data. A context menu is open over the first row, with the 'Create subordinate' option highlighted by a red box. The menu also includes 'Make as subordinate'.

Client CO ID	Issue name	Issue start date
	Bearing Pad...	09/03/2019
9.1	Bearing Pad...	09/03/2019
7	Bearing Pad...	09/02/2019

- The Create subordinate issue window opens



The dialog box is titled 'Create subordinate issue'. It contains the following fields:

- *Subordinate issue name: A text input field with a hint: 'Type name of subordinate issue'.
- *Issue start date: A date input field set to '09/09/2019' with a calendar icon.
- Issue ID/Issue name: A text input field containing '9 - Bearing Pads 3'.
- Description: A text input field containing '1000'.

At the bottom are 'Cancel' and 'Save' buttons.

A subordinate issue comes in as a new issue.

4. Fill in the required fields to complete this window.

5. Select **Save**.

- The subordinate issue will open its own record to be completed with the proper information.

Subordinate issue description

Subordinate of issue [9 - Bearing Pads 3](#) Created by Susan cappelloni on 09/03/2019

*Subordinate issue name: Bearing Pads 3

*Issue start date: 09/03/2019

Description: 1000

Source/cause: None

Change condition: None

Scope: None


Assigned to: (empty field)

Change orders


- Assign to potential change order
- Convert to client change order

Make an existing issue into a subordinate of a main issue

1. In the project you have been using, navigate to Change > Issue Log tab.
2. Select the main issue and then select the Subordinate issue icon.
3. Select **Make as subordinate** from the list.



- The Make as subordinate issue window opens



4. Select Issue ID/name to choose which Standard issue or Main issue this issue should be a subordinate of.
5. Click **Save**.
 - The issue becomes a subordinate issue

The Issue ID number changes from original issue number to a subordinate and is logged in the Audit log. If this subordinate is ever removed from the main issue, it reverts to its original Issue ID number.

4.13 ISSUE IMPORT

A convenient way to add multiple issues is through import using the issue import template. The issue template includes the fields found on the issue Details page.


You can also export existing issues, make changes, and reimport the data.

4.13.1 Import the template

From the Issue Log, click the **Import** icon to begin downloading.

Issue Log										Audit Log																									
Actions		Issue ID		PCO ID		CCO ID		Issue name		Issue start date		Issue stat...		Assigned to		Approval ...		Responsi...		Responsi...		Value type		Current value		Pricing st...		Date price...		Proposal ...		Scope		Supportin...	
<input type="checkbox"/>	263							test_1		01/13/2022	New			Approved	***							\$0.00													
<input type="checkbox"/>	264							test_2		01/12/2022	New			Approved	***							\$0.00													

The Import data from template dialog box opens for you to import and save the template or for you to drop a completed template to be uploaded.



The template is an Excel spreadsheet. The first worksheet contains the Instructions for the template. Here is where the legend and guidelines are located. The guidelines describe the information on the Import template, exporting with data, and how to update or add more information to the existing data. The second worksheet, Template, is where you enter your data for the issues. Drop-down fields are populated from the organization and project settings. The only required fields are Issue name and Issue start date. It is recommended to download a new template each time you import, so the fields and field values are current. The columns are color coded to indicate which columns are system generated, required data, optional data, and ignored data.

System	System generated
REQUIRED	Field is required for import
OPTIONAL	Field is optional for import
IGNORED	Field not to be populated

After you add your information and save the worksheet, you can import it.

Change validates the dates based on the person who imports the data. If the dates do not match the preferences of that person, Change generates an error in the import history and deletes the date. You must then enter the dates manually before you can complete the import.


Do not change the names of the spreadsheet tabs.

Import issues

Import issues into Change when you want to quickly add multiple issues to the Issue log.

The import template reflects the fields on the Issue Details page. It is recommended to download the template each time you want to import issues, so the fields and field values are current.

1. From the Issue log, click the **Import** icon. The Import data from template dialog box opens.



2. Click **Import issue template** to download the template.
3. Open the Microsoft Excel template file, and then enter the issue information on the **Template** worksheet. Do not change the name of the **Template** worksheet.
4. Click the **Save** icon at the top of the **Template** page.
5. Drag and drop or browse for the file to move it to the import data from template dialog box, and then click **Import**. The data is imported, and the results are sent to you in an email message when completed.
6. Open the email to view the results.
 - If the status is *Complete*, the issues have been added successfully. If you want to review the import you can click **Review data** to see a summary. The Import history page opens, and the process is complete.
 - If status is *Pending*, click **Review data**. The import history page opens. All errors are flagged with a warning icon.
7. Correct any errors and make any other changes as needed. After you have corrected or updated all fields, click **Import**.
8. The import is reprocessed, and the results are sent to you in an email message when completed. If you want to see a summary, you can click **Review data**.

What's next: If workflow is turned on, issues come into Change with the status *In approval*, and they do not get issue IDs until they are approved; the issue ID is *Pending*. Workflow emails are sent for each

new issue included in import. If workflow is turned off, issue IDs are assigned upon import, and the status is *Not applicable*.

4.13.2 Import issues through an API

You can import issues into Change using the Create Issues API. The API lets you consolidate all issues in one place by importing issues in bulk or connecting to a third-party issue creation tool. For additional information about the Create Issues API, refer to the API documentation in [Resources > APIM Documents](#) and the [InEight API Developer Portal](#).

4.13.3 Export the template with data

The export with data function lets you make changes to multiple issues by exporting the data to an Excel template and then reimporting.

Click the **Export** icon, and then select **With data** to download a template. You can then make your changes and then follow the procedures to import the issues.

4.14 SPLIT ISSUES

At times, you may have an issue that affects multiple lines of work, where it makes sense to split the issue, so you can track the work more efficiently, effectively price it out, and view the impacts.

For example, the owner requests new access to a building and an issue is created. This involves rework to the asphalt design, railing, and structure designs, so you decide to split the issue into several issues to track each set of reworks separately.


The Split issue function is used to create multiple issues from one existing issue. When an issue is split, the original issue is reidentified as X (Original) with subsequent splits being named X (B), X (C) etc. (where X is the Issue ID number).

When a split is made, only issue details, supporting documents, associated vendors and status are copied. Pricing values in the Pricing tab are not copied

The following steps walk you through how to split an issue into multiple issues.

Split an Issue

1. From the Change page, on the Issue Log tab, select the check box for [your initials] – Bearing Pads.



PENDING ISSUES					3	ISSUE LOG
	Issue ID	PCO ID	Client CO ID	Issue name		
<input type="checkbox"/>	38			PT-Bearing Pads		
<input checked="" type="checkbox"/>	37			PT - Bearing Pads		
<input type="checkbox"/>	36 B	PAT001	Client Chang...	PAT - Bearing Pads (B)		


- The Split issue icon becomes available

2. Select the Split issue icon.



PENDING ISSUES					3	ISSUE LOG
	Issue ID	PCO ID	Client CO ID	Issue name		
<input type="checkbox"/>	38			PT-Bearing Pads		
<input checked="" type="checkbox"/>	37			PT - Bearing Pads		
<input type="checkbox"/>	36 B	PAT001	Client Chang...	PAT - Bearing Pads (B)		

- The Split issue window appears



Split issue

*Total number of issues needed

Why are you splitting this issue? 400

Cancel Split

3. Type 2 in the Total number of issues needed field to split the issue into two issues.
4. In the Why are you splitting this issue? field, type New bearing pad locations clash with deck penetrations.
5. Click Split.
 - On the Issue Log tab, your Bearing Pads issue is now two issues, parts A and B




	Issue ID	PCO ID	Client CO ID	Issue name
	38			PT-Bearing Pads
	37 B			PT - Bearing Pads (B)
	37 A			PT - Bearing Pads (Orig...)
	36 B	PAT001	Client Chang...	PAT - Bearing Pads (B)

- Note that while your original issue maintains its pricing details, your new issue's pricing needs to be defined

With your issue now split in two, the following Step by Step walks you through adding details to the new issue, this time entering values at the Estimate level.


Add details to a split issue

- From the Change page, on the Issue Log tab, open the Bearing Pads (B) issue you created in the previous step.



	Issue ID	PCO ID	Client CO ID	Issue name
<input type="checkbox"/>	38			PT-Bearing Pads
<input checked="" type="checkbox"/>	37 B			PT - Bearing Pads (B)
<input type="checkbox"/>	37 A			PT - Bearing Pads (Orig...)

- The Bearing Pads (B) issue record opens
- Note the Details tab contains all the information from the original Bearing Pads issue
- You have easy access to the other issues related to the split under the Split issue section



Issue description

Created by paul trippi on 06/26/2019

*Issue name	*Issue start date
PT - Bearing Pads (B)	06/26/2019
Hint: Date of the start of impact	
Description	904
Installed bearing pads do not match pad locations on turbine generator. This is a high priority.	
Source/cause	Change condition
None	None
Hint: Select what prompted the source/ca...	

Change orders

- Assign to potential change order
- Convert to client change order

Split issue

- 37 A - PT - Bearing Pads (Original)

- Select the Pricing tab.
- Complete the Estimate fields with the information below (issue is not required to have ROM values completed):
 - Estimate Self perform subtotal for Small tools & Supplies: \$10,210
 - Estimate Markup subtotal (create a new markup): \$1,021

- This is a 10% Markup on your directs

Pricing summary	ROM	Estimate	Proposed	Agreed CO	Contributed...
Self perform subtotal	\$11,231.00				
Labor					
Equipment					
Materials					
Small tools & supplies		\$10,210.00			\$10,210.00
Markup (Small tools & supplies 10.00%)				✖	\$1,021.00

4. Add a vendor by selecting the Add vendor icon.
5. In the Estimate column for the newly created vendor, type 3,500.

Pricing summary	ROM	Estimate	Proposed	Agreed CO	Contributed values
Self perform subtotal	\$11,231.00				
Labor					
Equipment					
Materials					
Small tools & supplies		\$10,210.00			\$10,210.00
Markup (Small tools & supplies 10.00%)				✖	\$1,021.00
Vendor subtotal					\$3,500.00
Merrill Iron & Steel Inc - 7400001253	✍		\$3,500.00	✖	\$3,500.00

6. In the Client pricing narrative text box, type Contractor agreed to re-use existing penetrations, pricing is for labor only. If additional material is needed contractor will submit a cost-plus invoice to client.

Client pricing narrative

336

Contractor agreed to re-use existing penetrations, pricing is for labor only. If additional material is needed contractor will submit a cost-plus invoice to client.]

7. Click Save.

If you have ROM / Estimate values entered in the original issue before splitting the issue and enter ROM / Estimate values in the newly created split issue B, you may need to adjust the ROM or Estimate values on the original issue as it will still have the pricing for the entire issue.

4.15 COST ITEM PRICING

Cost item pricing lets you build an estimate using existing cost items from InEight Control or unassigned items and then calculate an adjustment value based on an adjusted quantity using existing current budget or current estimate rates. You can also associate a cost item to a vendor change order. This provides easier estimating and continuous contract adjustment in Control and gives visibility into how the estimates were derived. Refer to the Control documentation for more information about cost items.

Cost item pricing is available at the issue level only.

Upon execution of a CCO, the cost pricing information goes to Control as a contract adjustment. Assigned cost items automatically populate the contract adjustment to provide a more continuous experience. Refer to the Control documentation for more information about budget and revenue details from Change.

To access cost item pricing from an issue, click the **Pricing** tab.

4.16 PRICING TAB

The Pricing tab lets you add cost items to help you price the labor, equipment, and other expenses related to resolving the issue.

VIDEO | Cost Item Pricing

The Pricing tab includes the following tools to help you complete the task.

Title		Description
1	Filter	Filters the grid by the selected value. You can filter as many columns as needed.
2	Clear all filters	Clears all filters in the grid.

Title		Description
3	Group columns	Lets you show cost items grouped by cost pricing type, UOM, or pay item. For more information on column grouping, see Pricing page organization tools .
4	Manage columns	Lets you select the columns and their order in the grid. For more information about column management, see Pricing page organization tools .
5	View project contract summary	Opens the Project contract summary slide-out panel that shows a view of the current project value, projected project value, milestones, and allowance category.
6	Add supporting document	Opens the Add supporting documents dialog box that lets you attach a document.
7	Row density	Lets you choose the density of the rows from relaxed for easy viewing, narrow, and tight to maximize the number of rows you can see at a time.
8	Import	Imports cost items from other sources. For more information about importing cost items, see Import cost items .
9	Export to Excel	Exports the cost item pricing into a Microsoft Excel spreadsheet.
10	Add note	Lets you add a note about the pricing.

4.17 PRICING PAGE ORGANIZATION TOOLS

You can use the column grouping and column management features to customize the grid, so you can organize cost items for your business needs.

4.17.1 Group by column


When you add items to the Pricing page, they are added sequentially without grouping into categories. Use the Group columns feature to show columns grouped by cost pricing type, UOM, or pay item.

Group cost items by column on the Pricing page


Summary: Group by columns on the page when you want to see the cost items grouped by cost item type, UOM, or pay item, instead of sequentially.

Considerations: You can group by one column at a time. If you want to change the grouping, you must remove the column from the grouping area before adding a different column header.


1. From the pricing page, click the **Group columns** icon. The grouping area (a gray bar) shows above the column headings.



2. Drag and drop the column header for the Cost pricing, Pay item, or UoM column to the grouping area. The image below shows the Cost pricing column header.




The cost items show in labeled groups, including counts of the cost items in each group. The following image shows the cost items grouped by cost item pricing type.



What's next: You can use column filtering as needed to narrow the cost items in the grid.

4.17.2 Column management

Use the Column section builder to select and arrange columns in the Pricing page grid to show only the columns you need. To access the Column section builder, click the **Manage columns** icon in the toolbar.



The screenshot shows the Column section builder dialog box. The 'Available columns' panel on the left lists various fields like 'Column name', 'Added by', 'Added date', etc. The 'Selected columns' panel on the right lists fields like 'Column name', 'Cost item description', 'WBS phase code', 'Adjusted Mhrs', 'Adjusted CB Qty', 'Cost source', etc. A red box highlights the directional arrows (right-pointing and left-pointing double arrows) used for moving columns between the two panels. The main Pricing page grid is visible in the background, showing a list of items with columns for 'Billing rate markup', 'Billing rate markup %', 'Cost pricing', 'Labor', 'Equipment', 'Materials', and 'Grand Total'.

The Column section builder lets you arrange columns by either using the directional arrows or with drag-and-drop editing. Transfer all to and Transfer all from directional arrows let you move all fields between the Available columns and Selected columns panels. You can use the drag-and-drop feature to move columns to and from the Selected columns panel and to change the column order. The Cost item description and WBS phase code columns are in the locked columns section. You can change the order of these columns within the locked section, but you cannot remove them from the locked section. You can drag and drop additional fields to the locked section or remove them as needed.

To return to the original layout, click the **Reset to default** button at the bottom of the Column selection builder.

You can also drag and drop columns if you need to arrange columns quickly without using the Column section builder.

4.18 ADD A COST ITEM

You can add an existing or new cost item. The cost item can be one of the following types:

- Plug – Unit and total costs are entered at the cost category level
- Detail – Resources are defined to determine costs

An existing cost item has already been established in InEight Control. When you add an existing cost item, details are pulled from Control. When you add a new cost item, you must add the detail information, such as UoM and a pay item. The detail information is added in Control when the CCO is executed and approved in Control. See [Edit cost items](#) for information about the types of details that can be edited for existing and new cost items. The number of cost items you can add is not limited in an issue. However, if you convert the issue to a change order or use it in a budget move, you are limited to 250 unique cost items or 100 unique pay items.

You can also add an unassigned pricing item that does not have a cost item associated to it. An unassigned item has lump sum cost pricing by default.

You can use the icons in the left toolbar to add, edit, delete, or copy cost items. You can also right-click in the grid to get a context menu with the same options. You can also import new plug items from a Microsoft Excel spreadsheet into cost item pricing.

The fields that are available for you to add values to and edit depend on the cost item type and the unit rate driver. See [Edit cost items](#) for information about editing plug and detail cost items.

Add an existing cost item

Add cost item pricing when you want to add detail to your pricing. Cost items are based on the CBS structure from Control. The unit rate driver for an existing cost item defaults to the current estimate. You can edit the unit rate driver after the cost item is added.


Only active terminal cost items are available for selection in cost item pricing.

- From the Cost item pricing page, click the **Add cost item pricing** icon.



Actions	DETAILS	PRICING	PRICING SUMMARY	SUPPORTING DOCUMENTS
<input type="button" value="Add existing cost items"/>				
<input type="button" value="Add new cost item"/>				
<input type="button" value="Add from template"/>				
<input type="button" value="Add Unassigned pricing item"/>				
<input type="checkbox"/> Cattle Guard RM	WBS phase code 1010	Adjusted CB Qty Enter adjusted qty	Adjusted Mhrs 0.00	Adjusted billable amou... \$ 0.00
<input type="checkbox"/> 1014				Adjusted cost \$ 0.00
				Billing rate markup \$ 0.00
				Billing rate markup % 0.00%

- Select **Add existing cost items**. The Add cost item pricing dialog box opens with the CBS structure from Control. The cost items use the same color coding as they do in Control.
- Select a cost item from the Select cost items section of the Add cost item pricing dialog box. Available cost items have the **Add** icon. Parent WBS codes have a selection box that automatically selects all the cost codes underneath it. You can use column choosers to select the columns you need to identify the cost item. You also can remove items you do not want to see. The cost item is added to the Select cost pricing pane, and the entry in the Select cost items section is dimmed.



Add cost item pricing

Select cost items

Select cost pricing

CBS position	Description	WBS	Account codes
1	Financial Res...	1000	
1.1	Financial Res...	1001	
1...	Direct Labor	1002	
...	Civil	1003	
+	Maintain Build...	2308	50.98.99
...	MOT (Install &...	1004	
+	MOT Labor - ...	1005	54.02.04
+	Flagger Crew - ...	1007	54.02.04
...	Environmental...	1008	

Description	WBS phase code	Cost
216th Fascia - Fab Forms ...	1184	Selected
216th Fascia Walls - F/P/S ...	3204	Selected
Maintain Buildings During ...	2308	Selected

Selected : 3

Create template

Cancel

Add

Repeat this step for each cost item you want to add.

- Assign the cost pricing category (for example, labor or materials) by selecting the cost item in the Select cost pricing section, and then choosing one of the options in the Cost pricing column. If there are multiple cost items that are in the same category, select them, and then click **Group cost pricing**.

After all cost items have a pricing category, the **Add** button becomes available.

- Click **Add**.

Change pulls the following fields from Control:

- WBS
- Description
- UoM
- Forecast (T/O) qty
- Current CB Qty
- Mhrs/Unit
- Unit/Mhr
- Unit cost
- Cost source
- Resources
- Billing rate markup % (Calculated based on resource billing rates for cost source detail cost items that have resources assigned with billing rate markups)

6. If you have the pricing information, enter a value in the Adjusted CB Qty column. Change calculates the values for the Adjusted cost, Updated CB qty, and Adjusted man-hours fields, if applicable, based on the current budget or current estimate rates. The value you enter in the Adjusted CB Qty field cannot make the value in the Updated CB Qty field less than zero. Each cost item defaults to current budget rates. If you change the Unit rate driver field from current estimate to current budget, Change calculates the adjusted cost and adjusted man-hours based on those unit rates. If you do not have the pricing information you can automatically calculate values to get adjusted values from Control. See [Auto calculate cost items](#) for information about automatically calculating cost items.

If a cost code is assigned to only one contract, Change automatically brings in that contract association, so you do not have to look for the contract. The cost pricing defaults to *Vendor*, but you can change it. After the cost item is added, Change automatically assigns the cost item to the vendor and contract number. The vendor is editable.

A negative quantity can be entered if it is smaller than the Current CB Qty column. You can use negative numbers in deductions so that Change calculates a true negative deduction.

7. Click **Save**. The cost items are added to the Cost item pricing page and the Pricing summary page.


The cost items can be edited from the Cost item pricing page. When you edit the description, it is shown in the Cost item pricing grid, but is not carried over to InEight Control. The cost items are read-only on the Pricing summary page.

Add a new cost item

Add a new cost item when you want to add detail to your pricing, but the pricing item does not exist in Control.

If you are adding a plug cost item, the adjusted cost is driven by the values in the Details tab. After the adjusted cost is calculated, the Cost categories tab shows a breakdown. If you are adding a detail cost item, the adjusted cost is calculated using the resources on the Resources tab.

1. From the Cost item pricing page, click the **Add cost item pricing** icon.



2. Select **Add new cost item**. The New cost item slide-out panel opens.
3. Enter the description, and then indicate whether the cost item has a cost source of Plug or Detail.
4. Enter the cost item information on the Details page.
 - If the cost source is Plug, you can enter information in any of the fields.
 - If the cost source is Detail, you can enter information in the Description, Adjusted CB Qty, UoM, and Cost pricing fields only. The value you enter in the Adjusted CB Qty field cannot make the value in the Updated CB Qty field less than zero. The other fields are populated

after you have added resources on the Resources tab.

5. Click **Apply**. The pricing item is added to the Cost item pricing grid.


You can edit the cost item to add more information regarding resources or cost categories. After the CCO is executed, you can see the newly created cost item in the Control contract adjustment. When the contract adjustment is approved in Control, a WBS phase code is assigned. You can see the WBS phase code in the CBS and the WBS number is reflected in the executed issue cost item pricing.

The cost item cost category in Control corresponds to the cost pricing section in Change the item was assigned to. If there are any man-hours on the new cost item, that portion of the value is allocated to the Labor cost category, and the remaining value to the category mapped to the cost pricing selected.


Add an unassigned pricing item

Add a pricing item that is not assigned to a cost item in InEight Control.

1. From the Pricing page, click the **Add cost item pricing** icon, and then select **Add unassigned pricing item**. The Add unassigned pricing item slide-out panel opens.



2. As a default, the Cost pricing is set to Lump sum adjustment. To change the cost pricing category, select a new option from the drop-down list.




3. You can optionally enter a description of the pricing item, the adjusted quantity, unit of measure, adjusted cost, adjusted man-hours, and value type (ROM, Estimate, Agreed, Proposed).
4. Click **Apply**. The pricing item is added to the Cost item pricing grid.

4.19 EDIT COST ITEMS

If you want to add more detail for a cost item, select the item, and then click the **Edit cost pricing summary** icon. The Edit slide-out panel includes tabs for details, cost categories, and resources.

4.19.1 Cost item details

The Details tab lets you edit the adjusted quantity and other information or the cost item. When the Cost source is Plug, you can edit the adjusted cost. The Details tab also lets you view adjusted man-hours pay item information for existing cost items.



When the Cost pricing field is set to Vendor, you can assign a vendor to the cost item. To assign a vendor, expand the drop-down list in the top right corner, and then choose a vendor.

4.19.2 Cost categories

The Cost categories tab shows the adjusted cost distributed across the cost categories. You can see the adjusted cost, billing rate markup, billing amount, current budget, and current estimate.

When the Cost source is Plug, you can update the adjusted cost, billing rate markup, and billing amount. Updating the adjusted cost affects other calculations. When you update the adjusted cost, Change prompts you to choose whether to adjust the Labor cost/Mhr or Adjusted Mhrs calculation.

4.19.3 Resources tab

The Resources tab shows resources assigned to that cost item in InEight Control. The Resources tab lets you add resources from the Control resources library.

4.20 EDIT PLUG ITEMS

4.20.1 Plug items

When the cost source is *Plug*, you can edit the following fields:

- Adjusted cost
- Unit cost
- Adjusted Mhrs
- Mhrs/Unit
- Unit/Mhr
- Labor cost/Mhr

These fields can be edited only in the Edit cost item slide-out panel. You can edit the Adjusted CB Qty value from the Cost item pricing register.

The fields work interactively. If you change the value of a field, Change calculates the values of the related fields. When you update the adjusted cost and there is a value in the Labor cost category, Change lets you select the Labor cost/Mhr or the Adjusted Mhrs field to be recalculated. When you

update the unit cost, Change calculates the adjusted cost, and then spreads the cost across all cost categories.

If no quantity has been entered, you can enter an adjusted cost. The Mhrs, Mhrs/Unit, and Unit/Mhr fields are disabled. After you enter an Adjusted CB Qty, all fields are enabled. Adjusting the man-hours maintains the Labor cost/Mhr from Control to calculate the overall adjusted cost. After you make a change, the Unit rate driver field changes to Manual. The manual changes are saved as an additional unit rate driver when they are applied and saved to the register.

Initially, the cost item has a unit rate driver value of Current Budget, and you are prompted to enter the Adjusted CB Qty. Afterwards, the adjusted cost uses the productivity rates to calculate the details and Cost Categories tab. Adjusted MHrs, MHrs/Unit, Unit/MHr, and Labor cost/Mhr are used to calculate the total Labor cost category.

The Cost categories tab in the Cost-item slide-out panel shows the assigned cost category assigned to the plug cost item. The adjusted cost is placed into a cost category based on the cost pricing selected. For example, when Cost pricing is Materials, the adjusted cost is shown in the cost category of Materials. You can manually distribute costs across individual cost categories. All cost categories are added together into a Total adjusted cost for the cost item. The name of each Cost category shown in the tab can be modified using custom labels. When you update the Labor cost category, a dialog box prompts you to choose to proportionally adjust the Labor cost/Mhr or the Adjusted MHrs value.

On the Resources tab, you can add or remove resources, but they do not affect calculations.

When the CCO is executed, Control consumes the updated quantity, cost, and man-hours in the Contract adjustment.

4.21 EDIT DETAIL ITEMS

When the cost source is *Detail*, you can edit resources in the Resources section. Each resource has a Cost driver of *Fixed*, *CI Duration*, or *CI Qty* as in Control. Cost driver and resource type determine which fields are editable for any given resource. For example, when the resource has a Cost driver of *CI Duration* exists, the Productivity and overall settings fields becomes editable.

Initially, the cost item has a unit rate driver value of Current budget, and you are prompted to enter an Adjusted CB Qty. After that, the adjusted cost uses the productivity rates, based on the value of the unit rate driver to calculate the values on the Details and Cost categories tabs. The Current budget and Current estimate have their own Productivity rates for Unit cost, Adjusted MHrs, MHrs/Unit, Unit/MHr, and Labor cost/Mhr, and cost category breakdown.

- If the unit rate driver is set to Current Budget, only the Adjusted Qty is used to recalculate productivity rates and cost category breakdown for the current budget.
- If the unit rate driver is set to Current Estimate, only the Adjusted Qty can be used to recalculate Productivity rates and cost category breakdown for the current estimate.

If you add, edit, or delete a resource on an existing Detail cost item, the value of the Unit rate driver field changes to *Manual* to indicate that this cost item is no longer using current estimate resources from Control. The option to return to the Current Estimate value becomes unavailable. The only way to go back to the current estimate is to delete the cost item, and then add it again. Added resources are indicated by a yellow circle to the left of the row number. Deleted resources show with strike-through text. When a Contract adjustment is executed, Control does not consume any resource changes on the existing cost items. This functionality is meant for estimating changes only.

Row#	Code	Description	Quantity	UoM	Work hours	C E-unit cost ...
1	Resource A (L...	Labor resource	5.00	Hour	41.67	\$93.14
2	Resource B (E...	Construction ...	5.00	Hour	50.00	\$890.00
3	Resource C (I...	Installed equip...	5.00	Each	10.00	\$370.00
4	1.C.01.1.01	GF - Laborer ...	1.00	Each	8.33	\$61.67

After you change a value in the Resources section, a blue dot is shown to indicate that someone has changed the value of the resource in Change. If you make changes to the Productivity and overall settings section, a yellow indicator shows the last field that was updated. If the update to the Productivity and overall settings affects resources, the blue dot is shown in resources.

When you undo a resource change, a dialog box prompts if you are sure you want to undo your changes. If you select Yes, the changes are removed, and Change recalculates the cost item. For

example, if you remove an existing resource and then you undo the removal, the strike-through text is no longer shown.

Any manual change on the Resources tab (Resources or Productivity and overall settings sections) changes the Unit rate driver to *Manual*. When the Unit rate driver is *Manual*, the cost item uses the Resources tab to recalculate the cost item.

Each resource has costs distributed across the different cost categories that are shown in the Cost categories tab. For Detail cost items, the Cost category tab is read-only.

4.22 COPY A COST ITEM

You can copy a new or existing cost item, so you do not have to start over when adding a similar item. You can select **Copy** from the context menu or click the **Copy** icon in the toolbar.

You can select a new or existing cost item to copy. Only one cost item can be copied at a time. If you have selected more than one cost item, the Copy cost item option in the context menu is disabled. You cannot copy a copied cost item until it is saved. The copied cost item remains on the register when you click **Save**.

Every copy is treated as a new cost item; therefore, a WBS phase code is not added because it is not yet in InEight Control. The phase code stays blank until the CCO is executed and the contract adjustment is approved.

4.23 COST ITEM PRICING TEMPLATES

4.23.1 Cost item pricing templates

When you have large projects with many cost items, or if you have a group of cost items that you use on a regular basis, you can create a cost item pricing template to quickly add cost items to cost item pricing. After you add an existing cost item, the Manage templates icon is enabled.


Templates are not specific to an issue. You can manage templates from any issue and reuse them.

Create a cost item pricing template from the register

Create a cost item template, so you can quickly add frequently used cost items when pricing an issue.


Only existing cost items can be saved as a template.

1. From the Cost item pricing page, add an existing cost item.
2. Click the **Manage templates** icon, and then select Create template. The Create as template dialog box opens.



The screenshot shows the 'Cost item pricing' page. At the top, there are summary details: Current value (\$40,703,827.12), Cost (\$40,092,669.00), Billing markup (\$2.00), Markup (\$611,156.12), Margin (1.52%), and Deductions (\$6.00). Below these are tabs for 'DETAILS', 'PRICING' (which is selected), and 'SUPPORTING DOCUMENTS'. A red box highlights the 'Actions' dropdown menu, specifically the 'Create template' option. The main table displays cost item pricing details, including categories like 'Labor' and 'Deductions', and specific items like 'Builder's Risk Insurance' and 'Validation- Material' with their respective values.

3. Enter the name of the template, and then select a value from the Sharing field drop-down list to indicate whether the template is private or shared.



The dialog box is titled 'Create as template' and contains the following fields:

- A warning message: **⚠ New cost item will not be saved in template**.
- A required field: ***Template name** (input field).
- A 'Sharing' section with a dropdown menu set to **Private template**.
- Buttons at the bottom: **Cancel** and **Save**.

4. Click **Save**. Change validates to ensure that the template name and shared value is unique. The existing cost item dialog box opens. You can then select and group cost items.


The template can now be used to add cost items when pricing an issue.

Create a cost item template when adding cost items


You can create a template as you add cost items to cost item pricing.

Only existing cost items can be saved as a template.

1. From the Cost item pricing page, click the **Add cost item pricing** button or right-click anywhere in the grid, and then select **Add existing cost items**. The Add cost item pricing dialog box opens.
2. Select one or more cost items, and then group them.
3. Click the **Create template** button. The Create as template dialog box opens.



4. Add the template name and indicate whether the template is private or shared.



5. Click **Save**. Change creates the template, but the items are not added to the grid.
6. Click **Add** in the Add cost item pricing dialog box to add the items to the grid.

The template can now be used to add cost items when pricing an issue.


Add cost items from a template

You can use a template to quickly add cost items when pricing an issue.


1. From the Cost item pricing page, click the **Manage cost item templates** icon, and then select **Manage templates**. The Manage templates dialog box opens.
2. Select a template, and then click **Open template**. The Add cost items dialog box opens.
3. Optionally add or remove items from the **Select cost pricing list**.
4. Click **Add** to add the items to the cost item pricing grid.

4.23.1.1 Manage templates

To manage a template, click the **Manage cost item templates** icon and then select **Manage templates**.



The Manage templates dialog box opens where you can add, edit, delete, and copy templates and send a copy of a private template to another user.



You must have the Edit shared template permission to edit a shared template and the Delete shared template permission to delete a shared template.

When you edit a template, you can only edit one template at a time. If you edit a shared template that you did not create, you must create a new template with a unique name and then save it. You can delete multiple templates at a time. When you delete a shared template, you delete it for all users.

You can copy a template and save it with a unique name.

You can send a copy of a template to another user.

4.23 Step by Step 1 – Send a copy of a template

If you have a template you want to share with another user without making it a shared template for all to use, you can send a copy.

1. From the Cost item pricing page, click **the Manage cost item templates** icon, and then select **Manage templates**. The Manage templates dialog box opens.
2. Select a template, and then click **the Send a copy** icon. The Send copy of template dialog box opens.
3. Enter the name of one or more users, and then click **Send**. The recipients receive a notification in the Notifications area. When they click on the notification, they are taken to the issue log where they can save the template.

4.24 DEPENDENT COST ITEMS

Dependent cost items are cost items with values calculated based on a percentage of the cost of other items. Examples include insurance the company carries, bonds, and labor overhead. The value of the cost item is calculated using the configured percentage and the adjusted billable amount of all items in a section. For example, if you add a dependent cost item that is configured at 2% for the Labor section, and the adjusted billable amount for all labor cost items is \$4000, the dependent cost item value is \$80.

Actions		WBS phase code	Dty	UoM	Adjusted M/Hrs	M/Hrs/Unit	Unit/M/Hr	Unit cost	Adjusted cost	Billing rate m...	Billing rat...	Markup	Adjusted billab...
Cost item description		Cost item pricing			0.00				\$ 4,080.00		\$ 0.00	\$ 0.00	\$ 4,080.00
Cost item pricing					0.00				\$ 4,080.00		\$ 0.00	\$ 0.00	\$ 4,080.00
		Labor											
<input type="checkbox"/>	Install UG SB Pipe Cs	1140	0.00	LF	0.00	0.00	0.00	\$ 0.00	\$ 500.00	0.00%	\$ 0.00		\$ 500.00
<input type="checkbox"/>	Install UG SB Fusion Jo...	1142	0.00	LF	0.00	0.00	0.00	\$ 0.00	\$ 1,000.00	0.00%	\$ 0.00		\$ 1,000.00
<input type="checkbox"/>	Install UG SB Welding...	2758	0.00	PLS	0.00	0.00	0.00	\$ 0.00	\$ 2,500.00	0.00%	\$ 0.00		\$ 2,500.00
<input type="checkbox"/>	Reference for labor	4143	0.00	PLS	0.00	0.00	0.00	\$ 0.00	\$ 80.00	0.00%	\$ 0.00		\$ 80.00


You can configure dependent cost items in the project level configurations (Settings > Configurations > **Dependent cost items**), or you can add them manually.

Add an existing dependent cost item

Add a dependent cost item when the value of a cost item is based on the values of other cost items in the same section.

A dependent cost item must already be configured in the project settings.

1. From the Cost item pricing page, click the **Add dependent cost item** icon. The Add dependent cost item dialog box opens.



2. In the Available dependent cost items section of the dialog box, click the **Add** icon for the dependent cost item. The selected items are shown in the Selected dependent cost items section of the dialog box. You can add multiple cost items.
3. Click **Add**. The dependent cost item is added as a line on the Cost item pricing page.
4. Click **Save** on the Cost item pricing page.


If a cost item for the section named in the cost item has already been added, Change calculates the adjusted cost of the dependent cost item based on the adjusted costs of the cost items in the section.

Add a new dependent cost item


When you want to add a dependent cost item, and it has not been configured, you can create it and add it manually.

The dependent cost item is added to this cost item pricing only and is not available for future pricing. If you plan to use a dependent cost item for multiple issues, it is best practice to define it in project settings.

1. From the Cost item pricing page, click the **Add dependent cost item** icon. The Add dependent cost item dialog box opens.



2. Click **Add manual dependent cost item**. A slide-out panel opens in the dialog box.



Add dependent cost item

Back to available dependent cost items

Dependent cost item name Cost percentage Applied to section Assigned WBS

Enter dependent cost item name Enter percentage Select one Type WBS ID/Description

Hint: Type WBS ID or WBS description

Cancel Add to selected dependent cost items

Selected dependent cost items

Cancel Add

3. Enter the dependent cost item information, and then click the **Add to selected dependent cost items button**. The new cost item is shown in the selected cost items section. You can add multiple cost items.
4. Click **Add**. The dependent cost item is added as a line on the Cost item pricing page.
5. Click **Save** on the Cost item pricing page.

If a cost item for the section named in the cost item has already been added, Change calculates the Adjusted cost of the dependent cost item based on the adjusted costs of the cost items in the section.

Edit a dependent cost item

You can edit the Adjusted CB Qty for any dependent cost item or the Cost percentage for a manual dependent cost item.


On the Details tab, the Cost percentage field for a manual dependent cost item and the Adjusted CB Qty and Value type fields for any dependent cost item are the only editable fields. The remaining fields on the Details tab and those on the Dependency and Cost Categories tab are for information only. The Dependency tab shows the items that are used to calculate the dependent cost item. When you add a dependent cost item to the grand total, the Dependency tab shows all cost items used to calculate the value.

The Cost percentage field in the Edit slide-out panel is disabled when the dependent cost item was configured in the project settings.

1. From the Cost item pricing grid, select the dependent cost item, and then click the **Edit** icon. The Edit slide-out panel opens.
2. On the Details tab, enter a new value in the Cost percentage field, if it is a manual dependent cost item. If the field is disabled, the dependent cost item was configured at the project level and cannot be edited. You can also enter an adjusted cost.
3. Click **Apply**. Change uses the updated cost percentage to calculate the value of the dependent cost item. If you entered an adjusted cost, Change calculates the unit cost.
4. Click **Save** on the Cost item pricing page.

4.24.1 Edit dependent cost items

You can enable a project setting to allow users to edit the adjusted cost or cost percentage on dependent cost items that were configured at the project level. To enable this setting, go to project settings > Change > Configuration > **Dependent cost items** and set the Allow users to edit adjusted cost items toggle to Yes.



English	Dependent cost item name	Cost percentage	WBS	Applied to section	Español	Dependent cost item name	ES-MX
	Enter dependent cost item name	Enter percentage	Type WBS ID/Description	Select one		Enter dependent cost item name	
	Equipment Maintenance	3.00%	1002-Job Overhead	Equipment		Equipment Overhead	
	Small Tools & Consumables	3.00%	1005-Erect Steel - Light	Labor		Small Tools & Consumables	

When the toggle is set to Yes, users can edit the Adjusted cost field, and then the Cost percentage field is automatically recalculated and vice versa.

4.25 MARKUPS

You can add a markup to any cost item. Markups can be applied to any section, including the grand total. After the cost item is saved, the markup is carried over to the pricing page and is included in the subtotals for each section. They are also included in the Markup field in the issue header.

Markups can be based on a percentage, or they can be a specified markup. When you specify a value markup, you can specify the amount of the markup. That value is applied regardless of the amount in the cost item sections. Value markups are always level 0 and can also be applied to the grand total at level 0. For information about markups based on percentages, see [Markups](#). For information about markup levels, see [Markup calculation levels](#).

The following image shows the cost item pricing with a 100% markup percentage and a markup value of \$100 in the Labor section, a value markup of \$100 in the equipment section, and a value markup of \$200 dollars in the grand total.

Actions		Cost item description	WBS phase ..	Adjusted Mhrs	Mhrs/Unit	Unit/Mhr	Unit cost	Adjusted cost	Billing rate m...	Markup	Adjusted billabl...	Unit rate driver	Pricing item...	Cancel	Save
		Cost item pricing		68.563883				\$ 2,796.254325	\$ 0.000000	\$ 2,536.890296	\$ 5,333.144621				
		Labor		57.196977				\$ 2,336.890296	\$ 0.000000	\$ 2,436.890296	\$ 4,773.780892				
<input type="checkbox"/>	Torch CMP Metal @ Pier Caps (Install b...	1016		7.015159	7.015159	0.142548	\$ 248.177778	\$ 248.177778	0.00000000%	\$ 0.000000	\$ 248.177778	Current Estimate	Cost item		
<input type="checkbox"/>	GB/PC - Bulkhead P&B Templates - La...	1015		50.181818	25.090909	0.039855	\$ 1,044.356259	\$ 2,088.712518	0.00000000%	\$ 0.000000	\$ 2,088.712518	Current Estimate	Cost item		
<input type="checkbox"/>	Labor value markup (Labor cost item p...									\$ 100.000000	\$ 100.000000		Markup		
<input type="checkbox"/>	M1 (Labor cost item pricing 100 00000...									\$ 236.890296	\$ 236.890296		Markup		
		Equipment		11.366906				\$ 459.364029	\$ 0.000000	\$ 100.000000	\$ 559.364029				
<input type="checkbox"/>	ST&S and Materials	1003 - 800		0.000000	0.000000	0.000000	\$ 1.000000	\$ 10.000000	0.00000000%	\$ 0.000000	\$ 10.000000	Current Estimate	Cost item		
<input type="checkbox"/>	Grade Beams/Pier Caps Excavate / F...	1006 - abc		11.366906	1.136691	0.879747	\$ 44.936403	\$ 449.364029	0.00000000%	\$ 0.000000	\$ 449.364029	Current Estimate	Cost item		
<input type="checkbox"/>	Equipment value markup (Equipment c...									\$ 100.000000	\$ 100.000000		Markup		

Value markups are included in the grand total summation before the grand total is multiplied by the percentage based markup. For example, the image below shows a grand total for an adjusted cost of \$5000. A 10% percentage markup (\$500) and a \$60 value markup are applied at level 0. The 5% markup at level 2 is calculated from \$5560, which is the adjusted cost plus the two level 0 markups.

Cost item description	WBS phase code	Unit/Mhr	Unit cost	Adjusted cost	Billing rate m...	Markup	Adjusted billabl...	Unit rate driver	Pricing item type
Cost item pricing				\$ 5,000.0000	\$ 0.0000	\$ 838.0000	\$ 5,838.0000		
Labor				\$ 5,000.0000	\$ 0.0000	\$ 0.0000	\$ 5,000.0000		
<input type="checkbox"/>		New	0.0000	\$ 5,000.0000	\$ 5,000.0000	0.0000%	\$ 0.0000	\$ 5,000.0000	Manual
Grand total							\$ 838.0000	\$ 5,000.0000	
<input type="checkbox"/>	GT level 0 (Grand Total cost item pricing 10.00000%) - Level 0						\$ 500.0000	\$ 500.0000	Markup
<input type="checkbox"/>	GT (Grand Total cost item pricing \$) - Level 0						\$ 60.0000	\$ 60.0000	Markup
<input type="checkbox"/>	GT Level 1 (Grand Total cost item pricing 5.00000%) - Level 1						\$ 278.0000	\$ 278.0000	Markup

Cost item markups are carried over to the pricing summary. The cost item markups are shown above the subtotal line and are included in the pricing summary subtotal.

After you convert the issue to a potential change order or client change order, both the cost item markup and the pricing summary markup are shown above the subtotal in the potential change order or client change order.


Add a percentage-based markup to a cost item

Summary: Add a percentage markup when you want to mark up cost items based on their values.

Considerations: Percentage markups are only calculated when a cost item has a value.

Quick steps:

1. From the Cost item pricing page, click **Add markups**, and then select **Markup percentage**. The Add markup dialog box opens.



2. Select an available markup, or click **Add manual markups** to add a new one. When you add a new markup, a slide-out panel opens in the Add markup dialog box that lets you add a markup name and percentage. The markup percentage can include up to three digits before the decimal. You can then select the section to which it is applied and the markup level, if applicable. Click **Add to selected markups** to add the markup.
3. Click **Add**. The markup is shown in the grid on its own line.


Add a value markup to a cost item

Summary: Add a value markup to a cost item when you want the markup to be a set amount and not based on the values of the cost items in that section.

Considerations: Because the value markup is a set amount, it is added to the cost item section regardless of the value of the cost category. Value markups are always level 0.

Quick steps:

1. From the Cost item pricing page, click **Add markups**, and then select **Markup value**. The Add markup dialog box opens.
Enter the markup name, the value of the markup, and the section it applies to. The markup level is set to Level 0 and cannot be changed.



2. Click **Add to selected markups**.
3. Optionally, repeat steps 2 and 3 if you want to add additional value markups.
4. Click **Add** to add the markups to cost item pricing. The markup is shown in the grid on its own line.

You can also add markups at different calculation levels to the grand total. See [Markup calculation levels](#) for more information.

4.26 AUTO CALCULATE COST ITEMS

The Change auto calculate feature lets you start your cost item pricing work with the most current adjusted values from InEight Control. With auto calculation, changes to the current estimate in Control populate change order values, resulting in matching CE and CB values after the change order is completed.

The auto calculate feature subtracts the current budget from Control from the current estimate in Control to update the adjusted CB cost in Change. When you auto calculate a value, other values associated with the value are also adjusted. For example, if you recalculate the adjusted quantity, the unit cost changes. When you recalculate man-hours adjusted man-hours, man hours per unit, unit per man-hour, and labor cost per man-hours are updated.

Auto calculate cost items


Summary: Using auto calculated cost items is helpful in the early stages of cost item pricing when you might not have access to budgets, estimates, and cost categories. Change calculates the adjusted values from current budget and estimate values from Control.

Considerations: Auto calculate is for existing plug cost items only. If you recalculate a detail cost item, Change shows a message saying it will change the detail cost item to a plug cost item. Auto calculate is not available for new cost items, dependent cost items, or markups.

The recalculation uses the values from Control. Values previously entered in Change are overwritten by values from Control.


Quick steps:

1. From the Cost item pricing page, select a cost item, and then click the **Auto calculate** icon. The Auto calculate dialog box opens.



Cost item description	WBS phase code	Pay item	Cost pricing	Adjusted CB Qty	UoM	Adjusted Mhrs
Cost item pricing						
\$ 426.67						
Labor						
<input checked="" type="checkbox"/> LC TASK NAME TEST12	LC1234.TEST12	Labor	Enter adjusted qty	Ea		
<input type="checkbox"/> ADJUST SEWER MANH...	1234	Labor	1.00	Ea		
<input type="checkbox"/> REWORK E/L/B SEWER ...	1648	Labor	1.00	LF		

2. Select the fields you want to match the current budget values with the current estimate values. You can select multiple values. When you select **Cost** or **Select all**, Change recalculates the cost categories. Click **Apply**. Change recalculates the cost item.



4.27 ASSOCIATE A PRICING ITEM TO A VENDOR CHANGE ORDER


If your environment includes InEight Contract, you can associate vendor pricing items to a vendor change order (VCO) in Contract. Associating the pricing item to a VCO while in Change saves time and prevents entry errors. You can associate a vendor pricing item to an existing Contract VCO, or you can create a new VCO.

Associate a vendor pricing item to an existing Contract VCO

Associate a vendor pricing item to an existing VCO when you know that a VCO in Contract already exists. Associating the pricing item from the Pricing page can save you time. Instead of opening Contract, you can associate to an existing VCO directly from the Change Vendor and pricing information.


The vendor must already be added to the cost item. If the Vendor has another pricing item on the issue associated to a VCO, all of that vendor's cost items for this issue will automatically be associated to the same VCO. A value in the Vendor Change order ID- Description column on the pricing grid indicates that a VCO has already been created. For information about adding a vendor to a cost item, see [Edit cost items](#).

1. From the Pricing page, select a cost item with the Cost pricing value *Vendor*. The Associate to Vendor Change order icon in the tool bar shows as enabled. If the icon does not show as enabled, the cost item is not associated to a vendor or already has a VCO associated to it.



Actions		Cost item description	WBS phase code	Adjusted Qty	Adjusted Mins	Adjusted billable amount	Adjusted cost	Billing rate markup	Billing rate markup %	Cost pricing	Cost source
		SUB - Maintenance For...	1010	Enter adjusted qty		0.00	\$ 0.00	\$ 0.00	0.00%	Labor	Plug
		Cattle Guard PM	1054	Enter adjusted qty		0.00	\$ 0.00	\$ 0.00	0.00%	Labor	Plug
		Off Duty Police	1014	Enter adjusted qty		0.00	\$ 0.00	\$ 0.00	0.00%	Equipment	Plug
		SUB-Maintenance Dur...	1000			0.00	\$ 0.00	\$ 0.00	0.00%	Vendor	
		STS Maintenance Dur...	1007			0.00	\$ 0.00	\$ 0.00	0.00%	Vendor	Plug
		PCTB - Load Set - up	4182			0.00	\$ 0.00	\$ 0.00	0.00%	Vendor	Plug
		PCTB-Shift and Reset	4193			0.00	\$ 0.00	\$ 0.00	0.00%	Vendor	Plug

2. Click the **Associate to Vendor Change order** icon. The Associate to Vendor Change order dialog box opens.
3. Select **Existing** as the Vendor Change order type. Enter the Vendor Change order ID.



The dialog box is titled 'Associate to Vendor Change order'. It contains the following fields:

- Vendor Change order type:** Radio buttons for 'New' (unchecked) and 'Existing' (checked).
- *Vendor Change order ID:** A dropdown menu with a placeholder 'Hint: Type Vendor Change order ID/Description.'
- Buttons:** 'Cancel' and 'Add'.


4. Click **Add**. Information from the VCO populates the fields in the pricing item grid on the Edit vendor and pricing information slide-out panel.

Create a VCO in Contract

You can create a new VCO in Contract and associate a pricing item to it when the VCO does not already exist. This task adds the VCO to the Contract VCO log and associates the pricing item to it.

A contract for the vendor must already exist in Contract.

1. From the Pricing page, select a cost item with the Cost pricing value *Vendor*. The Associate to Vendor Change order icon in the tool bar shows as enabled. If the icon does not show as enabled, the cost item is not associated to a vendor.




The screenshot shows the Pricing page with the following details:

Cost item description	WBS phase code	Adjusted Qty	Adjusted Mhrs	Adjusted billable amo...	Adjusted cost	Billing rate markup %	Billing rate markup %	Cost pricing	Cost source
SUB - Maintenance Fo...	1010	Enter adjusted qty	0.00	\$ 0.00	\$ 0.00	0.00%	0.00%	Labor	Plug
Cattle Guard FM	1054	Enter adjusted qty	0.00	\$ 0.00	\$ 0.00	0.00%	0.00%	Labor	Plug
Off Duty Police	1014	Enter adjusted qty	0.00	\$ 0.00	\$ 0.00	0.00%	0.00%	Equipment	Plug
PCTB-Shift and Reset	4193	Enter adjusted qty	0.00	\$ 0.00	\$ 0.00	0.00%	0.00%	Vendor	Plug

A red box highlights the 'Vendor' value in the 'Cost pricing' column for the last row. A red arrow points from the 'Actions' toolbar to the 'Associate to Vendor Change order' icon.

2. Click the **Associate to Vendor Change order** icon. The Associate to Vendor Change order dialog box opens.
3. Select **New** as the Vendor Change order type.
4. Enter the VCO information. The Vendor Change order number, Description, and Vendor Change order type fields are required.



Associate to Vendor Change order

Vendor Change order type

New Existing

*Vendor Change order number: vco002

*Description:

MCR/Engineering change number:

Effective date: MM/dd/yyyy

*Vendor Change order type:

Scope of change:

Comments:

5. Click **Add**. The VCO is added to the vendor contract in Contract, and the pricing item is associated to it.

The VCO is listed on Contract's Vendor Change order log for the vendor's contract.

4.28 IMPORT COST ITEMS

Importing cost items from other sources, such as a Microsoft Excel spreadsheet or from InEight Estimate can save time and reduce errors when adding cost items to cost item pricing.

4.28.1 Import cost items from an Excel spreadsheet

When you need to add a large number of plug cost items to cost item pricing, you can add them to an Excel template, and then import them into Change. The import function lets you import new and existing cost items with the cost source Plug into cost item pricing. Any plug cost item that is in the current project is eligible for import.

If you import an existing cost item, the description that is configured in InEight Control is imported by default. To change how the description of the cost item is shown in Change, enter a new description in the Description field of the template. When the Description field is blank, Change uses the description

provided by Control. In the following image, the cost item with WBS phase code 1064 has no updates to the description, so the description from Control is imported. The item with phase code 1063 has a new description for this project. A new cost item has also been added on line 6.

A	B	C	D	E	F	G	H	I	J
Leave blank = New Cost item			ignored for existing	Select Cost pricing					
WBS phase code	Description	Adjusted CB Qty	UoM	Cost pricing	Adjusted cost	Unit cost	Adjusted Mhrs	Labor Adjusted cost	Labor Billing rate markup
1	Text	Numeric	Select one	Select one	Numeric	Numeric	Numeric	Numeric	Numeric
2	1064		Ea	Equipment		0	300		
5	1063 new description		Ea	Labor		40	4000		
6	new cost item		Hour	Labor					
7	1007 line 7	10 Liter	Small tools & supplies		600	20	600		
8									

The next image shows the items after they have been imported into cost item pricing. The new cost item has been added, the item with phase code 1063 shows the new description, and the item with phase code 1064 shows the description from Control.

Actions	Cost item description	WBS phase code	Pay item	Cost pricing	Adjusted CB Qty	UoM	Adjusted Mhrs	SL DC
Cost item pricing								
				\$ 4,900.00			60.00	
	Labor						40.00	
	<input type="checkbox"/> new description	1063	Labor	0.00	Ea		40.00	
	<input type="checkbox"/> new cost item	New	Labor	0.00	Hour		0.00	
	Equipment						0.00	
	<input type="checkbox"/> Tower Crane Foundation...	1064	Equipment	0.00	Ea		0.00	
	Small tools & supplies						20.00	
	<input type="checkbox"/> line 7	1007	Small tools & supplies	10.00	CY		20.00	

Change also calculates the Man-hours per unit, Units per man-hour, and Labor cost per man-hour fields using the Adjusted CB Qty, Adjusted Mhrs, and Labor Adjusted cost values. In the template image above, line 7 shows an Adjusted CB Qty value of 10, Adjusted Mhrs value of 20, and a Labor Adjusted cost of 600. The following image shows the calculated Mhrs/Unit and Unit/Mhr values. To see the Labor cost per man-hour, click the **Edit** icon.

Actions	Cost item description	WBS phase code	Adjusted CB Qty	UoM	Adjusted Mhrs	Mhrs/Unit	Unit/Mhr	Unit cost	Adjusted cost	Billing rate m...	Billing rat...	Markup	Adjusted billab...
Cost item pricing													
			60.00						\$ 4,900.00	\$ 0.00	\$ 0.00	\$ 0.00	\$ 4,900.00
	Labor		40.00						\$ 4,900.00	\$ 0.00	\$ 0.00	\$ 0.00	\$ 4,900.00
	<input type="checkbox"/> new description	1063	0.00	Ea	40.00	0.00	0.00	\$ 0.00	\$ 4,900.00	0.00%	\$ 0.00	\$ 0.00	\$ 4,900.00
	<input type="checkbox"/> new cost item	New	0.00	Hour	0.00	0.00	0.00	\$ 0.00	\$ 0.00	0.00%	\$ 0.00	\$ 0.00	\$ 0.00
	Equipment		0.00						\$ 300.00	\$ 0.00	\$ 0.00	\$ 0.00	\$ 300.00
	<input type="checkbox"/> Tower Crane Foundation...	1064	0.00	Ea	0.00	0.00	0.00	\$ 0.00	\$ 300.00	0.00%	\$ 0.00	\$ 0.00	\$ 300.00
	Small tools & supplies		20.00						\$ 600.00	\$ 0.00	\$ 0.00	\$ 0.00	\$ 600.00
	<input type="checkbox"/> line 7	1007	10.00	CY	20.00	2.00	0.50	\$ 60.00	\$ 600.00	0.00%	\$ 0.00	\$ 0.00	\$ 600.00


Import Plug cost items

Importing cost items can save you time when you have to add a large number of cost items. You can enter the items into an Excel template, and then import them into Change.

The import function is for new and existing plug cost items only. If you have changes to make to existing items, you must edit them instead of importing new ones. If you enter a WBS phase code, you must use a code that already exists in Control. New cost items do not have a WBS phase code, and the field in the template must be left blank.

The Excel template reflects the current settings for the organization and project. It is recommended that you download a new template each time you import items. You can refer to the Instructions tab of the template for information about importing, validations, and limitations.

1. From the Cost item pricing page, click the **Import** icon in the toolbar. The Import data from template window opens.



2. Click **Import cost item template** to download the template.
3. Open the template, and then add the plug cost items to the template. The columns with orange headers are required. To change the cost category distributions of existing cost items, enter the value in the corresponding field of the template.

Do not change the names of the spreadsheet tabs.

4. Save the template with a unique name.
5. Drag and drop the template to the Import data from the template window, and then click **Import**. After importing, you receive an email message listing status, the total cost items, the total imported, and number of errors.
6. If the status is *Pending*, you can click the **Review data** link to see the cost items that have completed and those with errors. If the import details page shows an error in the WBS phase code column, you can use the drop-down list to select a valid WBS phase code.
7. Correct the cost items with errors from the Import history grid, select them, and then click **Import** to continue with the import process. The import is reprocessed, and Change sends you

an email message when the import is completed.

If there is an error in an interdependent field such as an adjusted cost, the Import history grid shows an error for every related field. When you correct the error in one field, the others automatically recalculate but might still show an error if you did not click in those fields. After you correct the original error, you can click **Import**.

You can view the import history for cost item pricing by selecting **View import history** from the Actions menu.


4.28.2 Import cost items from Estimate

An Estimate user can publish cost items that you can then import into Change. Before an Estimate user can publish the cost items, Estimate must be integrated with Change. Refer to the [InEight Estimate Integration to Change](#) document for information about integration.

After Estimate has been integrated with Change, the Estimate user can publish the cost breakdown structure (CBS) to Change. The CBS file can contain both Plug and Detail cost items, but only Plug items are imported to Change.

You can access the published file from the Import history page for any issue in the project. The file can only be consumed one time in Change.

On the Import history page, the file name for the imported file is the Estimate project ID followed by the Estimate project description. The file location is *InEight Estimate*, and the status is *Pending*. You can then click the link in the Status or Total records column to select the file.



File name	File location	Status	Total records	Errors	Total imported	Last imported by	Last modified on
102447 - Border west Project	InEight Estimate	Pending	3	0	0	InEight Service Account	09/05/2024 08:19 AM

The cost item pricing items are imported with the Import status of *Error* in the import history Details page because they do not have a Cost pricing value assigned. You can select cost pricing values for the cost items you want to import to the issue. Any cost item that does not have a Cost pricing value selected is not imported.

Each cost item has a WBS code of *New*. They are assigned WBS phase codes after they are executed in a client change order (CCO).


Import cost items from Estimate

Summary: Import cost items into Change after the cost items are exported from Estimate, so you can use them for cost item pricing in an issue. Refer to [Cost items for change management](#) in Estimate for more information about publishing files to be imported into Change.

Considerations: These steps start after the project file has been published from Estimate.

Because the imported file can only be consumed one time in Change, if you want to use cost items that were not imported in another issue, the file must be published again from Estimate.

1. From an issue's Cost item pricing or Pricing tab, open the Import history page (Pricing > Cost item pricing > Actions > **View import history**), and then click the link in the Status column to open the import history details page.
2. From the history page, select the cost pricing type for each cost item you want to import.




3. Click **Import**. Only the items that have no cost pricing type errors are imported. Values on the cost item's Details and Cost categories tabs are imported with the cost item. The items show in cost item pricing with a WBS code of *New*.

What's next: Change sends a confirmation email when the import is complete.

4.29 COST ITEM SYNC


Change takes a snapshot of the cost item from Control at the time it is added. Any updates made to the cost item in Control are not automatically reflected in the pricing. This is to ensure pricing is not changed without the Change user knowing or completing an action. If you want to update cost items from Control, you can sync each cost item individually or in groups.

To sync an individual cost item, click the **Edit** icon, and then click **Get cost item** in the slide-out panel. The cost item is updated with any changes made in Control. Updates are also reflected in the Issue log.



The screenshot shows a comparison of cost item data. The left pane displays the current values: Current value (\$2,356.06), Cost (\$1,936.37), Billing markup (\$115.70), Markup (\$304.00), Margin (21.67%), Deductions (\$0.00), Net value (\$2,356.06), Issue status (Executed), Pricing status (None), and Proposal status (None). The right pane shows the historical data for cost item 1018, 'Haul - To Stockpile-EB'. It includes details like Forecast (T/O) Qty (56,619.00), UoM (SY), GB Qty (56,819.06), Last synced on (06/01/2021 07:23:33 AM), Description (Haul - To Stockpile-EB), Cost source (Plug), and various cost parameters like Adjusted CB Qty (100.00), Adjusted cost (\$73.87), and Adjusted Mhrs (1.00). A red arrow points from the 'Adjusted Mhrs' column in the left pane to the 'Adjusted Mhrs' column in the right pane. A red box highlights the 'Get cost item' button in the top right of the right pane.

To sync multiple items, go to Actions > Sync > **Get cost items**. The Get cost item dialog box shows a list of cost items that have changed in Control since they were originally added to the Cost item pricing page. This dialog box shows before and after comparisons based on the current unit rate driver.




The screenshot shows the 'Get cost items' dialog box. It displays a table titled 'Updated cost items' with three rows. Each row contains a checkbox, a description, WBS phase code, Mhrs/Unit value, and various unit rate values. The descriptions are: 'Haul - To Stockpile-EB', 'Load At Stockpile - Common Top...', and 'Haul - To Stockpile_1_ed'. The WBS phase codes are 1018, 1013, and 1010 respectively. The Mhrs/Unit values are 0.01, 0.04, and 0.02. The table also includes columns for Unit/Mhr value, Unit/Mhr var., Unit cost var., Unit cost val., and Unit rate driver. At the bottom of the dialog box are 'Cancel' and 'Sync' buttons.

Not all fields show in this dialog box as fields that have been modified. For example, if current estimate rates have been updated in Control, and you are using the current budget rates for your pricing, the changed fields would not be listed.

The Synced date column on the cost item pricing grid shows when information was pulled from Control.

4.30 PRICING SUMMARY

The Pricing summary is used to collect pricing information related to your issue, so you can manage and track the current estimate price and see a progression of your pricing totals from rough order of magnitude (ROM) to Agreed. The Pricing Summary tab can be used to record high-level pricing information or more detailed information on the Pricing page using cost item pricing. If you have more detailed pricing information related to the issue (for example, pricing sheet, pricing change from estimate, quote from sub), you can attach it to the issue under the Supporting Documents tab.



The Pricing summary tab includes the following tools to help you complete the task.

Pricing tab - tools

Title		Description
1	View project contract summary	Opens the Project contract summary slide-out panel that shows a view of the current project value, projected project value, milestones, and allowance category.
2	Jump to pricing section	Lets you jump to a section of the Pricing page without scrolling.
3	Add supporting document	Opens the Add supporting documents dialog box that lets you attach a document.
4	Row density	Lets you choose the density of the rows from relaxed for easy viewing, narrow, and tight to maximize the number of rows you can see at a time.
5	Export to Excel	Exports the pricing information, including cost item pricing, into a Microsoft Excel spreadsheet.
6	Add note	Lets you add a note about the pricing.
7	Show Pricing	Opens the Pricing summary page from the Cost item pricing page.

Pricing tab - tools (continued)

Title	Description
summary	
8 Show Cost item pricing	Opens the Cost item pricing page from the Pricing summary page.

The Pricing summary register records the total costs related to the issue that you potentially would propose to the client, should it become a change order. The Pricing summary is organized into Direct cost total, Vendor total (if you've added a vendor), and Indirect cost total.

Pricing summary		ROM	Estimate	Proposal	Agreed CO	Contributed value
+ Direct cost total						\$16,665.00
+ Labor						\$15,150.00
+ New labor		\$100,000.00	\$20,000.00	\$15,000.00	<input checked="" type="checkbox"/>	\$15,000.00
+ Labor subtotal						\$15,000.00
+ Labor issue markup (Labor 1.000%)						\$150.00
+ Equipment						\$0.00
+ Type equipment name						\$0.00
+ Equipment subtotal						\$0.00
+ Materials						\$0.00
+ Type material name						\$0.00
+ Materials subtotal						\$0.00
+ Small tools & supplies						\$0.00
+ Type small tools & supplies name						\$0.00
+ Small tools & supplies subtotal						\$0.00
+ Direct cost subtotal						\$15,150.00
+ Direct cost issue markup (Direct cost total 1.000%)						\$151.50
+ Vendor total						\$0.00
+ Vendor subtotal						\$0.00
+ Indirect cost total						\$0.00
+ Time related overhead						\$0.00
+ Type time related overhead name						\$0.00
+ Time related overhead subtotal						\$0.00
+ Fixed indirect cost						\$0.00
+ Type fixed indirect cost name						\$0.00
+ Fixed indirect cost subtotal						\$0.00
+ Non billables						\$0.00
+ Type non billable name						\$0.00
+ Non billables subtotal						\$0.00
+ Indirect cost subtotal						\$0.00
+ Grand total						\$16,665.00
+ Lump sum adjustment						\$0.00
+ Type lump sum adjustment name						\$0.00
+ Lump sum adjustment subtotal						\$0.00
+ Current value						\$16,665.00

The register is organized by five value types in order of precedence:

- ROM (rough order of magnitude) –This is a quick rough estimate and is an estimation of a project's level of effort and cost to complete
- Estimate – Actual estimated price
- Proposed – This is the price proposal given to a client. In most cases, the estimate can be the proposal (Proposed).
- Agreed – Client agreed price
- Contributed values – This is the value taken from the farthest to the right of all value types. For example, if there is a price in ROM and a price in Proposed, the Contributed value equals the Proposed price

If you have subtotals for each of these values, the Contributed value always takes the value furthest to the right. For example, if you have \$12,000 in Estimate, and \$9,000 in Agreed, the Contributed value is \$9,000.

As another example of pricing, you have an issue for which you originally calculated a rough order of magnitude (ROM) of \$1,000 for Labor. You then priced the issue in your estimating system and came up with an Estimate value of \$800. Finally, you worked with the owner and came to an Agreed value of \$500. You enter these values into the Labor fields.

You also have two lines of \$100 each for Materials. One is a ROM, and one is an estimate. You do not have an Agreed price for Materials. Your subtotal value that is furthest to the right contributes to your Contributed values.

Category	Subtotal	Contributed Value	Total
Direct cost total		\$700.00	\$700.00
Labor	\$1,000.00	\$800.00	\$500.00
Equipment			\$0.00
Materials	\$100.00	\$100.00	\$200.00
Small tools & supplies			\$0.00
Direct cost subtotal			\$700.00

The values furthest to the right also contribute to the totals (such as the Direct Cost total) and the Current value.

Values shown in dimmed text are summary values from the cost item pricing page and are read-only. See [Cost item pricing](#) for more information about these items.

4.30.1

4.31 DIRECT COST TOTAL

4.31.1 Direct cost total


The direct cost total has sections for Labor, Equipment, Materials, and Small tools & supplies. Each section can have multiple lines to help you break pricing down into further detail.

Each line contributes to the category subtotal, and then each subtotal contributes to, or rolls down into, the Direct cost subtotal. A markup for a section rolls down to the Direct cost subtotal. Markups to the Direct cost subtotal roll up to the Direct Cost total.

See [Markups](#) for more information about markups.


4.32 VENDOR TOTAL

You can add vendors directly from the Pricing summary in the Vendor total section. When you click the **Add vendor** icon, the Add Vendor dialog box opens, and you can choose from a list of available vendors to include in your Pricing Summary.



You can add a temporary vendor from the Pricing summary section if they are not listed as an available vendor. A temporary vendor might not have a contract in the system yet or might not yet be available in your ERP system.

You can select a vendor that is already associated with the issue, PCO, or CCO, or you can manually enter a temporary vendor name and select **Add to selected vendors**. Vendors can also have more than one pricing item.



Add vendor

Temporary vendor name

Paul's Concrete and Supply


Cancel Add to selected vendors

Selected vendors

Cancel Add

As a best practice, generic names such as temporary vendor, or temp vendor should not be used. The actual name of the temporary vendor should be used.

Click the **Add** button to create the temporary vendor.



Add Vendor

Temporary Vendor name

Paul's Concrete and Supply

Cancel Add to selected Vendors

Selected Vendors

Paul's Concrete and Supply X


Cancel Add

After you select **Add**, the new temporary vendor is automatically shown under the Pricing summary > Vendor subtotal section of the page.

After you receive a contract from the vendor, you can select the **Edit** icon to make additional changes and replace the actual contract that is reserved for this vendor.

4.33 EDIT VENDOR INFORMATION

To edit vendor information, select the **Edit vendor and pricing information** icon in the vendor line. The Edit vendor pricing information dialog box is shown below.



In the Edit vendor pricing information dialog box, you can then change the vendor or add the RFP status, vendor notes, pricing items or cost items. If you used a temporary vendor, you can replace it in the Edit vendor pricing information drop-down field, as shown in the image below.

Edit vendor and pricing information

Merrill Iron & Steel Inc


Hint: Replace temporary vendor with permanent vendor by typing Vendor name, Contract description or Subcontract ID

RFP status	Vendor change order ID
Select one	V

Pricing item	ROM	Estimate	Proposed	Value
Default				

After you replace the temporary vendor to the newly assigned vendor in the Edit vendor and pricing information drop-down list, all the temporary vendors are replaced with the newly assigned vendor. It is important not to use generic temporary vendor names such as temporary vendor, or temp vendor. This action cannot be undone.

After you click **Apply**, a message opens stating that all issues that contain the temporary vendor name will be replaced with the newly selected. Click **Yes** to accept.



With the vendor added, you can record pricing. This includes ROM, Estimate, Proposed, and the value you agree upon (Agreed). The value farthest to the right for each line is used in the Contributed values column.

Pricing summary		ROM	Estimate	Proposal	Agreed CO	Contributed value
^ Direct cost total						\$0.00
^ Labor	Type labor name					\$0.00
Labor subtotal						\$0.00
^ Equipment	Type equipment name					\$0.00
Equipment subtotal						\$0.00
^ Materials	Type material name					\$0.00
Materials subtotal						\$0.00
^ Small tools & supplies	Type small tools & supplies name					\$0.00
Small tools & supplies subtotal						\$0.00
Direct cost subtotal						\$0.00
^ Vendor total						\$800.00
^ -1140						\$800.00
1	\$200.00					\$200.00
2		\$500.00				\$500.00
3			\$100.00			\$100.00
Vendor subtotal						\$800.00
^ Indirect cost total						\$0.00
^ Time related overhead						\$0.00
Time related overhead name						\$0.00

The vendor's subtotals populate in the Contributed values and are reflected in the Grand total for the issue, which also becomes your Current Value.

Cost items that have a cost pricing of Vendor, come in as individual lines in the Vendor section as temporary vendors. Click **Edit** to assign the temporary vendor to an existing contract vendor. If that vendor already exists on the pricing summary page, the pricing items are combined under the vendor.

After a CCO is executed, only the Vendor field is editable, so you can replace the temporary vendor with the current vendor.

4.34 VENDOR CHANGE ORDERS

If your environment includes InEight Contract, you can associate vendor pricing items to a vendor change order (VCO) in Contract. Associating the pricing item to a VCO while in Change saves time and prevents entry errors. You can associate a vendor pricing item to an existing Contract VCO, or you can create a new VCO.

Associate a vendor pricing item to an existing Contract VCO

Associate a vendor pricing item to an existing VCO when you know that a VCO in Contract already exists. Associating the pricing item from the Pricing summary can save you time. Instead of opening Contract, you can associate to an existing VCO directly from the Change Vendor and pricing

information.

The vendor must already be added to the Pricing page. The vendor must not have pricing items that have already been associated to a VCO. A value in the Vendor Change order ID- Description column on the pricing grid indicates that a VCO has already been created.

1. Click the **Edit vendor and pricing information** icon for a vendor. The Edit Vendor and pricing information slide-out panel opens.

2. Select one or more pricing items. The Associate to Vendor Change order icon becomes enabled.

3. Click the **Associate to Vendor Change order** icon. The Associate to Vendor Change order dialog box opens.
4. Select **Existing** as the Vendor Change order type. Enter the Vendor Change order ID.
5. Click **Add**. Information from the VCO populates the fields in the pricing item grid on the Edit vendor and pricing information slide-out panel.

Create a VCO in Contract

You can create a new VCO in Contract and associate a pricing item to it when the VCO does not already exist. This task adds the VCO to the Contract VCO log and associates the pricing item to it.

A contract for the vendor must already exist in Contract.

1. Click the **Edit vendor and pricing information** icon for a vendor. The Edit Vendor and pricing information slide-out panel opens.
2. Select one or more pricing items. The Associate to Vendor Change order icon becomes enabled.
3. Click the **Associate to Vendor Change order** icon. The Associate to Vendor Change order dialog box opens.
4. Select **New** as the Vendor Change order type.
5. Enter the VCO information. The Vendor Change order number, Description, and Vendor Change order type fields are required.
6. Click **Add**. The VCO is added to the vendor contract in Contract, and the pricing item is associated to it.

The VCO is listed on Contract's Vendor Change order log for the vendor's contract.

4.35 INDIRECT COST SUBTOTAL

The Indirect cost subtotal section contains the time related overhead, fixed indirect, and non billables summaries. These summaries are added together (rolled down) to get the indirect cost subtotal. You can add multiple lines to each section and apply markups.

4.36 MARKUPS

You can add a markup to any subtotal. Markups apply to the subtotal of each selected section, then roll up to an overall section total. For example, if there is a 1% markup for labor, and a 10% markup for the direct total cost, a \$15,000 line in the labor section has a markup of \$150, which makes the labor contributed value \$15,150. The direct cost markup is 10% of the \$15,150, so \$1,515 is added to the direct cost subtotal for a total of \$16,665. Any markups from cost item pricing are included in separate lines above the subtotal.

The screenshot shows the Pricing & Proposal screen with the Pricing tab selected. It displays a breakdown of costs for a project, including Direct cost total, Labor, Equipment, Materials, and Small tools & supplies. The Direct cost subtotal and Direct cost value markup (Direct cost total 10.00%) are highlighted with a red box. The contributed value column shows the total value for each category.

Category	Value
Direct cost total	\$16,665.00
Direct cost subtotal	\$15,150.00
Direct cost value markup (Direct cost total 10.00%)	\$150.00
Equipment subtotal	\$0.00
Materials subtotal	\$0.00
Small tools & supplies subtotal	\$0.00
Direct cost subtotal	\$15,150.00
Direct cost value markup (Direct cost total 10.00%)	\$150.00

All markups are located directly underneath the subsection and apply to the level (that is, Issue, PCO, or CCO) you are applying them in. In a PCO, the markups from the issue are above the PCO subtotal line, and the markup added at the PCO is below the subtotal. This is because multiple issues can be collected into a PCO, and then a PCO level markup is applied to all the associated issues. The following image shows the issue-level markups and new markups at the PCO level.

The screenshot shows the Pricing & Proposal screen with the Pricing tab selected. It displays a breakdown of costs for a project, including Direct cost total, Labor, and Equipment. The Labor subtotal and PCO level labor markup (Labor 5.00%) are highlighted with a red box. The contributed value column shows the total value for each category.


Category	Value
Direct cost total	\$2,656.50
Direct cost subtotal	\$2,656.50
Labor subtotal	\$2,300.00
PCO level labor markup (Labor 5.00%)	\$126.50
Equipment subtotal	\$0.00

In a CCO, the markups from the issue and the PCO are above the CCO subtotal line, and the markups added at the CCO is below the subtotal, so you can collect multiple PCOs into a CCO and then apply a CCO level markup to all the associated PCOs.

You can hover over markups in a PCO or CCO to see level where the markup has been added to give you visibility. Markups are indicated by orange arrows. If you hover over the arrow, you can see the type of markup, the name or ID, and the markup amount.

The screenshot shows the Pricing & Proposal screen with the Pricing tab selected. A tooltip is displayed over a markup entry, showing the details: "Markup applied to: Type ID - Name: Issue 29-Parking Lot Ad., Markup: \$115.00". The tooltip also shows another entry: "Issue 42-Parking Lot Ad., \$115.00".

To add a markup, click the **Add markup** icon at the top of the page. The Add markup dialog box opens, and you can select from available markups or add a manual markup. A markup can have up to three digits before the decimal.



Pricing summary			
	ROM	Estimate	Proposal
Direct cost total			
Labor			
Type labor name			
Labor cost item pricing			\$ 142.272
Labor markup 1 (Labor cost item pricing 5.000%)			
Labor test (Labor cost item pricing 1.000%)			
Labor subtotal			
Labor (Labor 10.000%)			

You can also add markups at different calculation levels to the grand subtotal. See [Markup calculation levels](#) for more information.

4.37 DEDUCTIONS

The Deductions section lets you reduce or allocate value to one or more specific cost items. The Deduction value can only be populated from the Cost item pricing tab and produces a net value of overall change issue. For example, for a current value of \$10,000 with deductions of -\$7,500, the net value is \$2,500. To produce a negative deduction, you must use a negative quantity.

4.38 MARKUP CALCULATION LEVELS

When you want a markup in the Grand total section of the pricing summary or cost item pricing to consider previous markups, you can add markups at different calculation levels. Change adds the value of lower-level markups to the grand total to calculate the next level markup.


Markups can be set at levels 0 through 4. Level 0 is considered the root level. The markups are based on the grand total in a cost item or grand subtotal in the pricing summary and show below those lines. Markups to other sections are also considered level 0. Markups for subsequent levels are calculated from the subtotal plus markups from lower levels. For example, if markups in cost item pricing are 1% for levels 0, 2 and 4; 2% for level 1; and 5% for level 3, and the grand total is \$1000, Change calculates the values as follows:

- Level 0: $\$1000 \times 1\% = \10
- Level 1: $\$1010 \times 2\% = 20.20$
- Level 2: $1030.20 \times 1\% = 10.302$

- level 3: $1040.502 \times 5\% = 52.025$
- level 4: $1092.527 \times 1\% = 10.925$

The total markups to the grand total in cost item pricing is 103.452.

The various markups from cost item pricing are shown in the grand subtotal in the pricing summary. When multiple markup levels are added to the grand total in the pricing summary, they show under the grand total. Markup levels can be added to the pricing summary at the issue, PCO, and CCO levels. The following image shows the Pricing summary page with the markup levels from the above example and two levels of markups added from the pricing summary.



The screenshot shows the 'Pricing' tab of the 'Cost item pricing' page. The table has columns for Cost item description, WBS phase code, UoM, Adjusted Mhrs, Mhrs/Unit, Unit/Mhr, Unit cost, Adjusted cost, Markup, Adjusted billable, and Unit rate driver. The 'Markup' column shows the cumulative markups: \$1,000.000, \$103.452, and \$1,103.452. The 'Grand total' row shows the final adjusted cost of \$1,103.452 and the unit rate driver of \$1,000.000. The 'Markup' column for the 'Grand total' row shows the breakdown of markups: \$10.000, \$20.200, \$10.302, \$52.025, and \$10.925.


4.39 BUDGET MOVES

When you have issues that are not going to result in client change orders, you can now initiate a budget move in InEight Control directly from the issue, so the value can be moved to another part of the budget.

4.39.1 Initiate a budget move

When the integration is enabled, a budget move from Change automatically creates a budget move entry in the Change Register in Control. When the Control user creates a budget move, the attributes that were set up in Change flow into Control.

To create a budget move from an issue, click the **Actions** menu, and then select **Submit budget move**.



In a budget move, an issue is limited to 250 unique cost items or 100 unique pay items. If a message shows indicating that you must remove cost items or pay items, it is best practice to create a new issue. Creating a new issue lets you create another budget move with the removed cost items and pay items.

A budget move is sent to Control with a *Draft* status. After the budget move is sent to Control, the issue is given a status of *Budget move*. You cannot associate the issue to a PCO or CCO, and the Pricing tab is disabled. The Control user can review, revise, or delete the budget move. If you make a budget move that is not zero, the Control user can zero out the budget move.

You can track the budget move from the Control budget change section in the Additional details section of the Issue details.



The heading of the Control budget change section shows the Control icon representing the budget move status. The budget move in Control can have one of the following statuses: *Approved*, *Draft*, *Revised*, or *Rejected*.




4.39.2 Budget move workflow

If workflow is configured for the budget move, the budget move must be approved in Change before it can be sent to Control. The workflow begins after you select **Submit budget move** from the Actions menu. The Start approval dialog box opens, where you can add a message or attach supporting documents before starting the workflow.

After the workflow has begun, the issue is locked, and no edits can be made while the budget move is pending approval. If the budget move is recalled or rejected, the issue is enabled for editing.

4.39.3 Revise a budget move

If circumstances change, and you need to edit the issue, you can revise the budget move. To revise the budget move, click the **Actions** menu, and then select **Revise budget move**.



The status in the Control budget change section changes to *Revised*. You can then make changes to the pricing or associate the issue to a PCO or CCO.

4.40 TASK CREATION IN INEIGHT COMPLIANCE

When you have tasks associated with an issue, PCO, or CCO, you can create them in InEight Compliance to take advantage of Compliance's task management features. The task is created in Compliance and is completed in the issue, PCO, or CCO.

4.40.1 Compliance integration

Before you can create tasks for Change in Compliance, you must ensure that Compliance task templates are in place and permissions are set up for you in Compliance.

4.40.1.1 Permissions

You must have permissions to create task in Compliance. Permissions for Change users who are allowed to create tasks include access to the following:

- The project or organization
- The category for the template the organization uses
- The reporter role for creating and editing tasks

4.40.1.2 Compliance task template

The task you create in Change follows the default task template. An administrator can create a task template in Compliance. The template must have the following:

- Task title
- Change ID
- Description
- Task person
- Due date
- Assign button
- Notes
- Complete button
- Cancel button

The template must be published before it can be used in Change. Refer to the [Compliance documentation](#) for information about how to set up a standard task template.

The template must then be selected in the organization settings (organization Settings > Change > Configurations > **Task type setup**). The selected template is used for all projects in the organization.

4.40.2 Create a task


You can create a task from the Details page of an issue, PCO, or CCO.

Create a task

Create a task in an issue, PCO, or CCO when you have task items that you want to follow up.

A task template must be in place, and you must have permission to create tasks in Compliance.

1. From the Details page of an issue, PCO, or CCO, expand the Actions menu, and then select **Create Task**. The template opens in Compliance in a new window.



The screenshot shows the 'Change Task' window with the following details:


- Task title:** A required field with a character limit of 250 characters remaining.
- Change ID:** A field showing '1'.
- Description:** A required field with a character limit of 4000 characters remaining.
- Task person:** A dropdown menu labeled 'Select one' with a 'Assign' button.
- Due date:** A date picker with a 'Schedule' button.
- Assign:** A red box highlights this button, which is used to open the Task log in compliance.
- Notes:** A text area with a character limit of 4000 characters remaining.
- Buttons:** 'Cancel task' and 'Complete'.

2. Enter information in the required fields, and then click **Assign**. The Task log in compliance opens, and you can see your task in the list.

The task person completes the task, and then clicks Complete. You can track the task progress in the task log and on the Details page where you originated the task.

4.40.3 Task log

After work has begun on a task, it becomes available on the Change Task log. The Task log (Change > **Task log**) shows the tasks assigned to the project. A red circle icon indicates the number of tasks in the project that are pending, scheduled, or overdue.



Type	ID	Name	Task title	Task person	Start date	Due date	Completed date	State
Issue	197	ASD	Task 1	Esteban Conforte	12/26/2021	12/29/2021		Complete
PCO	New PCO	NCW	Task 2	Esteban Conforte	12/26/2021	01/03/2022		Canceled
Issue	191	A	Task 4	Marianne Crane INEIGHT		01/04/2022	01/05/2022	Scheduled
CCO	CCO test	Error handling	Task 3	Esteban Conforte		01/05/2022		Scheduled
PCO	DCT PCO	DCT PCO	Task 5	Marianne Crane INEIGHT	12/26/2021	01/06/2022	01/06/2022	Overdue
Issue	191	B	testing	Karen Loftus		01/19/2022		Scheduled

The task log shows all tasks that have been assigned on the project. The View drop-down menu in the upper right of the page lets you change the view to show your tasks only. You can also change the row density.

Values in the ID column are links to the originating issue, PCO, or CCO. The Task title is a link to the task in Compliance. The Due date and State columns highlight tasks that are past due in red. The Name column contains the Name of the issue, PCO, or CCO.

You can click the Export icon to export the tasks to a Microsoft Excel spreadsheet.


You also can view tasks from the issue, PCO, or CCO in the Task section of Additional details. See the Additional details for issues, PCOs, and CCOs for more information about the Tasks section.

This page intentionally left blank.

CHAPTER 5 – CHANGE ORDERS

Features in Change help you create and manage potential change orders and client change orders.


5.1 INEIGHT CONTRACT WORKFLOW - CHANGE ORDERS



5.2 POTENTIAL CHANGE ORDER (PCO)

5.2.1 Overview

During the process of managing changes, some of your issues will require additional work for either you or your subcontractors to perform. As you seek compensation from the client (owner) for issues that require additional work, you will convert those issues into Potential Change Orders (PCOs), as indicated in the below workflow.



The table below further defines each step of the change management process.

Term	Description
Issue	<p>Something that happens on the project that could incur costs or impact the schedule.</p> <ul style="list-style-type: none"> Provides a way to track issues that may or may not become a contract change (PCO or CCO) You can track how many issues occurred on the project, what their impact was, and how many were recovered via change orders

Term	Description
Potential Change Order (PCO)	<p>A potential change to the owner's contract that you are pricing and getting ready to negotiate with the owner.</p> <ul style="list-style-type: none">• A PCO may contain one or more issues• A PCO may go through several changes during the negotiation with the owner• You can track PCOs to see the potential effects on your budget and revenue
Client Change Order (CCO)	<p>A finalized change you are ready to send to the owner.</p> <ul style="list-style-type: none">• You can bundle multiple PCOs together to become one CCO

5.2.2 Potential Change Order (PCO) Creation

A PCO is generated from one or more issues that already exist within the issue log. The PCO will carry over all pertinent data from the Issue and populate the fields within the PCO. The link between Issue and PCO is one-way, upstream. Data carried over from the Issue into the PCO can be modified without any changes occurring to the original data, however, changes to the Issue can be pushed upstream to the PCO.

Any changes made to PCO pricing does not update the original issue. If an issue needs to be updated, you will need to open the issue and update it.

The following steps walk you through how to convert an issue to a PCO.

Create a potential change order (PCO)

Summary: Create a PCO when you are ready to negotiate the issue with the owner.


Considerations: These steps start from the Issue log. You can also create a PCO from the Change orders section of the issue Details page. If your contract is already negotiated with the owner, you can convert an issue directly to a CCO and skip the PCO process altogether.

When converting to a change order, an issue is limited to 250 unique cost items or 100 unique pay items. If a message shows indicating that you must remove cost items or pay items, it is best practice

to create a new issue. Creating a new issue lets you create another change order with the removed cost items and pay items.


Quick steps:

1. From the Issue log , select the issues you want to convert to a PCO.




	Issue ID...	PCO ID	CCO ID	Issue name
<input checked="" type="checkbox"/>	62			
<input checked="" type="checkbox"/>	61			
<input type="checkbox"/>	60	PCO - 20		

2. Click the **Associate to change order** icon, and then select **Assign to potential change order**.



	Issue ID...	PCO ID	CCO ID	Issue stat...
<input checked="" type="checkbox"/>	62			New
<input checked="" type="checkbox"/>	61			New



Associate to Potential change order
Associate to Client change order

If any of the issues you selected are already part of a PCO or CCO, you will receive an error message. You can check the Issue Status column in the Issue Log to ensure the selected issues have a status other than PCO or CCO.

The Assign to potential change order dialog box shows.

3. Indicate whether the issue is to be associated to a new or existing PCO, and then enter the PCO ID and PCO name. You can also enter an alternate PCO ID and a description of the change.

4. Click **Save**. The PCO Details page opens.

DETAILS PRICING & PROPOSAL SUPPORTING DOCUMENTS PROPOSAL & PRICING

PCO Details

Created by: paul trippi on 06/21/2019

*PCO ID

PT001

Alternate ID

Hint: Type new or existing Alternate ID

*PCO description

Bearing Pads Rework

981


Change orders

 Convert to client change order

5. Optionally, scroll to the Associated issues section, and then add any additional issues you want to associate to the PCO.
6. Go back to Change > **PCO Log** to see the status of your newly created PCO.

5.2.2.1 Assign a PCO from Issue Record

Another option for Assigning an issue to a potential change order is on the Details tab of an issue record. Clicking the Assign to potential change order link will open the window to assign the issue to a PCO.




5.2.3 PCO Header

The header at the top of your PCO record contains the same functionality as the issue header, allowing you to update the following:

- PCO status
- Pricing status
- Proposal status



As you change the statuses, you will be prompted to enter notes. These notes are stored in the Notes slide out panel, which you can access at any time by clicking on the View notes icon.



5.3 PCO DETAILS TAB

Below the header on the PCO record, there are tabs for capturing the PCO's details, costs, and supporting documentation.



The PCO Details tab contains the identifying information you entered on the Assign to potential change order window, along with a listing of the issues associated with the PCO, and the option to convert the PCO to a CCO.

Overview - PCO Details Tab

Title		Description
1	PCO navigation	Lets you navigate to other PCOs without having to go back to the PCO log. Click the arrow to see a list of PCOs, and then select one. The selected PCO opens in the same window.
2	PCO ID	Free text entry field carried over from filling out the Assign to potential change order window.
3	PCO Name	Free text entry field carried over from filling out the Assign to potential change order window.
4	Alternate ID	Free text entry can be used as a subset to your PCO ID.
5	PCO start date	The date that work on the PCO started. You can use a start date that is different from the created date when the day work on a PCO was

Overview - PCO Details Tab (continued)

Title		Description
		started is different from when the PCO was created. The PCO aging days open column on the PCO log uses the start date instead of the created date to give a more accurate count.
6	Description of change	Free text entry for describing the PCO, carried over from filling out the Assign to potential change order window. You can use the Expand icon to expand the text box for easy text entry and viewing. You can then collapse the text box when you are finished.
7	Change orders	Clicking this link converts the PCO to a Client Change Order (CCO).
8	Additional details	Sections for Schedule impact, Responsible parties, Correspondence, Request for information, Tasks, Revenue category, Project values, and Custom fields.
9	Associations	<ul style="list-style-type: none"> List of issues that were associated to the PCO for creation Click the ID-Name link to go back to the issue Details screen Issue Details show the PCO ID for the issue the PCO is tied to Cost information is available in the Current value, Cost, Billing Markup, Markup, Markup %, Deductions, and Net value columns Click the Add associated issue icon to add additional issues to PCO if they are not assigned to an existing PCO or CCO You can also remove issues from the PCO from here
10	Potential change order terms	Terms specific to the PCO. You can add up to two terms. You can use the Expand icon to expand the term text boxes for easy text entry and viewing. You can then collapse the text boxes when you are finished.
11	eSign	Lists of eSign recipients and Project contacts that default as signees for an eSignature via a provider, such as DocuSign. When custom labels are used for contacts in InEight Platform project details, Change uses the labels in the Project contacts section. The labels are also used in the Send for signature dialog box.

The screenshot shows the 'PCO: pco - details' tab with the following sections and numbered callouts:

- 1** General status: Shows 'Created by' and 'on 06/15/2023'.
- 2** PCO ID: 'pco'.
- 3** PCO name: 'pco'.
- 4** Alternate PCO ID: 'pco'.
- 5** PCO start date: '06/15/2023'.
- 6** Description of change: 'Format' dropdown.
- 7** Change orders: Shows 'Associate to Client change order' button.
- 8** Additional details: Includes dropdowns for 'Schedule impact', 'Responsible parties', 'Correspondence', 'Request for information', 'Tasks', 'Revenue category', and 'Custom fields'.
- 9** Associations: Shows a table with one row: '1001...existing'.
- 10** Potential change order terms: Shows two sections: 'View details' and 'Potential change order term 1'.
- 11** DocuSign: Shows a table for 'DocuSign' with columns: Recipient, Name, Company, Title, Email. It also lists 'DocuSign 1' through 'DocuSign 10' and 'DocuSign'.

5.3.0.1 eSign

The eSign section lets you view or add recipients to be used as default eSign signees. This section has subsections for eSign and Project contacts. All signees must be added to at least one section.

- Names in the eSign section are populated from the project eSign setup tab (Project settings > Change > Configurations > **eSign setup**). You can also manually enter the names of the signees.

- Names in the Project contacts section are populated with contact information from project contacts set at the suite administration level. This section is for reference only. If you want to add or change recipients, you must edit the Project contacts section of the Project details.

5.3.1 Additional details

The Additional details section has expandable subsections for the following features:

- Schedule impact
- Responsible parties
- Correspondence
- Request for information
- Tasks
- Revenue category
- Project values
- Custom fields

5.3.1.2 Schedule impact

The Schedule impact section includes the requested time extension. When there is only one issue associated to the PCO, the issue delay days populates this field. When there is more than one issue associated, the field is blank. You can add forecasted days in the Forecast field.

5.3.1.3 Correspondence

Use the Correspondence section to track the following:

- PCO Date client notified. An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.
- PCO Date price to client. An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.
- PCO Client approval date. You can enter a client approval date.
- Executed change order. An information icon in the Date column shows the specific supporting

document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.

5.3.1.4 Request for information

The Request for information fields are assigned by a supporting document of type RFI. The heading for the Request for Information section includes a counter so you can quickly see the number of associated RFIs the PCO has.

5.3.1.5 Tasks

The Tasks section shows all tasks assigned in InEight Compliance for the PCO. For each task, the section shows the task name with a link to the task, the name of the person assigned to the task, the due date, and the current state. Overdue tasks show in red in both the Due date and State columns. Pending tasks show in yellow in the State column. Completed tasks show in green in the State column.

5.3.1.6 Project values

The Project Values section shows the project values configured for the project. For each project value, you can select a value from the drop-down list. Each field has a Settings icon that takes you to the Available project values page of the project. You can add project values or change the status of existing project values with the applicable permission.

5.3.1.7 Custom fields

Custom fields include PCO custom lists 1 and 2 and PCO custom fields 1-4.

5.4 PCO PRICING TAB

Pricing for a PCO originates from its assigned issues. When you open a PCO, the Pricing tabs show the values inherited from those issues, along with associated vendors and contracts. This automatic inheritance of issue values occurs when the PCO is created.

The PCO includes two tabs for pricing:

- Pricing - Shows the inherited pricing details. Values on this tab are read-only.
- Pricing Summary - Shows pricing subtotals organized by cost pricing section, along with any amounts entered as ROM, Estimate, Proposal, and Agreed values. Values from the Pricing tab are displayed in the Estimate column and cannot be edited.

5.4.1 Pricing tab

The Pricing tab shows the pricing established at the issue level. You cannot edit the inherited values on this tab. You can only add an unassigned pricing item, if needed. To make detailed pricing updates, return to the associated issue.


5.4.1.1 Pricing Summary tab

The Pricing Summary tab allows you to make lump-sum adjustments to the PCO total. When reviewing or adjusting pricing here, keep in mind the following:

- Value precedence follows the same order as on issues:
 - Estimate values take precedence over ROM .
 - Proposed values take precedence over Estimate.
 - Agreed values take precedence over Proposed.
- The PCO's current value is the sum of the cost pricing sections including Labor, Equipment, Materials, Vendor, and Time-related overhead totals.

5.4.1.2 Update PCO values with issue values

If Change is not configured to automatically update value changes to higher levels, you can manually update the PCO Pricing Summary tab with new pricing and associated vendor data from your issues. Select **Update values > Pull values from issue** from the Actions menu.



For example, you have a PCO with a total price of \$10,210, totaled from Estimate values in the Pricing summary on the PCO's Pricing tab.

As your field engineer assesses things out in the field, he determines the estimate to be a little low, so he changes one of the assigned issue's Estimated subtotal to \$12,000. You can update the PCO with the new pricing by selecting Pull values from issue from the Actions menu.

You will receive a prompt asking if you are sure you want to update the PCO's values. When you select Yes, the PCO's Estimate values update and the PCO's new Grand total updates to \$12,000.

Pricing changes made on the PCO do not change the pricing of the assigned issues. Pricing changes made on the issue's Pricing Summary can only change pricing on the related PCO if you select Update PCO values with issue values from the Actions menu, or you have configured Change to automatically update value changes to higher levels. Values inherited from the issue Pricing tab automatically update on the higher levels of PCO and CCO.

The ability to automatically update values from higher or lower levels is configured in project Settings > Configurations > **Pricing configuration**. When set to automatically update value changes to higher levels or lower levels, any changes made at the issue level are automatically reflected in the PCO. Any changes made at the PCO level are automatically reflected in the issue and CCO.

When the Change is not configured to update values to higher levels, you can manually update values as follows:

- At the issue level, you can push values to the PCO. If the PCO is associated to a CCO, the value is automatically pushed to the CCO.
- At the PCO level, you can push values up to a CCO or pull values down to an issue.
- At the CCO level, you can pull values from the PCO. If the issue is associated with a PCO, the value is automatically pulled from the issue.

When Change is not configured to update values to lower levels, you can manually update values as follows:

- At the issue level, you can pull values from the PCO. If the PCO is associated to a CCO, the value is automatically pulled from the CCO.
- At the PCO level, you can push values to the issue or pull values from the CCO.
- At the CCO level, you can push values to the PCO. If the issue is associated with a PCO, the value is automatically pushed to the issue.

If you make a change to the pricing at any level, the Pricing pages at the other levels show a banner warning that the updated values are not reflected at all levels. For example, if a pricing change is made at the issue level, the banner shows at the PCO and CCO levels. To update values, go to the Actions menu. Then select whether to push values down or pull values up.


5.5 PCO LOG

On the Change page, the PCO Log tab contains a register of all your PCOs.

- Executed PCOs have a green checkmark next to them and are no longer editable
- Dropped PCOs have a yellow caution sign next to them and are locked
- Note that there is no delete button. Once a PCO is created, it cannot be deleted
- Many of the PCO details and statuses are editable from the Issue Log register
- The PCO Log provides subtotals at the bottom of the register for total number of PCOs and total current values of the PCOs

PENDING ISSUES	ISSUE LOG	POTENTIAL CO LOG	CLIENT CO LOG	ACTION ITEMS	AUDIT LOG	CHANGE TEMPLATES
PCO ID	Description	Creation date	PCO aging...	PCO status	PCO date client no...	Bal in co...
077	IH PCO-077	09/21/2018	0	Dropped		
PB001	Bearing Pads Rework	09/21/2018	0	Executed	Contractor	In p
PB01	Partial Owner Request	09/20/2018	1	Dropped		
016	MH - Bearing Pads	09/07/2018	14	In Review	Client	
017	Anchor Bolts	09/07/2018	14	In Review		\$15,000.00
045	FH PCO-099	09/07/2018	14	In Review		\$20,075.00
MWR - PC01	Keep same description as origi...	08/21/2018	31	Executed	Contractor	\$20,075.00
PCO.44	BQ PCO-022	08/17/2018	35	Dropped		
PCO.055	PCO demo	08/16/2018	36	CCO		
MTH-PC01	Bearing Pad PCO	07/10/2018	73	Executed	Contractor	\$16,500.00

By clicking the drop-down menu on the View box, you can change the viewsets of your table and can save a custom view. You can also export your table (will export the data exactly as displayed within the table), show details, and search for data within the table.



You can generate a change document from the PCO log. Select a PCO, go to the Actions menu, and then select **Generate Change document**. See 5.8 Change writer on page 236 for information about generating change documents.

5.5.0.1 Aging days


The number of days that a PCO has been open is shown in the PCO aging days open column. The Aging days value is calculated using today's date minus the start date. This calculation stops when the item is changed to a status of executed or dropped.

5.6 CLIENT CHANGE ORDER (CCO) GENERATION

5.6.1 Overview

As you manage your issues and PCOs, you can convert them to Client Change Orders (CCOs) when they reach any of the following criteria:

- You are finalizing the negotiating process with the client
- You have an agreement in place
- You have something up for signature or already signed
- You already know the final value of your change order



5.6.2 Client Change Order (CCO) Creation


A CCO can be generated from an existing PCO, or directly from an Issue. The CCO will carry over all pertinent data from the PCO/Issue and populate fields within the CCO. Just like the relationship between issue and PCO, the link between Issue/PCO to the CCO is one-way, upstream. Data carried over from the Issue/PCO into the CCO can be modified without any changes occurring to the former; however, changes to the Issue/PCO can be pushed upstream to the CCO.

Create a Client change order (CCO)

Create a CCO when the change is finalized and ready to send to the owner.

When converting to a change order, an issue is limited to 250 unique cost items or 100 unique pay items. If a message shows indicating that you must remove cost items or pay items, it is best practice to create a new issue. Creating a new issue lets you create another change order with the removed cost items and pay items.


1. From the PCO tab, select the PCOs you want to associate to a CCO, and then click the **Associate to Client change order** icon..



PCO LOG						
Actions	PCO ID	PCO name	CCO ID	PCO creation d...	PCO agin...	PCO status
<input checked="" type="checkbox"/>	PCO - 9	Issue_E		06/06/2024	43	New
<input checked="" type="checkbox"/>	PCO - 8	PCO_8		06/03/2024	46	New
<input type="checkbox"/>	PCO - 7	From Contract		05/22/2024	58	New

The Associate to Client change order dialog box opens.

2. Indicate whether the PCO is to be associated to a new CCO or an existing CCO, and then enter the CCO ID and CCO name. You can also enter an alternate CCO ID and a description of the change.



Associate to Client change order

CCO Type

New Existing

CCO ID

Alternate CCO ID

Hint: Type new or existing Alternate CCO ID

*CCO name

Description of change


Cancel Save

3. Click **Save**. The CCO Details page opens.

What's next: You can enter additional CCO details, manage pricing, and add supporting documents.

5.6.2.1 Convert to CCO from Issue/PCO Record

Another option for Converting to a CCO is on the Details tab of an issue record. Clicking the Assign to potential change order link will open the window to assign the issue to a PCO.



Issue description

Created by Paul Bennion on 09/19/2018

*Issue name: Paint peeling

*Issue start date: 09/19/2018

Description: 966

Hint: Date of the start of impact

Change orders

Assign to potential change order

Convert to client change order

Split issue

5.6.3 CCO Header

The header at the top of your CCO record contains the same functionality as the issue/PCO header, allowing you to update the following:

- CCO status
- Pricing status
- Proposal status

5.6.4 CCO Details Tab

Below the header on the CCO record, there are tabs for capturing the CCO's details, costs, and supporting documentation.

The CCO Details tab contains the identifying information you entered on the Convert to client change order window, along with several other fields to capture the change order amount, approved extension information, and type of signing agreement.

Overview - CCO Details Tab

Title		Description
1	CCO navigation	Lets you navigate to other CCOs without having to go back to the CCO log. Click the arrow to see a list of CCOs, and then select one. The selected CCO opens in the same window.
2	CCO ID	Free text entry for describing the CCO, carried over from filling out the Convert to client change order window.
3	CCO name	Free text entry for the name of the CCO.
4	Alternate CCO ID	Free text entry can be used as a subset to your CCO ID.
5	CCO start date	The date that work on the CCO started. You can use a start date that is different from the created date when the day work on a CCO was

Overview - CCO Details Tab (continued)

Title		Description
		started is different from when the CCO was created. The CCO aging days open column on the CCO log uses the start date instead of the created date to give a more accurate count.
6	Description of change	Free text entry for describing the PCO, carried over from filling out the Convert to client change order window. You can use the Expand icon to expand the text box for easy text entry and viewing. You can then collapse the text box when you are finished.
7	Control budget change	Information about the contract adjustment status and the change register ID from InEight Control.
8	Additional Details	Sections for Client change order execution details, Schedule impact, Responsible parties, Correspondence, Request for information, Tasks, Revenue category, and Custom fields.
9	Associations	<ul style="list-style-type: none"> • List of issues or PCOs that were associated to CCO for creation • Clicking Issue or PCO ID link will navigate you back to Issue/PCO record • Cost information is available in the Current value, Cost, Billing Markup, Markup, Markup %, Deductions, and Net value columns • Able to add or remove issues or PCOs to the CCO if they are not assigned to an existing CCO
10	Client change order terms	Terms specific to the CCO. You can add up to two terms. You can use the Expand icon to expand the term text boxes for easy text entry and viewing. You can then collapse the text boxes when you are finished.
11	eSign	Lists of eSign recipients and project contacts that default as signees for an eSignature via a provider, such as DocuSign. When custom labels are used for contacts in InEight Platform project details, Change uses the labels set at the suite administration level. The labels are also used in the Send for signature dialog box.

CCO: cco - details

Control budget change

Associations

Client change order terms

DocuSign

5.6.4.2 eSign

The eSign section lets you view or add recipients to be used as default eSign signees. This section has subsections for eSign and Project contacts. All signees must be added to at least one section.

- Names in the eSign section are populated from the project eSign setup tab (Project settings > Change > Configurations > **eSign setup**). You can also manually enter the names of the signees.
- Names in the Project contacts section are populated with contact information from project contacts added in Project details. This section is for reference only. If you want to add or change recipients, you must edit the Project contacts section of the Project details.

5.6.5 Additional details

The Additional details section has expandable subsections for the following features:

- Client change order execution details
- Schedule impact
- Responsible parties
- Correspondence
- Request for information
- Tasks
- Revenue category
- Project values
- Custom fields

5.6.5.3 Client change order execution details

The Client change order execution section contains fields that are used when the CCO is executed.

The Signing agreement field describes how the CCO was executed (bilaterally, unilaterally, or unassigned). The Current value is carried over from the Pricing tab and is read only. The executed change order amount typically matches the Agreed Change Order Amount, but could differ due to changes by the client. This value is shown in the CCO log.

The remaining fields are read-only and are automatically filled when the CCO is executed.

5.6.5.4 Schedule impact

The Schedule impact section includes the Approved time extension and the Time extension. The Approved time extension is the number of days granted by the client per CCO. You can also select *Deferred* to defer the extension or *N/A* when the time extension is not applicable. The time extension fields show the time extension requested. When there is only one PCO associated to the CCO, the PCO

delay days populate this field. When there is more than one PCO associated, the field is blank. You can add forecasted days in the Forecast field.

5.6.5.5 Correspondence

Use the Correspondence section to track the following:

- CCO Date client notified - An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.
- CCO Date price to client - An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.
- Executed change order - An information icon in the Date column shows the specific supporting document that must be attached to populate the date. You can add the document on the Supporting documents page. After a document is added, a link is shown in the File/Link column.

5.6.5.6 Request for information

The Request for information fields are assigned by a supporting document of type RFI. The heading for the Request for Information section includes a counter so you can quickly see the number of associated RFIs the CCO has.

5.6.5.7 Tasks

The Tasks section shows all tasks assigned in InEight Compliance for the CCO. For each task, the section shows the task name with a link to the task, the name of the person assigned to the task, the due date, and the current state. Overdue tasks show in red in both the Due date and State columns. Pending tasks show in yellow in the State column. Completed tasks show in green in the State column.

5.6.5.8 Project values

The Project Values section shows the project values configured for the project. For each project value, you can select a value from the drop-down list. Each field has a Settings icon that takes you to the Available project values page of the project. You can add project values or change the status of existing project values with the applicable permission.

5.6.5.9 Custom fields

Custom fields include CCO custom lists 1 and 2 and CCO custom fields 1-4.

5.6.6 CCO Pricing Tabs

On the CCO Pricing tabs, you can work out the final pricing for your change order, ending up with a current value for the CCO derived from cost items and any assigned markups. You have the same pricing functionality on the CCO Pricing tabs as you have on the PCO Pricing tabs.

5.6.6.10 Pricing tab

The Pricing tab shows the pricing established at the PCO and issue levels. It includes cost item pricing including any unassigned pricing items and markups. You cannot edit the inherited values on this tab. You can only add an unassigned pricing item, if needed. To make detailed pricing updates, return to the associated issue.

5.6.6.11 Pricing Summary tab

The Pricing Summary tab shows subtotals organized by cost pricing section . You can make lump sum adjustments to the CCO total.

- The Pricing summary has the same rules of precedence for ROM, Estimate, Proposal and Agreed values.
- On the Pricing Summary tab, the Grand total is the sum of the Direct cost, Vendor, and Indirect cost subtotals.

The ability to automatically update values from lower levels is configured in project Settings > Configurations > **Pricing configuration**. When set to automatically update value changes to lower levels, any changes made at the PCO level are automatically reflected in the CCO. Any changes made at the CCO level are automatically reflected in the PCO.

When the Change is not configured to update values to higher levels, you can manually update values as follows:

- At the issue level, you can push values to the PCO. If the PCO is associated to a CCO, the value is automatically pushed to the CCO.
- At the PCO level, you can push values up to a CCO.
- At the CCO level, you can pull values from the PCO. If the issue is associated with a PCO, the value is automatically pulled from the issue.

When Change is not configured to update values to lower levels, you can manually update values as follows:

- At the issue level, you can pull values from the PCO. If the PCO is associated to a CCO, the value is automatically pulled from the CCO.
- At the PCO level, you can pull values from the CCO.
- At the CCO level, you can push values to the PCO. If the issue is associated with a PCO, the value is automatically pushed to the issue.

If you make a change to the pricing at any level, the Pricing pages at the other levels show a banner warning that the updated values are not reflected at all levels. For example, if a pricing change is made at the issue level, the banner shows at the PCO and CCO levels. To update values, go to the Actions menu. Then select whether to push values down or pull values up.


5.6.7 CCO Log

The CCO Log tab is a display of all CCOs, regardless of status. Most fields will contain data from the CCO Details header and Pricing. However, there are some editable fields on within the CCO Log.

- Executed CCOs have a green checkmark next to them and are no longer editable
- Dropped CCOs have a yellow caution sign next to them and are locked
- Note that there is no delete button. Once a CCO is created, it cannot be deleted
- The CCO Log provides subtotals at the bottom of the register for total number of CCOs and total current value of the CCOs (based on those CCOs that have locked pricing – ROM, Estimate, Agreed)

You can also export your table, show details, and search for data within the table.


When you export your table, the table exports the data exactly as it shows within the table; thus, if any filters are on that data will not export. To export your table, click the **Export** icon from the toolbar.



You can generate a change document from the CCO log. Select a CCO, go to the Actions menu, and then select **Generate Change document**. See 5.8 Change writer on page 236 for information about generating change documents.

5.7 CLIENT CHANGE ORDER (CCO) EXECUTION

Once the change order is finalized with the client, you can change the CCO status to Executed.




An Executed change order document type must be uploaded as a supporting document prior to changing CCO status to Executed.

- When the CCO Status in the CCO Details Header is changed to Executed, the Close CCO and mark complete window appears for final closeout of the change order
- When the CCO is closed, it is sent to the Change Register of InEight Control to make a contract adjustment for cost, revenue, and man-hours, using the details and values entered in the CCO in Change Management

5.7.1 Client Change Order Workflow Settings

With Client Change Orders you can turn on the workflow to send the CCO through an approval process before execution is complete. This is similar to the issue approval workflow.

Once a CCO is completed (and workflow is turned on) the Submit CCO for approval button shows up in the top left corner.



The screenshot shows the 'Client CO status' dropdown set to 'In Review', the 'Pricing status' dropdown set to 'Not Started', and the 'Proposal status' dropdown set to 'Not Started'. Below these are two tabs: 'SUPPORTING DOCUMENTS' and 'PROPOSAL & PRICING'. At the bottom are three buttons: 'Cancel', 'Submit client CO for approval' (which is highlighted with a red box), and 'Save'.

Click the button to send an approval request to whomever is set up as the approver in the Project Settings. To get to the CCO Workflow settings go to Project Settings > Change > Workflow > **CCo Approval Setup** and then turn on or off the approval step.

Overview - Close CCO and Mark Complete Window, Executed details

Title	Description
1 Agreed Change Order Amount	Pulled from CCO Pricing Grand total.
2 Executed Change Order Amount	<ul style="list-style-type: none"> Free text entry pulled from CCO Details tab. The net value is used by default. This is the value that will be pushed into the InEight Control Change Register
3 Approved Time Extension	<ul style="list-style-type: none"> Drop-down selection menu; time extension granted by client per CCO Shows in the CCO Log Defaults to 0 but can be changed

Overview - Close CCO and Mark Complete Window, Executed details (continued)

Title	Description
4 Approved Time Extension	<ul style="list-style-type: none"> Time extension granted by client per CCO Shows in the CCO Log
5 Signing Agreement	<ul style="list-style-type: none"> Used to indicate how the contract was executed, for information only Bilateral - Both client and contractor Unilateral - Client or contractor only Unassigned
6 Notes	Free text entry

Executed CCOs can be switched back to In Review with applicable permissions.

5.7.2 Executed CCO status

After a CCO is executed, the status changes to Executed in the Issue log, PCO log, and CCO log, and all associated issues and PCOs are locked and cannot be edited, with the exception of a temporary vendor. See [Edit vendor information](#) for information about editing a temporary vendor.

When a cost item is associated to an executed CCO, you can view details of the cost item by selecting it and then clicking the **Edit** icon. The resources details and cost categories are shown but are read-only.

5.7.3 Vendor change order creation

You can configure Change to automatically create a vendor change order (VCO) in InEight Contract for any pricing items that are not already associated to a VCO. When the setting (Settings > Change > Configurations > Pricing configuration > **Vendor change order configuration**) is set to Yes, Change creates the VCOs upon execution of the CCO. You are prompted in the CCO Execution wizard to select the vendor change order type. After the CCO is executed, the VCOs are in Contract with *Service Account* as the Created by name. When the project setting is set to *No*, you must create the VCOs manually in Contract.


Execute a CCO

Summary: Execute a CCO when the change order is finalized with the client.

Considerations: If the Vendor change order configuration setting in the project settings Configurations (Settings > Change > Configurations > Pricing configuration > **Vendor change order configuration**) is set to Yes, Change automatically creates a vendor change order from the executed CCO.

Quick steps:

1. From the CCO Log tab, select the change order.



	Client CO ID	Description	Created
<input type="checkbox"/>	PB111	Potential change request	09/21/
<input type="checkbox"/>	PB001	Bearing Pads Rework	09/21/

2. Select the **Supporting Documents** tab.
3. Click the **Add supporting documents** icon, and then add a supporting document with the type Executed change order
4. In the CCO header, change the CCO status to Executed. The Close CCO and mark complete window opens.
5. Complete the required fields.

Close CCO and mark complete

1 Executed details 2 Supporting attachments

Agreed change order amount ⓘ

\$17,775.00

Executed change order amount

\$17,775.00

Hint: Enter value from change order document

*Approved time extension

Number of days

4

Hint: Enter value from change order document

*Approved time extension days

Notes

400

Type message here

Cancel Next

6. Click **Next**.
7. Review and confirm the correct Executed Change Order document is attached to the CCO. If it is not attached, you can attach it in the wizard.
8. Click **Next**.
9. Select the Vendor change order type for the pricing items that are not yet assigned to a VCO.

Close CCO and mark complete

1 Executed details 2 Supporting attachments 3 Create Vendor Change order

The following items will automatically create a Vendor Change order for each contract listed.

ID - Name	Value	Vendor change order type
PCO : pco1 - issue1	\$100.00	Select one
Issue : 485 - issue1	\$111.00	
Issue : 486 - issue2	\$100.00	

Cancel Back Submit

10. Click **Submit**. Upon successful completion, the CCO is pushed to the Control change register.

What's next: If Change is configured to automatically create VCOs, the VCOs are created in Contract for the pricing items. If Change is not configured to create VCOs, you can associate the CCO to a VCO in Contract.

5.8 CHANGE WRITER

If you need to create a customized change document between the contractor, owner or subcontractors, Change provides Change writer to aid in the development. This is a legal document that needs to be signed by all parties and stakeholders. The Change writer supports both standard and bulk template generation.

5.9 STANDARD AND BULK TEMPLATE PROCESSING

The Change writer lets you choose between standard and bulk processing.

Standard processing lets you choose between generating a merged PDF of all templates or individual documents for each template. If you use standard processing with templates that include template contact tags, you can choose one contact for a customized document.


Bulk processing automatically generates a merged PDF document for up to 10 contacts in a single action. The bulk templates feature works in conjunction with template contact tags, so you can customize documents for up to 10 contacts, similar to a mail merge. You can use bulk processing for generating multiple documents that include customized information for each contact, such as a cover letter with a pricing request.

5.10 GENERATE A CHANGE DOCUMENT

When you are ready to create a change document, you can generate it from one or more templates. Go to the Actions drop-down menu from any issue, PCO, or CCO, and then select **Generate change document** to start the Change writer wizard. The Change writer wizard supports standard or bulk processing.


Generate a standard change document

1. From an issue, PCO or CCO, select the **Actions** menu drop-down list, and then select **Generate change document** from the menu. You can also find this option in the Actions menu on the PCO and CCO logs. Select a PCO or CCO, and then go to the Actions menu.



- The Change template opens to show the assigned templates to your project.
- Templates for lower levels are available. For example, if you are in a PCO, templates for PCO and issue are available. When you use an issue or PCO template type at a higher level and choose to generate the document as individual documents, Change generates a separate document for each issue or PCO.

2. Move one or more templates from the Available templates column to the Selected templates column.




Use the up and down arrows to the right of the Selected templates column to change the order of the templates, if needed.

3. In the Change template details section, select the *Standard* template generation type.
4. Select one of the following in the Generate document as field:
 - **Individual documents** to get a separate document for each template you selected.
 - **Merged document (PDF only)** to merge the templates into a single PDF document.
5. If you selected Individual documents in the previous step, use the Generate document file type as field to indicate whether to download as a template file type or download as a PDF. If you selected Merged document in the previous step, skip this step.
6. Use the toggle to indicate whether to save the contract document in the Supporting documents tab.
If you choose to save in the Supporting documents tab, add the name of the document. After the document is generated, the name shows in the Title and the File/Link columns on the Supporting documents register.
7. Select the watermark text. If the organization-level settings require a document, the Select watermark stamp field is required. Also, if the organization-level settings require a watermark and the end watermark event has not occurred, the Select watermark stamp field is required. If the end watermark event has occurred, the watermark is optional.

8. Click **Next**.

9. If Change writer detects a template contact tag, processing moves to the Select contact step. If no template contact tags are detected, the Change document wizard skips this step and moves to the Review fields step.



- Select one contact from the contact list, and then click **Next**. Processing moves to the Review fields step.
- If no contacts have been configured in the project contacts, this step is disabled. You can either go back, so you can remove the templates that have template contact tags, or cancel.

10. On the Review fields step page, expand to Review templates page to see a list of all templates used. If you specified a contact, the contact name is also shown. The review dialog box lets you edit or add information to the fields that will populate the document after it is generated. Any field that is blank is not added to the document, and you cannot add information later.
11. Review the fields and enter any information in the fields that apply to your issue. When you use an issue or PCO template type at a higher level and choose to generate the document as individual documents, Change generates a separate document for each issue or PCO. When you choose to merge the document into a single PDF, the document uses the template for each issue and merges it into the single document. When you review the templates, the project name and the fields are repeated for each issue.

The <<Blankn>> tag, where *n* is a value in the range 1-15, shows in the downloaded tag list. The tag serves as a placeholder in your template where the text can be entered to appear in the fields when you review the template. When you generate the Microsoft Word document, the text is replaced with what you entered in the review. You must enter text each time you generate the Word document. If you do not enter values in the Review fields, the <<Blankn>> tag is shown in the Word document.


12. After you have reviewed all changes, you can see a preview of your document by clicking the **Preview document** button. The preview opens in a separate window with the tags filled in. If you used collection tables in any of your templates you cannot view them in the preview document. The content of the preview varies as follows:
 - If you selected Download as a PDF document when you generated the document, the preview contains all of the templates in the order you specified.
 - If you selected Download as individual documents when you generated the document, the preview contains only the template that was displayed when you clicked Preview document. You can preview other documents by selecting the file from the Review templates list and clicking preview document.
13. Click **Finish**. If you use templates from other levels, multiple completion messages are shown.
14. If you created a merged document, Change writer downloads a PDF that includes all of the templates. If you created individual documents, Change writer downloads a PDF for the selected template only.

Generate a change document using bulk template processing

You can use bulk template processing when you want to generate separate change documents in a single action. When used in conjunction with templates that contain template contact tags, you can customize a document for each specified contact.


If you want to generate customized documents, you must include a template that has template contact tags. Contacts must be assigned in the project's Assigned contacts (project > **Assigned contacts**).

1. From an issue, PCO or CCO, select the **Actions** menu drop-down list, and then select **Generate change document** from the menu. You can also find this option in the Actions menu on the PCO and CCO logs. Select a PCO or CCO, and then go to the Actions menu.



- The Change template opens to show the assigned templates to your project.
- Templates for lower levels are available. For example, if you are in a PCO, templates for PCO and issue are available. When you use an issue or PCO template type at a higher level and choose to generate the document as individual documents, Change generates a separate document for each issue or PCO.

2. Move one or more templates from the Available templates column to the Selected templates column.




Use the up and down arrows to the right of the Selected templates column to change the order of the templates, if needed.

3. In the Change template details section, select the Bulk template generation type.
4. Use the toggle to indicate whether to save the contract document in the Supporting documents tab.


If you choose to save in the Supporting documents tab, add the name of the document. After the document is generated, the name shows in the Title and the File/Link columns on the Supporting documents register.

5. Select the watermark text. If the organization-level settings require a document, the Select watermark stamp field is required. Also, if the organization-level settings require a watermark and the end watermark event has not occurred, the Select watermark stamp field is required. If the end watermark event has occurred, the watermark is optional.
6. Click **Next**.
7. If Change writer detects a template contact tag, processing moves to the Select contact step. If no template contact tags are detected, the Change document wizard skips this step and moves to the Review fields step.



- Select up to 10 contacts from the contact list, and then click **Next**. Processing moves to the Review fields step.
- If no contacts have been configured in the project contacts, this step is disabled. You can either go back, so you can remove the templates that have template contact tags, or cancel.

8. On the Review fields step page, expand to Review templates page to see a list of all templates used. If you specified contacts, the templates are listed for each contact name.



Click each template to review the information. The review dialog box lets you edit or add information to the fields that will populate the document after it is generated. Any field that is blank is not added to the document, and you cannot add information later.

9. Review the fields and enter any information in the fields that apply to your issue. When you use an issue or PCO template type at a higher level and choose to generate the document as individual documents, Change generates a separate document for each issue or PCO. When you choose to merge the document into a single PDF, the document uses the template for each issue and merges it into the single document. When you review the templates, the project name and the fields are repeated for each issue.

The <<Blankn>> tag, where n is a value in the range 1-15, shows in the downloaded tag list. The tag serves as a placeholder in your template, so text can be entered in the fields when you review the template. When you generate the Microsoft Word document, the text is replaced with what you entered in the review. You must enter text each time you generate the Word document. If you do not enter values in the Review fields, the <<Blankn>> tag is shown in the Word document.


10. After you have reviewed all changes, you can see a preview of your document by clicking the **Preview document** button. The preview opens in a separate window with the tags filled in. If you used collection tables in any of your templates you cannot view them in the preview document. The preview contains all of the templates in the order you specified.
11. Click **Finish**. If you use templates from other levels, multiple completion messages are shown. Change writer downloads a PDF that includes all of the templates.

5.11 SUPPORTING DOCUMENTS


The PCO and CCO Supporting Documents tabs let you add supporting documentation. You can upload documentation via a file, link or through InEight Document integration.

Supporting documents can be uploaded via a file or through InEight Document integration. At the PCO level, no supporting documents are required, however it is a best practice to include all documents relating to the PCO. At the CCO level, an executed change order must be attached before the CCO status can be changed to Executed.

You add supporting documents by clicking the **Add** icon on the PCO or CCO Supporting Documents tab. You have the choice of adding a new supporting document or adding a document from InEight Document.



When you choose **New supporting document**, you can add the appropriate documents as needed by filling out the Title and Document type in the Add supporting document dialog box, then browsing to your document file and attaching it. When the document is added from InEight Document, and the document type in Document matches a document type in the cloud platform, that value shows as the default document type. You can edit the document type as needed.



The screenshot shows a modal dialog box titled "Add supporting documents". It includes fields for "Title" (text input), "Document type" (dropdown menu with "Select one" option), "File/Link" (text input), and "Notes" (text area with "Type message here" placeholder and character limit "200"). A "SELECT FILE..." button is highlighted with a red box. At the bottom are "Cancel" and "Add" buttons.

When you choose From InEight Document, you are taken to the Document login window.

When you add a supporting document type of Proposal and subtype From vendor, you can select a vendor from a list of all contracts on the PCO or CCO. This lets you specify which contract the supporting document is related to and gives visibility into which contract to associate the proposal to.

5.11.0.1 Show supporting documents in generated documents

A toggle on the Supporting documents register, Show in generated document, lets you indicate whether the document is shown in a collection table based on the collection table type. When you have a supporting document that you do not want to show in a collection table in a generated document, set the toggle to *No*. When a document is generated, only the documents that were set to *Yes* are shown.

5.12 VIEW A SUPPORTING DOCUMENT

To view a supporting document, click the link in the File/Link column of the Supporting documents register. The document opens a preview in a new tab, so you can view the pages of the document and then decide if you want to download it to your workstation. You can use the **Previous** and **Next** buttons to view all pages.

Historical Weather Record					
Omaha, Nebraska, 68114, United States Of America, Lat. 41.2656, Lon. -96.0493 (UTC-06:00) Central Time (US & Canada)					
Selected Range:		Date:	Time:	Date:	Time:
From:	04/05/2023	12:30 AM	To:	04/05/2023	11:30 PM
Date	Time	Temperature	Weather condition	Wind	Precipitation
04/05/2023	12:30 AM	20°C, 67°F.	clear sky	0 m/s, 0.00 mph	
04/05/2023	01:30 AM	22°C, 71°F.	clear sky	3.6 m/s, 8.00 mph	
04/05/2023	02:30 AM	22°C, 72°F.	clear sky	6.17 m/s, 14.00 mph	
04/05/2023	03:30 AM	20°C, 68°F.	clear sky	8.75 m/s, 20.00 mph	
04/05/2023	04:30 AM	14°C, 58°F.	clear sky	11.32 m/s, 25.00 mph	
04/05/2023	05:30 AM	11°C, 51°F.	clear sky	9.26 m/s, 21.00 mph	
04/05/2023	06:30 AM	7°C, 44°F.	scattered clouds	12.88 m/s, 29.00 mph	
04/05/2023	07:30 AM	5°C, 41°F.	broken clouds	10.29 m/s, 23.00 mph	
04/05/2023	08:30 AM	4°C, 39°F.	overcast clouds	8.23 m/s, 18.00 mph	
04/05/2023	09:30 AM	3°C, 38°F.	overcast clouds	10.29 m/s, 23.00 mph	
04/05/2023	10:30 AM	3°C, 37°F.	overcast clouds	11.83 m/s, 26.00 mph	
04/05/2023	11:30 AM	2°C, 35°F.	broken clouds	10.8 m/s, 24.00 mph	
04/05/2023	12:30 PM	2°C, 35°F.	overcast clouds	8.75 m/s, 20.00 mph	
04/05/2023	01:30 PM	1°C, 34°F.	broken clouds	9.77 m/s, 22.00 mph	

To download the document to your workstation, click **Download file**.

5.13 SEND CHANGE DOCUMENTS FOR eSIGNATURE VIA DOCUSIGN

When a project is integrated with DocuSign, you can send a change document to DocuSign for an eSignature.


DocuSign tags can be embedded in the change document template. The DocuSign tags correspond to DocuSign recipients configured in the project settings and project contacts.

Send a document for eSignature

After a document has been created, you can send it for official eSignatures via DocuSign.


Documents must be in Word, Excel, or PDF format. They must be saved to the PCO or CCO supporting documents page with the document source *My computer*. You must have Edit change document permissions to send documents. Ensure that your browser's pop-up blocker is disabled before you click Send from the Contract DocuSign wizard. You must have the Send for eSignature permission to send a document for signature.

1. From the PCO or CCO Supporting documents page, select one or more documents with the document source *My computer*, and then click the **Send for signature** icon.



The Send for signature wizard opens.


2. Review the Names in the Assigned section of the wizard. If you want to add additional recipients, find their names in the Unassigned section, and then click the **Add** icon. All signees in the Assigned section have ad-hoc signee tags that can be placed on the document in DocuSign.



3. For each assigned recipient, specify in the Action column whether they need to sign the document or if they are just to receive a copy. When the value is *Needs to sign*, the recipient receives a document that is ready to sign. When the action is *Receives a copy*, the recipient receives a snapshot of the document in the signing order. For example, if the recipient marked *Receives a copy* is second in the signing order, they receive the document after those first in signing order, even though they are not signing.
4. Review the values in the Signing order column. The numbers in the column specify the order in which the recipients are sent the document for eSignature. You can assign a single number to multiple signees. The signee or signees with signing order 1 are notified first by DocuSign. After all signees in signing order 1 have signed, DocuSign notifies all signees with signing order 2, and so on.
5. Click **Next**. The Add message page opens.
6. Enter an email subject line and message to the recipients, and then click **Send**. A DocuSign window opens with the documents you chose.

If the DocuSign window does not open, ensure that your browser's pop-up blocker is disabled.

7. If your DocuSign administrator has configured Advanced Options, you can optionally expand the **Actions** menu, and then select **Advanced Options**.




You can then customize the following options:

- **Branding** – Select a logo and brand colors, that were set up by the DocuSign administrator, for the envelope.
- **Recipient privileges** – Give recipients options for how they sign the document, such as signing on paper, assigning delegates, and editing documents.
- **Reminders** – Specify whether DocuSign sends reminders to signees, when to start sending them, and how often to send them.
- **Expiration** – Set the number of days until the envelope expires and how often to send alerts.
- **Comments** – allow senders and recipients to enter comments on documents in the envelope.

Click **Save**. You are returned to the document.

8. Optionally, add additional tags for signatures, initials, and dates. All names from the Assigned section of the wizard are shown in a drop-down list in the upper left pane. Select the name of the person you want to add, and then select Signature, Initial, or Date Signed, and then click the location in the document.



9. If the document has tags for a text box, drop-down list, check box, or radio buttons, add the values to the document. Click **Send**.


The documents are routed for signature, and DocuSign sends an email message to each recipient based on the signing order. In Change, the DocuSign status column on the Supporting documents page is populated with the status of *Sent*. You can hover over the status to see the name of the person who sent the document, the status of the signatures, and the date and time the document was last modified. The Change writer automatically adds the sender to the last position of the list with the action *Receives a copy*. After it is completed, the signed document is loaded as a supporting document with a document type *Signed document*, and the sender also receives a copy.

When a supporting document has a DocuSign status of *Created*, *Completed*, or *Signed*, you can no longer edit the file link. When the status is *Sent*, you can edit the document in the original eSign envelope without incurring the expense of additional envelopes.

Edit a sent document

You must have the Correct eSignature permission to correct DocuSign documents.

1. On the Supporting documents register, hover over the ellipsis in the DocuSign status column for a sent document. The DocuSign Status dialog box is shown.




2. Click the **Correct** button. DocuSign opens with the view of the original envelope.

Make the corrections in the DocuSign envelope. Refer to DocuSign documentation for more information about envelopes.

5.14 DOCUSIGN CERTIFICATE OF COMPLETION

After signing is completed, the certificate of completion is now available when you hover over the ellipsis in the DocuSign status field in Supporting documents.

The View certificate of completion link becomes available after a document is completed. The certificate of completion is stored in Supporting documents, but it does not take up a separate entry in the Supporting documents register. The certificate does not expire in Change.



When you click **View certificate of completion**, a preview of the certificate from DocuSign opens in a new tab. You have the option to download the file if you want to store it separately.

5.15 WORKFLOW ASSIGNMENTS

Each PCO and CCO is unique and might require various levels of approval for the PCO, CCO, or supporting documents. The Workflow Assignments tab lets you to set up the proper approval steps. Workflow approvals are assigned at the organization, project, and PCO or CCO levels to allow for maximum flexibility in the approval workflow.

5.15.1 PCO and CCO workflows

Workflows configured at the organization or project level are based on value thresholds. The thresholds are absolute values. When the change order reaches a value above or below the specified threshold, a user or role must approve the change order before it can advance. For example, if the threshold is \$1000, a change of \$1000 or -\$1000 or more starts the workflow.

You can configure approval workflows for any PCO or CCO. These approval steps are first in the approval workflow. If the difference in value of the PCO or CCO is greater than absolute value workflow thresholds set at the organization or project levels, the approval steps are shown on the page. They are marked with the information icon. Any steps you add are performed before those set at the organization and project levels. When the value of the PCO or CCO is within the absolute value thresholds or if no thresholds have been set, only the steps at the PCO or CCO level are performed.

A PCO does not need to be fully approved before converting it to a CCO. When you convert a PCO that has not been fully approved to a CCO, the PCO approval status is shown in the new Approval status field in the Associations section of the CCO details. You must complete all of the PCO approval steps before you can start the CCO approval workflow. The CCO must be approved, if required, before it can be submitted for execution.

Set up a PCO or CCO approval workflow

Set up an approval workflow for a PCO or CCO when the change order requires approval by various levels of your organization before it can advance.

Steps set at the PCO or CCO level are performed before those set at the project and organization levels, respectively. If the value difference of the PCO is greater than the absolute value thresholds, the steps are shown on the Workflow approvals page, and you cannot rearrange or delete them.


1. On the record page for a PCO or CCO, select the **Workflow Assignments** tab.
2. Click the **Add approval** icon. The Add approval slide-out panel opens.
3. Enter an approval step title, and then specify the users, groups, or roles who must give their approval.
4. Click **Add**.
5. Repeat steps 3 and 4 until all approval steps are added. You can use the up and down arrows to change the order of the steps you added, if necessary. Click **Save** after rearranging the approval steps.

When the change order is ready to advance, you can start the approval workflow.

Start the approval workflow

Start the approval process when the PCO or CCO is complete and you are ready to advance to the next stage.

1. Go to the Details page for the PCO or CCO, and then click **Save and start approval**. The Start approval dialog box opens to the approval steps page.



2. Review the change approval steps.
3. Choose one of the following:

- If you do not want to add a message and attach supporting documents, click **Start**. The approval process starts.
- If you want to add a message or attach supporting documents, click **Next**. The Add messages page opens.

4. Choose one of the following:

- If you want to add a message to be included in the workflow email, type and format it, and then click **Next**. The Attach supporting documents page opens.
- If you do not want to add a message, click **Next**. The Attach supporting documents page opens.

5. Choose one of the following:

- If you want to attach supporting documents, click **Next**. The Attach supporting documents page opens.
- If you do not want to attach supporting documents, click **Start**. The approval process starts.


6. Select one or more supporting documents from the list of documents.

7. Click **Start**. The approval process starts.

The approvers receive a notification of the approval item. When you start the approval process and you are the first approver in the approval workflow, the first step of the workflow is automatically approved, and the workflow continues with the next step, if applicable. If you are the only step in the approval, you receive a second email confirming the new issue has been approved.

5.15.2 Document approval workflows

Document approval workflows are based on document type. Document approval workflows are set up at the organization and project levels. At the change order level, you can set up additional document approvals on the Document approval page of the Workflow assignments tab.



Set up a document approval workflow

Set up a document approval workflow when a document associated with change order requires approval by various levels of your organization before it can advance.

Approval steps might have been set at the organization or project levels. You cannot rearrange or delete the approval steps; you can add steps that are performed before those set at the project and organization levels.

1. On the record page for a PCO or CCO, select the **Workflow Assignments** tab, and then select the **Document approval setup** tab.
2. Click the **Add approval** icon. The Add approval slide-out panel opens.
3. Select a document type. If there are already approval steps for a document type, it is not shown in the drop-down list.

You can add steps to an existing approval by canceling this set up and then clicking **Add another step** for the document type.

4. Enter an approval step title, and then specify the users, groups, or roles who must give their approval.
5. Click **Add**.
6. Repeat steps 2 - 4 until all approval steps are added. You can use the up and down arrows to change the order of the steps you added, if necessary. Click **Save** after rearranging the approval steps.

When the change order is ready to advance, you can start the approval workflow.

Start the document approval workflow

Start the approval process when the document is complete, and you are ready to advance to the next stage.

1. Go to the Supporting documents page for the PCO or CCO, and then select one or more documents.
2. Click **Start approval**. The Start approval dialog box opens. The Start approval dialog box shows all the steps in the approval workflow for each document selected.
3. Review the change approval steps for each document. If there are group steps, you can select the group for the workflow. If you want to make changes to the approval process, click **Cancel**, and then go to the Workflow Assignments tab to make your changes. If the steps do not require changes, click **Start**. The Start approval dialog box stays open until all workflows have successfully started.

If you are an approver, you receive a notification of the approval item. Each approval workflow generates its own mail notification to the first approver. When you start the approval process and you are the first approver in the approval workflow, the first step of the workflow is automatically approved, and workflow continues with the next step, if applicable. If you are the only step in the approval, you receive a second email confirming the new issue has been approved.

When the document is in approval, you can change the supporting document title or add or change notes and other metadata. You cannot change the document type or the file link. If you want to change the file link or the document type, you must recall the document from the approval, make the changes, and then start the approval again.

You can view document approval workflow progress and history on the project Workflows > **Workflow details** page. If the workflow has been recalled, the name of the person who recalled the workflow is shown in the workflow heading.

5.16 AUDIT LOG

The Audit Log captures all changes made to issues, Potential Change Orders, and Client Change Orders. The CCM ID and Name/Description columns contain hyperlinks that if clicked will open the issue/change order for your review.

The Log shows the Value before and Value after the change and displays who made the change and when.

		NEW ISSUE	ISSUE LOG	POTENTIAL CO LOG	CLIENT CO LOG	AUDIT LOG				
Audit action no	Audit type	CCM ID	Name/Descrip...	Action	Object	Attribute	Value before	Value after	Changed by	Chan
97755	CCO	023	AH CCO 023	Manual Save	CCO	CCO status	In Review	Dropped	Paul Bennion	09/2
97755	PCO	077	IH PCO 077	Manual Save	PCO	PCO status	CCO	Dropped	Paul Bennion	09/2
97755	Issue	8	Removals	Manual Save	Issue	Issue status	CCO	Dropped	Paul Bennion	09/2
97752	CCO	PB001	Bearing Pads Re...	Manual Save	CCO	CCO status	In Review	Executed	Paul Bennion	09/2
97752	CCO	PB001	Bearing Pads Re...	Manual Save	CCO	Approved time ex...		4	Paul Bennion	09/2
97752	PCO	PB001	Bearing Pads Re...	Auto Save	PCO	PCO status	CCO	Executed	Paul Bennion	09/2
97752	Issue	21 A	PB - Bearing Pad...	Auto Save	Issue	Issue status	CCO	Executed	Paul Bennion	09/2